

1/8/77

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

P 24981
A 16428

ELLICOTT CITY
DISTRICT 4th
DATE 12/14/76

Garriott & Hiday IS PERMITTED TO INSTALL ALTER

ADDRESS Old Court Road, Woodstock, Md. 21163 PHONE 922-5571

A SEWAGE DISPOSAL SYSTEM LOCATED AT _____

SUBDIVISION _____ ROAD Duvall Road LOT _____

PROPERTY OWNER Hardin E. Ross, III

ADDRESS 28 P. O. Box 900, Columbia, Md. 21044 Phone: 730-7677

SPECIFICATIONS 4 bedrooms

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA _____ SQ. FT.

SEPTIC TANK CAPACITY 1250 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%.

OTHER DRY WELL - 480 sq. ft. absorbent sidewall area below inlet pipe. Maximum depth permitted for dry well is 11 ft. below original grade. Inlet of dry well to be 3 1/2 ft. below original grade. Place the dry well 235 ft. from edge of stream and 315 ft. from right sideline as seen when facing lot from Duvall Road.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.
PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED.

PLANS APPROVED BY Donald W. Monaghan DATE 11/11/71

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

A 16428

