

10/22/71
after 2 PM

10-22-71
Du 23

INDEXED PERMIT

P 16384
A 26134

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

DISTRICT A

DATE 10/15/71

Herman C. Sirk IS PERMITTED TO INSTALL X ALTER

ADDRESS Woodbine, Md. PHONE 489-4724

A SEWAGE DISPOSAL SYSTEM LOCATED AT _____

SUBDIVISION _____ ROAD 2375 Duane Rd. LOT _____

PROPERTY OWNER Rebecca Thomas

ADDRESS Daisy, Maryland

SPECIFICATIONS

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

SEEPAGE FITS _____ ABSORBENT SIDE WALL AREA _____ SQ. FT.

SEPTIC TANK CAPACITY 1000 GALLONS

FOR GARRAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%.

OTHER Dry Well - 300 sq. ft. absorbent sidewall area below inlet pipe. Inlet 3 1/2 ft. below orig. grade. Max. depth permitted for dry well is 11 ft. below orig. grade. Locate dry well about 95 ft. from back of house and about 36 ft. from left lot line as seen when facing lot from Duwall Rd. All pipe must be heavy duty cast iron from house to tank and tank to dry well. Joints must be leaded with 75 ft. radius of well.

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON.
PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL.

PLANS APPROVED BY D. W. Monaghan DATE 9/1/71

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

A 16134

