

4/3/01  
4/13/01 3pm  
4/4/01  
unclassified

01-55-110-0

# PERMIT

**SEWAGE DISPOSAL SYSTEM**  
HOWARD COUNTY HEALTH DEPARTMENT  
BUREAU OF ENVIRONMENTAL HEALTH  
410-313-2640

P 514974  
A 56478-D  
ISSUE DATE 3/12/01  
APPROVAL DATE 4/4/01

INDEXED

Whitworth Excavating IS PERMITTED TO INSTALL  ALTER

ADDRESS 12680 Clarksville Pike, Clarksville, MD 21029 PHONE 410-531-5033

SUBDIVISION DiPaula Property LOT NUMBER 4 ADDRESS 1420 Florence Road

PROPERTY OWNER Catoctin Homes, Inc. PROPERTY OWNER'S ADDRESS P.O. Box 512, EC 21041

SEPTIC TANK CAPACITY 1250 GALLONS \* WATERTIGHT SEPTIC TANK REQUIRED AS PER

PUMP CHAMBER CAPACITY N/A GALLONS STANDARD REQUIREMENTS \*

NUMBER OF BEDROOMS 4

SQUARE FEET PER BEDROOM 180

LINEAR FEET OF TRENCH REQUIRED 240

TRENCHES: Trenches to be 3 feet wide. Inlet 2 feet below original grade. Bottom maximum depth  
4 feet below original grade. 2 feet of stone below distribution box.

LOCATION: Starting at the lot corner at the end of the driveway, place the distribution  
box 150 feet down the 359.01' lot line and 90 feet off this same lot line. Run  
(3) 80' trenches toward the 359.01' lot line.

PLANS APPROVED Mark Rifkin, R.S. OK SRK 12/21/00 DATE 12/14/2000

PERMIT VOID AFTER 2 YEARS

BLDG. PERMIT SIGNED  
AND RETURNED 7/11/2001  
B00131444  
DECK

NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS

NOTE: TOP OF SEPTIC TANKS ARE TO BE NO DEEPER THAN 3.0 FEET BELOW FINISH GRADE

NOTE: WATERTIGHT SEPTIC TANKS REQUIRED

NOTE: CLEANOUT REQUIRED EVERY 70 FEET OF SEWER LINE AND/OR AT 90° SWEEPS IN LINES FROM HOUSE TO DRAIN FIELDS, 90° ELBOWS ARE NOT ACCEPTABLE

NOTE: ALL PARTS OF SEPTIC SYSTEMS (I.E. TANK, DISTRIBUTION BOX, DRAINFIELDS) TO BE 100 FEET FROM ANY WATER WELL UNLESS OTHERWISE SPECIFICALLY AUTHORIZED

NOTE: NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH UNLESS SPECIFICALLY AUTHORIZED

BLDG. PERMIT SIGNED  
AND RETURNED 6/20/2001  
B00130725  
PROPANE TANK

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 35/40 PVC OR ABS

NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

NOTE: DISTRIBUTION BOXES MUST HAVE BAFFLES

NOTE: IF PUMPED SEPTIC SYSTEM REQUIRED, (1) SEPTIC PUMP DETAIL TO BE PROVIDED BY INSTALLER PRIOR TO ISSUANCE OF SEPTIC PERMIT (2) PUMP PERFORMANCE TEST IS NECESSARY PRIOR TO HEALTH DEPARTMENT APPROVAL OF SEPTIC PERMIT

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE  
SUCCESSFUL OPERATION OF ANY SYSTEM  
PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT  
CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM

0514974

