

SEPTIC SYSTEM TO BE INSTALLED
FIRST REFC. BUILDING
PERMIT IS SIGNED

PERMIT

P 25519
A 25267

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

DISTRICT 4th

DATE 3/28/77

4/9/77
8/9/77 - applied F.S.

INDEXED

Jack Fyock

IS PERMITTED TO INSTALL ALTER

ADDRESS 13775 Triadelphia Road, Glenelg, Md.

PHONE 988-9270

A SEWAGE DISPOSAL SYSTEM LOCATED AT

from Co. line west on Forsythe Rd past Hugg Thomas Refuge to top of hill 1st full on left

SUBDIVISION _____ ROAD Forsythe Road

LOT _____ 5.0 Acres

PROPERTY OWNER Henry L. & Phyllis McRobie

ADDRESS 614 Aldershot Road, Catonsville, Md. 21228

SPECIFICATIONS 3 bedrooms

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA _____ SQ. FT. BLDG. PERMIT SIGNED

SEPTIC TANK CAPACITY 1000 GALLONS

AND RETURNED 5/2/77
Serial No. 30494

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%.

OTHER DRY WELL to have a total of 375 sq. feet effective sidewall absorbent area *below*
~~before~~ the first 4 1/2 feet of non absorbent soil at original grade. Inlet to
dry well to be absolutely no deeper than 3 feet below original grade. Maximum
depth of dry well to be 11 feet below original grade. Locate dry well 200 feet
from the front lot line (Forsythe Road) and 155 feet from the right lot line
as seen when facing lot from Forsythe Road.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON. PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK. STAND PIPES MUST BE 6 INCHES IN DIAMETER.

PLANS APPROVED BY William W. Zepp DATE 3/15/77

CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED.

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

*Van Sant fax
301-831-
0233*

25267

