

4/12/01
1:00

04-357949

ISSUE DATE: 5/30/2001

P515266

APPROVAL DATE: 7/10/01

PERMIT INDEXED

A 49889-C

7/9/01
Final
2:30

7/10/01
Final
AM

ON-SITE SEWAGE DISPOSAL SYSTEM HOWARD COUNTY HEALTH DEPARTMENT BUREAU OF ENVIRONMENTAL HEALTH

South Carroll Backhoe, Inc IS PERMITTED TO INSTALL ALTER

ADDRESS: 4410 Salem Bottom Road, 21157 PHONE NUMBER: 410-875-4197

SUBDIVISION: Harless Manor II LOT NUMBER: 30

ADDRESS: 14021 Monticello Drive PROPERTY OWNER: Andy Ahn

SEPTIC TANK CAPACITY (GALLONS): 1250 (TOP SEAM) (410)-977-4959

PUMP CHAMBER CAPACITY (GALLONS): N/A 1250 (TOP SEAM)

NUMBER OF BEDROOMS: 4

SQUARE FEET PER BEDROOM: 180

LINEAR FEET OF TRENCH REQUIRED: 240

TRENCHES:	Trench to be 3.0 feet wide. Inlet ^{2.5} 2.0 feet below original grade. Bottom maximum depth 4.0 feet below original grade. Effective area begins at 2.0 feet below original grade. 2.0 feet of stone below distribution pipe.
LOCATION:	Place distribution box 100 feet from the left (218.00') lot line and 40 feet from the front lot line as viewed from Monticello Drive. Install trenches on contour in both directions away from the distribution box.
NOTES:	INSTALL TRENCHES 10' APART CENTER-TO-CENTER.

PLANS APPROVED: Mark Rifkin OK SRK 4/12/01 DATE: 4-2-01

- NOTE: PERMIT VOID AFTER 2 YEARS
- NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS
- NOTE: WATERTIGHT SEPTIC TANKS REQUIRED
- NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM

**BUILDING PERMIT SIGNED
AND RETURNED** 4-24-01
BOO 135710 - DECK W/STEPS

P515266

