

7/31/01
Layout
11:00

8/29/01
Anytime
WPS

ISSUE DATE: 7/24/2001

APPROVAL DATE: 10/16/01

PERMIT INDEXED

P 515953-C

A 59915-K

ON-SITE SEWAGE DISPOSAL SYSTEM HOWARD COUNTY HEALTH DEPARTMENT BUREAU OF ENVIRONMENTAL HEALTH

04-363515

Fogles Septic Clean, Inc IS PERMITTED TO INSTALL ALTER

ADDRESS: 580 Obrecht Road, Sykesville PHONE NUMBER: 410-795-5670

SUBDIVISION: Monticello LOT NUMBER: 9

ADDRESS: 1738 Oakdale Drive PROPERTY OWNER: D.R. Horton

SEPTIC TANK CAPACITY (GALLONS): 1250
PUMP CHAMBER CAPACITY (GALLONS): N/A
NUMBER OF BEDROOMS: 4
SQUARE FEET PER BEDROOM: 180
LINEAR FEET OF TRENCH REQUIRED: 240

**BUILDING PERMIT SIGNED
AND RETURNED**
6-18-03 BDD 14244-DECK

| | |
|-----------|--|
| TRENCHES: | Trench to be 3.0 feet wide. Inlet <u>3</u> feet below original grade. Bottom maximum depth <u>5.0</u> feet below original grade. Effective area begins at 4.5 feet below original grade. <u>2</u> feet of stone below distribution pipe. |
| LOCATION: | Begin trenches 125 feet up the right lot line and 135 feet off that same lot line as seen when facing the lot from Oakdale Drive. Run trenches on contour in both directions. |
| NOTES: | |

PLANS APPROVED: Amy Mc Millen 5/22/01 OK (BB) DATE: 5-11-01

- NOTE: PERMIT VOID AFTER 2 YEARS
- NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS
- NOTE: WATERTIGHT SEPTIC TANKS REQUIRED
- NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS
RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM
PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT
CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM**

P 515953-C

