

PUBLIC SEWER STATUS VERIFIED BY

ISSUE DATE: 6/16/2011

APPROVAL DATE: 6/23/11

# PERMIT

P 535201

A REPAIR

## Septic Repair ON-SITE SEWAGE DISPOSAL SYSTEM HOWARD COUNTY HEALTH DEPARTMENT BUREAU OF ENVIRONMENTAL HEALTH

South Carroll Backhoe IS PERMITTED TO INSTALL  ALTER

ADDRESS: 4410 Salem Bottom Rd., Westminster MD PHONE NUMBER: 410-875-4197

SUBDIVISION: \_\_\_\_\_ LOT NUMBER: \_\_\_\_\_

ADDRESS: 16400 Old Frederick Road PROPERTY OWNER: Larry Duva

SEPTIC TANK CAPACITY (GALLONS): 1500

PUMP CHAMBER CAPACITY (GALLONS): n/a

NUMBER OF BEDROOMS: 4

SQUARE FEET OF HOUSE: \_\_\_\_\_

LINEAR FEET OF TRENCH REQUIRED: 150

TRENCHES:	Trenches to be <u>2</u> feet wide. Inlet <u>3</u> feet below original grade. Bottom maximum depth <u>6</u> feet below grade. Effective area begins at <u>3</u> feet below original grade with <u>3</u> feet of stone below distribution pipe.
LOCATION:	Install new s.t. 20' from proposed addition. Set d box near perc hole B and run 2x75' trenches on contour towards right property line.
NOTES:	<b>System is sized for 5 BR per homeowner.</b> Proposed addition should be staked prior to setting new S.T. Pump and collapse old septic tank and drywell. Obs. Pipes required on both trenches.

PLANS APPROVED: K. Wolf DATE: 6/16/2011

NOTE: PERMIT VOID AFTER 2 YEARS

NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS

NOTE: WATERTIGHT SEPTIC TANKS REQUIRED

NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL

NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

NOTE: AN ELECTRICAL PERMIT IS REQUIRED FOR INSTALLATION OF ANY ELECTRICAL COMPONENTS OF THE SYSTEM

**NEITHER THE HOWARD COUNTY COUNCIL OR THE HEALTH DEPARTMENT IS  
RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM  
PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT  
CALL 410-313-1771 FOR INSPECTION OF SEPTIC SYSTEM**





Howard County  
Health Department

7178 Columbia Gateway Drive, Columbia MD 21046  
(410) 313-2640 Fax (410) 313-2648  
TDD (410) 313-2323 Toll Free 1-866-313-6300  
website: [www.hchealth.org](http://www.hchealth.org)

Peter L. Beilenson, M.D., M.P.H., Health Officer

**INFORMATION FORM – SEPTIC SYSTEM REPAIR / UPGRADE**

**Reason for Request:**

- A. Failing System (includes surface discharge or inadequate treatment zone)

Has the contractor verified through excavation/pumping evaluation that there are no pipe blockages?

- B. System relocation for proposed addition for setback compliance \*
- C. To replace a collapsed septic tank
- D. To replace a collapsed drywell

\_\_\_\_\_   
 \_\_\_\_\_

**\*\*For REPAIRS, are the owners proposing, or do they plan to add in the future, any additions or modifications to the property, i.e. pools, living space additions, garages etc? This information must be disclosed at the time of this application. The Health Department will not be able to accommodate requests in the field for property modifications unrelated to the repair request. Such requests may require an additional fee, additional testing, and submittal of a Percolation Certification Plan, if the property does not meet current Code and Regulation.**

Septic Contractor:  
Contractor's Address:

South Carroll Backhoe  
4419 Salem Bottom Rd  
Westminster MD 21157  
410-875-4197  
16900 Old Frederick Rd

Contactors Phone #:  
Property Address:  
Property (Subdivision) & Lot #:  
County file #, if known:

Owner's Name and Phone #:

Larry DUNA 443-822-3186

Is public sewer available/nearby:

If public sewer may be close, mention further research will be performed to verify availability

Names of any previous owners:

Year House Built:

# of Existing Bedrooms:

# of Bedrooms after completion of addition:

Has this request been discussed previously with another Sanitarian: \_\_\_\_\_ Name: \_\_\_\_\_

\* Needs tank  
relocated for  
addition but  
drywell is also  
failing. Need  
full system  
upgrade.

A Sanitarian will be in contact within three business days depending upon the urgency of the situation to coordinate the scheduling/review of the repair or upgrade.

Print out a copy of the Real Property Data via Dept. of Taxation website \_\_\_\_\_ Indexed file found \_\_\_\_\_

**\*Prior to scheduling inspections, scaled plans should be submitted to clarify the nature of the addition.**

If public sewer may be nearby, verify whether the sewer is technically "available" ( defined as abutting or within the property), through the Bureau of Engineering (x2414).

If sewer is available, verify whether the property is within the Metropolitan District (Finance x2061).

If sewer is available, and property is within the Metropolitan District, connection to sewer is required. If owner believes reasons for exemptions exist, owner should justify request in writing.

If soil/site conditions are limiting and sewer and/or Metro District status not conducive to connection, Sanitarian may recommend pursuit of Emergency Sewer Extension or Emergency Metro District Inclusion. Owner should contact Charlotte Dryden, x4419, for further detail.

No permit is to be issued nor inspection to be scheduled without prior fee collection at the office unless an emergency situation exists. Contractor is to notify office of the emergency situation as soon as possible.