

PERMIT

P 514986

SEWAGE DISPOSAL SYSTEM
HOWARD COUNTY HEALTH DEPARTMENT
BUREAU OF ENVIRONMENTAL HEALTH
410-313-2640

A 38965

ISSUE DATE 3/21/2001

APPROVAL DATE 5/7/01

South Carroll Backhoe, Inc. IS PERMITTED TO INSTALL x ALTER

ADDRESS 4410 Salem Bottom Road, Westminster, MD 21157 PHONE 410-875-4197

SUBDIVISION LOT NUMBER ADDRESS 13753 Old Rover Road

PROPERTY OWNER Gary Winkler PROPERTY OWNER'S ADDRESS 7608 Greendell Lane

SEPTIC TANK CAPACITY 1250 GALLONS * WATERTIGHT SEPTIC TANK REQUIRED *

PUMP CHAMBER CAPACITY N/A GALLONS

NUMBER OF BEDROOMS 5 as of 4/18/02 per BP application

SQUARE FEET PER BEDROOM 240

LINEAR FEET OF TRENCH REQUIRED 240 (240-275')

TRENCHES: Trenches to be 2 feet wide. Inlet 4 1/2 feet below original grade. Bottom maximum depth 8 1/2 feet below original grade. 4 feet of stone below distribution box pipe

LOCATION: Place the distribution box 200 feet from the front lot line and 75 feet from the left lot line. Run (2) 120' trenches along contour toward front of lot.

12/26/00 OK (BB)

4/10/01 - SPECS CHANGED TO ALLOW GRAVITY FLOW (MR)

4/12/01 - SPECS CHANGED BY DKC TO ACCOMADATE DEEPER INLET (DKC) SRK

4/18/01 - SPECS CHANGED TO ACCOMADATE UNEXPECTED ROCK IN TRENCH (D) SRK

PLANS APPROVED Mark Rifkin, R.S. DATE 12/27/2000

PERMIT VOID AFTER 2 YEARS

BUILDING PERMIT SIGNED 800135588

AND RETURNED 4/18/02 - FINISH ATTIC

NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS

NOTE: TOP OF SEPTIC TANKS ARE TO BE NO DEEPER THAN 3.0 FEET BELOW FINISH GRADE

NOTE: WATERTIGHT SEPTIC TANKS REQUIRED

NOTE: CLEANOUT REQUIRED EVERY 70 FEET OF SEWER LINE AND/OR AT 90° SWEEPS IN LINES FROM HOUSE TO DRAIN FIELDS, 90° ELBOWS ARE NOT ACCEPTABLE

NOTE: ALL PARTS OF SEPTIC SYSTEMS (I.E. TANK, DISTRIBUTION BOX, DRAINFIELDS) TO BE 100 FEET FROM ANY WATER WELL UNLESS OTHERWISE SPECIFICALLY AUTHORIZED

NOTE: NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH UNLESS SPECIFICALLY AUTHORIZED

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 35/40 PVC OR ABS

NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

NOTE: DISTRIBUTION BOXES MUST HAVE BAFFLES

NOTE: IF PUMPED SEPTIC SYSTEM REQUIRED, (1) SEPTIC PUMP DETAIL TO BE PROVIDED BY INSTALLER PRIOR TO ISSUANCE OF SEPTIC PERMIT (2) PUMP PERFORMANCE TEST IS NECESSARY PRIOR TO HEALTH DEPARTMENT APPROVAL OF SEPTIC PERMIT

BUILDING PERMIT SIGNED

AND RETURNED

3/20/02 - 800158832 - AG POOL

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM

P514986

3/30/01 Layout
4/9/01 - Layout 1:00 Canceled
4/10/01 - 10:30
4/12/01 1:00
4/18/01 - 12pm

04-316452

INDEXED

