

7/2/75
or 7/3/75

Kulu
P 21633
A 16196

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLCOTT CITY

DISTRICT 4

DATE 6/9/75

INDEXED

Mrs. Carmen Galindo IS PERMITTED TO INSTALL ALTER

ADDRESS 2045 Duvall Road, Woodbine, Md. PHONE 774-2297

A SEWAGE DISPOSAL SYSTEM LOCATED AT _____

SUBDIVISION _____ ROAD Route 144 (see application for better directions) LOT _____

PROPERTY OWNER Mrs. Carmen Galindo

ADDRESS _____

SPECIFICATIONS - 3 bedrooms

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA _____ SQ. FT.

SEPTIC TANK CAPACITY 1,000 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%.

OTHER Dry well - 480 sq. ft. sidewall area below the inlet.
Place the dry well 277 ft. from the front lot line and 133 ft. from the right side of the lot as seen when facing the lot from Route 144. Inlet of dry well to be no deeper than 4 ft.

and bottom of dry well to be no deeper than 12 ft.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.
PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. CLEANOUTS MUST BE 6" DIA. IN CONCRETE,

PLANS APPROVED BY Raymond Hodges DATE 9/2/71

CAST IRON OR TERRA COTTA ACCEPTED.
FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

BLDG. PERMIT SIGNED
AND RETURNED 4/7/82
Serial # 9573
Mr. Kaku for equipment

A
16196

