

APPLICATION

FOR PERCOLATION TESTING AND SITE EVALUATION

TEST DATE(S) _____ TEST TIME _____

APR 5 2008
DATE 2/3/06

AGENCY REVIEW: _____

DO NOT WRITE ABOVE THIS LINE

I HEREBY APPLY FOR THE NECESSARY TESTING/EVALUATION PRIOR TO ISSUANCE OF SEWAGE DISPOSAL SYSTEM PERMIT(S) TO:

CHECK AS NEEDED:

- CONSTRUCT NEW SEPTIC SYSTEM(S)
- REPAIR/ADD TO AN EXISTING SEPTIC SYSTEM
- REPLACE AN EXISTING SEPTIC SYSTEM

CHECK AS NEEDED:

- NEW STRUCTURE(S)
- ADDITION TO AN EXISTING STRUCTURE
- REPLACE AN EXISTING STRUCTURE

CHECK ONE:

- CREATE NEW LOT(S)
- BUILD ON AN EXISTING LOT IN A SUBDIVISION
- BUILD ON AN EXISTING PARCEL OF RECORD

IS THE PROPERTY WITHIN 2500' OF ANY RESERVOIR?

- YES
- NO

THE TYPE OF STRUCTURE IS:

- RESIDENTIAL WITH _____ PROPOSED BEDROOMS IN THE COMPLETED STRUCTURE (NOTE *UNKNOWN* IF APPROPRIATE)
- COMMERCIAL (PROVIDE DETAIL OF NUMBERS AND TYPES OF EMPLOYEES/ CUSTOMERS ON ACCOMPANYING PLAN)
- INSTITUTIONAL/GOVERNMENT (PROVIDE DETAIL OF NUMBERS AND TYPES OF EMPLOYEES/USERS ON ACCOMPANYING PLAN)

PROPERTY OWNER(S) HOLLY HOUSE DEVELOPMENT LLC

DAYTIME PHONE 410-531-8930 EXT 27 CELL _____ FAX 410-531-8939

MAILING ADDRESS 14045 GARED DR. GLENWOOD MD. 21738
STREET CITY/TOWN STATE ZIP

APPLICANT SAME AS OWNER

DAYTIME PHONE _____ CELL _____ FAX _____

MAILING ADDRESS _____
STREET CITY/TOWN STATE ZIP

APPLICANT'S ROLE: DEVELOPER BUILDER BUYER RELATIVE/FRIEND REALTOR CONSULTANT

PROPERTY LOCATION
SUBDIVISION/PROPERTY NAME 12402 LIME KILN ROAD LOT NO. 4

PROPERTY ADDRESS 12402 LIME KILN ROAD FULTON, MD. 20759
STREET TOWN/POST OFFICE

TAX MAP PAGE(S) 45 GRID 6 PARCEL(S) 24 PROPOSED LOT SIZE 4


AS APPLICANT, I UNDERSTAND THE FOLLOWING: THE SYSTEM INSTALLED SUBSEQUENT TO THIS APPLICATION IS ACCEPTABLE ONLY UNTIL PUBLIC SEWERAGE IS AVAILABLE. THIS APPLICATION IS COMPLETE WHEN ALL APPLICABLE FEES AND A SUITABLE SITE PLAN HAVE BEEN RECEIVED. I ACCEPT THE RESPONSIBILITY FOR COMPLIANCE WITH ALL M.O.S.H.A. AND "MISS UTILITY" REQUIREMENTS. APPROVAL IS BASED UPON SATISFACTORY REVIEW OF A PERC CERTIFICATION PLAN.

TEST RESULTS WILL BE MAILED TO APPLICANT.

SIGNATURE OF APPLICANT

HOWARD COUNTY HEALTH DEPARTMENT, BUREAU OF ENVIRONMENTAL HEALTH, WELL AND SEPTIC PROGRAM
3525-H ELLICOTT MILLS DRIVE, ELLICOTT CITY, MARYLAND 21043-4544 (410) 313-1771 FAX (410) 313-2648
TDD (410) 313-2323 TOLL FREE 1-877-4MD-DHMH

AP Lot #3



113A
dark brown L sbk
~5" uphill downhill
weak red dense sil / weak red sil
2.5" reddish yellow sil sg micasious
~5-8% saprolite gravel

116
dark brown L sbk
brownish yellow sil cw m
2.5" reddish yellow / light red brown dense sil micasious cw sg
5" light red brown sil micasious cw saprolite

12' 5% gravel cobble 45% quartz

117
dark brown L sbk
1" red sil m cw micasious
4.5" light red brown sil sg micasious cw saprolite
12'

115
1" feel
1" brown L
1" reddish yellow sil m cw
5' reddish yellow sil sg micasious 25% gravel
12'

114
dark brown L sbk
1" reddish yellow sil m micasious
6' brownish yellow sil cw sg micasious 45% gravel
12'

| DATE | TEST # | DEPTH | START | BREAK 1" DROP | STOP 2" DROP | TIME OF 2nd INCH | P/F/H |
|---------|--------|--------------|---------------------|---------------------|---------------------|------------------|-------|
| 2/22/06 | 113A | 4'8" / 12'8" | 12:40 ³⁴ | 12:41 ⁵⁰ | 12:47 ²⁹ | 3 | P |
| | 114 | 6' / 12' | 1:19 ⁰⁸ | 1:32 ¹⁸ | 1:49 ³⁰ | 17 | P |
| | 115 | 12' | | visual | | ok | P |
| | 117 | 12' | | visual | | ok | P |
| | 116 | 5' / 12' | 12:55 ⁰³ | 1:08 ³³ | 1:32 | — | F |
| | 116 | 6' | 1:08 | 1:09 ⁴¹ | 1:12 | 3 | P |

REMARKS Holes dug per plan = all soils consistent
 SANITARIAN SF BACKHOE Fogles OTHERS B. Sheesley
 TEST HOLES USED IN SDA _____ AVG. PERC TIME 8 SQ. FT/BR
 TRENCH WIDTH _____ INLET DEPTH _____ MAX. BOT DEPTH _____ EFFECTIVE SW _____
 # 116 effective area 5.5'

OWN PARCEL A
KILN RD
12/2/42
RR-DEO

URE
TION

E

PT105
411.0

EX. WELL TO
REMAIN AND BE
BROUGHT INTO
COMPLIANCE WITH
CURRENT CODE

LOCATION OF
PROPOSED
SWM FACILITY

PROP. 25' 1/2 R.O.W.

PT119b
420.2

PT116
428.4

PT117
428.3

427.4
PT115

PT113a
425.8

PT114
428.3

PT111
422.2

PT112
427.0

PT110
421.4

424.5
PT113

419.8
PT107

PT106a
422.4

PT108
415.0

PT106
416.8

PT104a
397.2

PT103
397.8

PT103
392.7

PT101
391.0

PT102
396.9

PT104a
397.2

PT103
397.8

PT103
392.7

PT101
391.0

PT102
396.9

4

5

6

3

7

2

8

9

PT152
430.9

416.6
PT127

410.2
PT131

EX. G
REMO

3' PR
RELOC
@ 30'

EX. PERGOLA TO

3 PROPOSED W
RELOCATION AR
@ 50' O.C., TYF

EX. SRA TO BE
PER HEALTH DE
SPECIFICATIONS

EX. HOUSES TO

BIORDI RUDO
BIORDI SUSAN
MAP 45, GRID 6,
12202 LINE &
L.F. 1584/
ZONE RR-

100' BUFFER FOR
EXISTING HILL ON
BIORDI PROPERTY
MAP 26 PARCEL, 26

EX. SRA TO BE
ABANDONED ACCORDING
TO HEALTH DEPT.
PROCEDURE

EX. GARAGE TO
BE REMOVED
PARCEL 'A' TO
BE CONVEYED
TO THE OWNER
OF PARCEL 23,
DEVOID OF
DEVELOPMENT
DENSITY

NON-BUILDABLE
PRESERVATION
PARCEL 'B'

Approved per cert
5/21/07

HOLLY MANOR WAY

HOLLY MANOR WAY

GIB2
MIC2

GIB2
MIC2

MIC2
303

EX
HO

N76°55'03"W 153.73'
S67°45'57"W 243.93'