

4/11/84
4/12/84
4/13/84
early
approved
2/5/85
S. Target (CW)

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH*

P 33590
A 32636

HOWARD COUNTY
BUREAU OF ENVIRONMENTAL HEALTH
992-2330

ELLICOTT CITY
DISTRICT 5th.
DATE 2/23/84

INDEXED

L. & F. Company, Inc. IS PERMITTED TO INSTALL X ALTER _____

ADDRESS _____ PHONE _____

SUBDIVISION _____ ROAD 6910 Haviland Mill LOT _____

PROPERTY OWNER Dennis & Anne Hofmann PHONE: 490-0270

ADDRESS 9630 Tower Drive
Laurel, Maryland 20707

IF GARBAGE GRINDER IS USED INCREASE SEPTIC TANK CAPACITY BY 50% AND ABSORPTION AREA BY 22%.

GARBAGE GRINDER? YES _____ NO X

SEPTIC TANK CAPACITY 1500 GALLONS NUMBER OF BEDROOMS 4

TRENCHES - 158 sq. ft. absorbent area per bedroom. Trench to be 2 ft. wide, Inlet 2 1/2 feet below original grade. Bottom maximum depth at 2 1/2 feet below original grade, with 3 1/2 feet of stone below distribution pipe. LOCATION: Start the trench at the high perc hole located 255 ft. from the front lot line and 65 feet from the right lot line as seen when facing the lot from Haviland Mill Road. Run the trench towards the left side of the lot as seen when facing the lot from Haviland Mill Road. NOTE: No trench to exceed 100 feet in length. If more than one trench used, a distribution box is required. Trenches to be installed on level ground. Provide 6"-8" diameter cleanout and cap to grade or above on septic tank and drywell. If a garbage disposal is used, increase septic tank capacity by 50% and increase absorbant sidewall area by 22%.

PLANS APPROVED BY Frank Skinner/Raymond Hodges DATE 7/12/83/8/10/83

- COVER NO WORK UNTIL INSPECTED AND APPROVED.
- NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.
- NOTE: IF TRENCH IS USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH.
- NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER. NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH.
- NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 40 PVC OR ABS.
- PERMIT VOID AFTER THREE YEARS.
- NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA, OR PVC OR ABS ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET MANHOLE TO GRADE REQUIRED.

*INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT

A 32636

