

02-207125

file complete - app
6/12/74
MSV

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

INDEXED

DISTRICT 2

DATE 5/28/74

P 20044
A 17384

Jenkins Brothers IS PERMITTED TO INSTALL ALTER

ADDRESS Wallas Park, Ellicott City, Md. PHONE 465-6646

A SEWAGE DISPOSAL SYSTEM LOCATED AT _____

SUBDIVISION _____ ROAD Sunset Farm Rd. (see application for better directions) LOT _____

PROPERTY OWNER Thomas J. Enaley

ADDRESS _____

SPECIFICATIONS - 3 bedrooms

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA _____ SQ. FT.

SEPTIC TANK CAPACITY 1,000 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%

OTHER Dry well - 300 sq. ft. sidewall area below the inlet. Dry well inlet to be 3 ft. below grade and dry well bottom to be no deeper than 13 ft. Place the dry well 150 ft. from the left side of the lot as seen when facing the lot from Sunset Farm Road and 30 ft. from the front lot line.

NOTE: ALL PIPE FROM HOUSE TO DRY WELL MUST BE CAST IRON.
PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL.

PLANS APPROVED BY Raymond Hodges DATE 8/10/73


FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

A 17384

DATE SYSTEM APPROVED _____ INSPECTOR _____

Help Me	Map Reset	Zoom Fit	Find Location	Remove Pin	Layer Control	Image Control	Theme Map	Local Print	Print Layout	Email Map	Map Exit



Disclaimer: Howard County, Maryland assumes no responsibility for the accuracy of this map or the information contained herein or derived therefrom. The buyer and/or user assumes all risks and liabilities whatsoever resulting from or arising out of the use of this map. There are no oral agreements or warranties relating to this sale and/or use of this map.

Thursday, February 23 2006 | 12:38:18 PM | @776

Map Legends

County Line	Property Line	Stream Major	Stream Minor	Ponds Lakes	Tree Lines	Wetlands	Fences	Railroad
House Driveway	Contour Lines 400	Contour Lines 401	Spot Elev. 401	Road Paving	Bridges Over Pass	Electric ROW & Tower		

Property Information

Property Boundary

Sanitary Sewer