

LAYOUT 7/21/04 9:30 INSP 4 \_\_\_\_\_  
 INSP 2 7/22/04 PM INSP 5 \_\_\_\_\_  
 INSP 3 7/23/04 AM INSP 6 \_\_\_\_\_

ISSUE DATE: 7/14/04

APPROVAL DATE: 7/23/04

**PERMIT  
INDEXED**

P 520779  
 REPAIR  
 A 517418-A

**ON-SITE SEWAGE DISPOSAL SYSTEM  
 HOWARD COUNTY HEALTH DEPARTMENT  
 BUREAU OF ENVIRONMENTAL HEALTH  
 03 - 303365**

EDWARD LINSENMAYER P+H IS PERMITTED TO INSTALL  ALTER

ADDRESS: 9304 MIGAN RD, RANDALLSTOWN PHONE NUMBER: 410-992-8172

SUBDIVISION: BREEZEWOOD FARMS (SEC 4) LOT NUMBER: 19

ADDRESS: 10648 BREEZEWOOD DRIVE PROPERTY OWNER: MASON HURD

SEPTIC TANK CAPACITY (GALLONS): \_\_\_\_\_ OUTLET BAFFLE FILTER REQUIRED

PUMP CHAMBER CAPACITY (GALLONS): \_\_\_\_\_ COMPARTMENTED TANK REQUIRED

NUMBER OF BEDROOMS: 4 Repair Put in On Side of House, Well Downhill of Existing System

SQUARE FEET PER BEDROOM: \_\_\_\_\_

LINEAR FEET OF TRENCH REQUIRED: As Much as Will Fit In Area

TRENCHES:	Trench to be _____ feet wide. Inlet _____ feet below original grade. Bottom maximum depth _____ feet below original grade. Effective area begins at _____ feet below original grade. _____ feet of stone below distribution pipe.
LOCATION:	<b>BUILDING PERMIT SIGNED AND RETURNED</b>
NOTES:	<u>8/15/2002 B 00137996 INGROUND POOL</u>

PLANS APPROVED: \_\_\_\_\_ DATE: \_\_\_\_\_

- NOTE: PERMIT VOID AFTER 2 YEARS
- NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS
- NOTE: WATERTIGHT SEPTIC TANKS REQUIRED
- NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS UNLESS SPECIFICALLY AUTHORIZED

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM**

A517418-A



# PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

*11/13/77 inspect house & sewer connections*

ELLICOTT CITY

DISTRICT 3rd

DATE 8/31/76

**INDEXED**

William Hopkins

IS PERMITTED TO INSTALL  ALTER

Address Jennings Chapel Road, Woodbine, Md, 21797

PHONE 482-4711

A SEWAGE DISPOSAL SYSTEM LOCATED AT \_\_\_\_\_

SUBDIVISION Breezewood Farms

ROAD Breezewood Drive

LOT 19 ~~18~~ Sec. 4

PROPERTY OWNER James P. Bowlin

ADDRESS 2602 Annapolis Road, Severn, Md. 21144

SPECIFICATIONS 3 bedrooms

*B. MOORE FIELD CHANGED LOT #*

DRAIN FIELD \_\_\_\_\_ DEPTH \_\_\_\_\_ FEET, BOTTOM AREA \_\_\_\_\_ SQ. FT.

SEEPAGE PITS \_\_\_\_\_ ABSORBENT SIDE-WALL AREA \_\_\_\_\_ SQ. FT.

SEPTIC TANK CAPACITY 1250 ~~1000~~ GALLONS

*where spec are for lot 2*

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 25% & TANK CAPACITY 50%.

OTHER DRY WELL - 360 sq. ft. sidewall area below inlet (3 bedrooms), and 480 sq. ft. sidewall area below inlet (4 bedrooms). Dry Well inlet to be 4 ft. deep below original grade and bottom of dry well to be 11 ft. deep below original grade. Place Dry Well 125 ft. from the front lot line and 20 ft. from the left side of the lot as seen when facing the lot from Breezewood Drive. Lot is also suitable for deep ditches.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED.

PLANS APPROVED BY Raymond Hodges

DATE 12/22/75

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

*A 17984*