

2-348
1/21/83

7/15/83
Approved
5 Aug

P-37489
A-22823

PERMIT

SEWAGE DISPOSAL SYSTEM
MARYLAND STATE DEPARTMENT OF HEALTH*

HOWARD COUNTY
BUREAU OF ENVIRONMENTAL HEALTH
ZIMMERMAN
461-9933

ELICOTT CITY
DISTRICT 416
DATE 7/21/83

INDEXED

{ = C.O.P. covered only }
Times expired }

Paul Schisler IS PERMITTED TO INSTALL X ALTER

ADDRESS 4410 Salamotton Road, Westminster, MD 21157 PHONE 875-4187

SUBDIVISION Green's Estate ROAD 1221 Sharp Road LOT 9, SUB I

PROPERTY OWNER Self - David Swank

ADDRESS _____

IF GARBAGE GRINDER IS USED INCREASE SEPTIC TANK CAPACITY BY 50% AND ABSORPTION AREA BY 25%

GARBAGE GRINDER YES _____ NO X

SEPTIC TANK CAPACITY 1250 GALLONS NUMBER OF BEDROOMS 4

OP
69917

TRENCHES - 158 sq. ft. per bedroom. Trench to be 2 feet wide. Inlet 4 feet below original grade. Bottom maximum depth 9 feet below original grade. Effective area begins at 4 feet below original grade. 5 feet of stone below distribution pipe.

LOCATION - Place distribution box 160 feet from the front lot line and 95 feet from the right lot line, as seen when facing the property from Sharp Road. Run trench(s) along contour toward both side lot lines.

NOTES - NO trench to exceed 100 feet in length. If more than one trench used, a distribution line is required. Call for inspection of trench(s) before and after gravel is installed. Provide 4" - 6" diameter cleanout and cap to grade or above on septic tank.

BLDG. PERMIT SIGNED

AND RETURNED 7/21/83
Jeri H. Williams - Bldg.

PLANS APPROVED BY (Revised) C. Williams DATE 7/21/83

COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

NOTE: IF TRENCH IS USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH.

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER. NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH.

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 40 PVC OR PIPE.
PERMIT VOID AFTER THREE YEARS.

BLDG. PERMIT SIGNED
AND RETURNED 7/21/83
Jeri H. Williams - Bldg.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRAZO COTTA OR PVC OR ABS ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET MARKER TO GRADE REQUIRED.

*INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT

*CALL 892-2330 FOR INSPECTION OF SEPTIC SYSTEMS.

EN - 2 - 1082

A-22823

