

2:30 3-24-03 714

PUB. SEWER STATUS VERIFIED BY SRK NA

ISSUE DATE: 3/14/2003

APPROVAL DATE: 3/25/03

PERMIT INDEXED

P 518594
A REPAIR

ON-SITE SEWAGE DISPOSAL SYSTEM HOWARD COUNTY HEALTH DEPARTMENT BUREAU OF ENVIRONMENTAL HEALTH

04-319249

WRF & Sons, Inc. IS PERMITTED TO INSTALL ALTER

ADDRESS: 15 North Main St., Mt. Airy PHONE NUMBER: 410-795-0331

SUBDIVISION: _____ LOT NUMBER: _____

ADDRESS: 16309 Old Frederick Road PROPERTY OWNER: Eugene Curtin

SEPTIC TANK CAPACITY (GALLONS): existing Install Manhole Cleanout
PUMP CHAMBER CAPACITY (GALLONS): NA on existing septic tank &
NUMBER OF BEDROOMS: 5 Check baffles & repl. if
necessary

SQUARE FEET PER BEDROOM: 210 x 5 = 1050 / 3 = 350' x .62 = 217

LINEAR FEET OF TRENCH REQUIRED: 217 (3-72' trenches)

TRENCHES:	Trench to be 3 feet wide. Inlet 4' feet below original grade. Bottom maximum depth 6' feet below original grade. Effective area begins at 4' feet below original grade. 2' feet of stone below distribution pipe.
LOCATION:	Tie into ex. drywell as a backup/overflow system Set leveler 1" high in d. box feeding to drywell
PURPOSE:	Existing septic system has failed. Call for inspection when ground is opened so sanitarian can recommend repair.

PLANS APPROVED: Steven R. Krieg DATE: 3/17/03

- NOTE: PERMIT VOID AFTER 2 YEARS
- NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS
- NOTE: WATERTIGHT SEPTIC TANKS REQUIRED
- NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM

P518594

