

PERMIT

P 2025

A 1397

11/6/75
after 12 noon

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELlicOTT CITY

DISTRICT 3rd

INDEXED

DATE 10/6/75

Jim Brittingham

IS PERMITTED TO INSTALL X ALTER

ADDRESS 3004 N. Rogers Avenue, Ellicott City, Md.

PHONE 461-1878

A SEWAGE DISPOSAL SYSTEM LOCATED AT

SUBDIVISION Kingston

ROAD Camilla Drive

LOT 28

PROPERTY OWNER James V. King, Sr.

ADDRESS 304 Freedom Road, Blanesville, Md. 21150

SPECIFICATIONS 3 bedrooms

DRAIN FIELD DEPTH FEET, BOTTOM AREA SQ. FT.

SEEPAGE PITS ABSORBENT SIDE-WALL AREA SQ. FT.

SEPTIC TANK CAPACITY 1000 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA AND TANK CAPACITY SEE

OTHER DRY WELL - 200 sq. ft. absorbent sidewall area. Inlet at 5 ft. and maximum depth permitted for dry well is 10 ft. Locate dry well 45 ft. from rear of lot and 155 ft. from Williamfield Drive. Connect dry well with 5 ft. 4" dia. pipe and 6" dia. trench. Trench to run towards Williamfield Drive. Trench shall inlet at 5 ft. and maximum depth 10 ft., 50 ft. long. Call for inspection of trench before gravel is installed.

NOTE! ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS. NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL.

STAND PIPE MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED.

PLANS APPROVED BY Donald W. Monaghan

DATE 3/31/74 & 7/24/75

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER HO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

BLDG. PERMIT SIGNED AND RETURNED

11/10/75
Serial # 45738
Additional Standards
check fast area

A 13397

