

1/2 (84)
a.m.

approved
8-2-84
C. Wilbur

PERMIT

P 34101
A 26092

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH*

HOWARD COUNTY
BUREAU OF ENVIRONMENTAL HEALTH
992-2330

ELLICOTT CITY
DISTRICT 5th
DATE 7/12/84

INDEX

Donald Parlette IS PERMITTED TO INSTALL ALTER

ADDRESS 6565 Route 32, Clarksville, Maryland 21029 PHONE 286-2140

SUBDIVISION Simpson Woods ROAD 7302 Meadow Wood Way LOT 19, Sec. 3

PROPERTY OWNER Jerry A. Walker and Frances Caruso

ADDRESS 7499 Hickory Log Circle, Columbia, Md. 21043 Home: 964-3788
Office: 800-424-888 8874

IF GARBAGE GRINDER IS USED INCREASE SEPTIC TANK CAPACITY BY 50% AND ABSORPTION AREA BY 22%.

GARBAGE GRINDER? YES NO

SEPTIC TANK CAPACITY 1000 GALLONS NUMBER OF BEDROOMS 3

DRY WELL - 135 sq. ft. absorbent sidewall area per bedroom to begin below the first 3 1/2 ft. of original grade. Maximum depth permitted for dry well is 11 ft. below original grade. Place dry well 155 ft. from front lot line and 60 ft. from left lot line as seen when facing from the front.

PLANS APPROVED BY Donald W. Monaghan DATE 6/4/80

COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

NOTE: IF TRENCH IS USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH.

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER. NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH.

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 40 PVC OR ABS.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER CAST IRON, CONCRETE OR TERRA COTTA, OR PVC OR ABS ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET MANHOLE TO GRADE REQUIRED

***INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APROVAL ON THIS PERMIT**

*CALL 992-2330 FOR INSPECTION OF SEPTIC SYSTEMS.

EH - 2-1082

A 26092

