

7/2/81 App'd S.S.

3/6/81
3/10/81 open trench

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH*

HOWARD COUNTY

Indexed

P 31204

A 24134

ELLICOTT CITY

DISTRICT 5th.

DATE 3/3/81

Charles W. Schroyer IS PERMITTED TO INSTALL ALTER

ADDRESS 6805 Haviland Mill Road, Clarksville, Md. 21029 PHONE 596-9160

SUBDIVISION _____ ROAD 6825 Haviland Mill Road LOT 3

PROPERTY OWNER Charles W. Schroyer

ADDRESS 6805 Haviland Mill Road

SPECIFICATIONS 4 Bedrooms

SEPTIC TANK CAPACITY 1250 GALLONS

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

DEEP TRENCH _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

Dry Well

SEEPAGE PITS 3 ABSORBENT SIDE-WALL AREA 145 SQ. FT. 10 per bedroom

INLET PIPE _____ FT. BELOW ORIGINAL GRADE. MAXIMUM DEPTH _____ FT. BELOW ORIGINAL GRADE

EFFECTIVE DEPTH AT _____ FT. BELOW ORIGINAL GRADE.

LOCATE DISPOSAL AREA 340 FT. FROM front LOT LINE AND 127 FT. FROM left LOT LINE AS SEEN WHEN

FACING LOT FROM Haviland Mill Road

145
7
80

NOTE: The front lot line is the line which separates this lot from Lot #2. See Plat.

OKAY TO USE TRENCH OFF DRY WELL TO MAKE UP ABSORBENT SIDEWALL AREA IN SYSTEM.

LEAVE 5 FT. EARTH BUFFER BETWEEN TRENCH AND DRY WELL. TRENCH TO FOLLOW CONTOUR OF THE

LAND. CALL FOR TWO (2) INSPECTIONS OF TRENCH - BEFORE AND AFTER STONE IS INSTALLED.

PLANS APPROVED BY Raymond Hodges DATE 11/10/77

COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

NOTE: IF TRENCH IS USED CALL FOR INSPECTION BEFORE PLACING GRAVEL IN TRENCH.

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED.

BLDG. PERMIT SIGNED
AND RETURNED 3/12/81
Serial # 45727

A 24134

***INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT.**

A24134

580 #



INDICATE NORTH. - NAME ADJOINING ROADWAY AS BASE LINE.

PERMIT CARD

SEPTIC TANK, LEVEL OK

CLEANOUTS

ST	DW
ALL YES	ALL YES

DISTRIBUTION BOX, LEVEL NA.

TILE FIELD, DEPTH 9 FT. TRENCH WIDTH 2 FT.

GRAVEL DEPTH 6 IN. TOTAL LENGTH 37 FT.

NUMBER OF TRENCHES 1 TOTAL BOTTOM AREA 222 #

SEEPAGE PITS, INSIDE DIAMETER Bermester 48 FT. DEPTH BELOW INLET 7 FT.

ABSORBENT AREA 336 SQ. FT.

558 #
Total

REMARKS 3/6/81 DW HOLE DUG LOCATION OK HOLE IS 10 FT
BELOW O.G. FINISH DITCH & DW. & CALL CALLED SCHROYER
LEFT MESSAGE RH 3/10/81 FOR to work with mud House
connection for final approval -SK-

DATE SYSTEM APPROVED 7/2/81

INSPECTOR F. Skinner