

*House back in woods*  
*Approved 5/11/70*  
*Hopkins taking*  
*the driveway*  
*between street*  
**PERMIT** P. 14653  
SEWAGE DISPOSAL SYSTEM A 14653  
MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

**INDEXED**

DISTRICT 5

DATE 4/16/70

Paul Greger

IS PERMITTED TO INSTALL  ALTER

ADDRESS Rt. 2, Kameover, Maryland

PHONE 796-0952

A SEWAGE DISPOSAL SYSTEM LOCATED AT \_\_\_\_\_

SUBDIVISION \_\_\_\_\_ ROAD John Hopkins Rd. & Sanner Rd. (see application for better directions) LOT 6

PROPERTY OWNER Arthur J. Adkins

ADDRESS \_\_\_\_\_

SPECIFICATIONS - 3 bedrooms

DRAIN FIELD \_\_\_\_\_ DEPTH \_\_\_\_\_ FEET, BOTTOM AREA \_\_\_\_\_ SQ. FT.

SEEPAGE PITS \_\_\_\_\_ ABSORBENT SIDE-WALL AREA \_\_\_\_\_ SQ. FT.

SEPTIC TANK CAPACITY 750 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 25% & TANK CAPACITY 50%.

OTHER Dry well - 336 sq. ft. absorbent sidewall area below inlet pipe.

Inlet pipe 4 ft. below original grade. Max. depth permitted for dry well is 12 ft.

below original grade. Place dry well 50 ft. from the 199.96 part of front lot

line and 141 ft. from left sideline as seen when facing from the front.

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

PLANS APPROVED BY D. W. Monaghan

DATE 7/22/69

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

A 14653

