

Approved: 7-8-80  
Stephen E. Kiel

P 30709

A-23346

# PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

INDEXED

ELLICOTT CITY

DISTRICT 4th.

04-36835

DATE 6/3/80

Michael Hall

IS PERMITTED TO INSTALL  ALTER

ADDRESS 6134 Olney - Laytonsville Road, Gaithersburg, Md. PHONE 869-8590

SUBDIVISION ROAD A.E. Mullinix Road LOT 3

PROPERTY OWNER Michael Hall PHONE: 869-8590

ADDRESS 6134 Olney - Laytonsville Road, Gaithersburg, Md.

SPECIFICATIONS 3 Bedrooms

SEPTIC TANK CAPACITY 1500 GALLONS

DRAIN FIELD DEPTH FEET. BOTTOM AREA SQ. FT.

DEEP TRENCH DEPTH FEET. BOTTOM AREA SQ. FT.

Dry Well

SEEPAGE PITS  ABSORBENT SIDE-WALL AREA 130 SQ. FT. per bedroom

INLET PIPE 3/4 FT. BELOW ORIGINAL GRADE. MAXIMUM DEPTH 11 FT. BELOW ORIGINAL GRADE

EFFECTIVE DEPTH AT FT. BELOW ORIGINAL GRADE.

LOCATE DISPOSAL AREA FT. FROM LOT LINE AND FT. FROM LOT LINE AS SEEN WHEN

FACING LOT FROM

Inlet can come in at a higher elevation. Location per owner's plan - when facing lot with driveway as front line 175 ft from rear lot line and 277 ft from right property line (1 & 2). Dry well or trench: (1) Leave 5 ft. earth buffer between dry well and trench. (2) Inspection before gravel in (3) Inspection after gravel in. If trench is used - trench must follow constant contour of ground and be inspected before gravel is installed.

PLANS APPROVED BY C. B. Sreaker DATE 4/26/77

COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

NOTE: IF TRENCH IS USED CALL FOR INSPECTION BEFORE PLACING GRAVEL IN TRENCH.

NOTE: NO DRY WELL SHALL EXCEED 16 FOOT IN DIAMETER.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRAZO ACCEPTED.

\*INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT.

A 23346 P 30709

