

10/2/72

44-1455-29288
DU 77 15439

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

DISTRICT 4th

✓ INDEXED

DATE 10/18/72

Jack Fyock

IS PERMITTED TO INSTALL X ALTER

ADDRESS Ten Oaks Road, Glenelg, Maryland

PHONE 286-2939

SEWAGE DISPOSAL SYSTEM LOCATED AT

SUBDIVISION

ROAD Duval Rd. - off A. E. LOT

PROPERTY OWNER Ford B. Mallow

Mullinix Rd. - pass first house on right property joins this land.

ADDRESS 6119 Landover Road, Cheverly, Maryland

SPECIFICATIONS 4 bedrooms

DRAIN FIELD _____ DEPTH _____ FEET. BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA _____ SQ. FT.

SEPTIC TANK CAPACITY 1200 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 80%.

OTHER DRY WELLS - 2 dry wells - dig wash pit 12 ft. square - set block and top for 10 ft. diameter and fill in rest of pit with gravel. Dry well to have 6 ft. effective depth below the first 24 ft. of non-absorbent ground. Maximum depth permitted for dry wells to be 13 ft. below original grade. Place dry well 137 ft. from edge of Duval Road and about 15 ft. from left sideline as seen when facing from Duval Road. Off dry well install trench 24 ft. long - bucket width - 12 1/2 ft. deep with 6 ft. gravel. Two inspections.

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL.

PLANS APPROVED BY Donald W. Monaghan

DATE 8/14/70

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

