

2/17/76
2/24/76 before
of new

PERMIT

P. 22814
21941
A

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH
HOWARD COUNTY

ELLICOTT CITY
DISTRICT 3rd
DATE 2/13/76

INDEXED

Jack Fyock

X

IS PERMITTED TO INSTALL ALTER

ADDRESS Ten Oaks Road, Glenelg, Maryland PHONE 286-2939

A SEWAGE DISPOSAL SYSTEM LOCATED AT

SUBDIVISION Woodmark ROAD 12232 Mt. Albert Road LOT 63, Blk. B, Sec. 7

PROPERTY OWNER Manfred J. Reinhard and Wife

ADDRESS 1131 Elbank Avenue, Baltimore, Md. 21239 Phone: 433-1191

SPECIFICATIONS 3 bedrooms

DRAIN FIELD DEPTH FEET, BOTTOM AREA SQ. FT.

SEEPAGE PITS ABSORBENT SIDE-WALL AREA SQ. FT.

SEPTIC TANK CAPACITY 1000 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%.

OTHER dry well and trench - Dry well to be located 225 ft. from front of lot, 75 to 100 ft. from right side line. Inlet at 5 ft. and maximum depth 10 ft.; 200 sq. ft. absorbent sidewall area. 5 ft. earth buffer between dry well and trench. Trench to run approximately parallel with right property line towards rear of lot. Trench inlet at 5 ft. Maximum depth 10 ft. Trench to be 35 ft. long. Call office for inspection of trench before pouring stone in trench.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED.

PLANS APPROVED BY David J. O'Neill DATE 8/14/75

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

A 21941

