

8/23/77 am.
please to check trip.
8/23/77 p.m. please
Final check

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

DISTRICT 5th

DATE 8/10/77

P 26540

A 21412

INDEXED

Kastner Plumbing & Heating IS PERMITTED TO INSTALL X ALTER

ADDRESS 13556 Argo Drive, Dayton, Md. 21036 PHONE 725-5000

A SEWAGE DISPOSAL SYSTEM LOCATED AT 0.5 mi. from Trin. Mill Rd. on right

SUBDIVISION 13707 ROAD Highland Road LOT _____

PROPERTY OWNER Ronald B ryan

ADDRESS 4307 Sarasota Place, Beltsville, Md. 20705 Phone: 937-3316

SPECIFICATIONS 4 bedrooms

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA _____ SQ. FT.

SEPTIC TANK CAPACITY 1250 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%.

OTHER DRY WELL - Dry well to be located between perc holes 1 and 3, 25 ft. from left lot line approximately 450 ft. from rear of lot; inlet to be at 4 1/2 ft. below original grade and maximum depth 11 1/2 ft. below original grade. Dry well to have 250 sq. ft. absorbent sidewall area. Trench to run towards right property line, to be 11 1/2 ft. deep, inlet at 4 1/2 ft. 5 Ft. Earhh buffer to be between dry well and trench. Trench to be 35 ft. long. NOTE: CALL FOR INSPECTION OF TRENCH BEFORE RXXI PLACING GRAVEL IN TRENCH. NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON. PERMIT VOID AFTER THREE YEARS. NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA-COTTA ACCEPTED.

PLANS APPROVED BY David J. O'Neill DATE 6/9/77

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

BLOG. PERMIT SIGNED
AND RETURNED 4/20/89
Serial # 24664-prod

21412

