

Subj: **Well & Septic Information**
Date: 6/9/2014 8:42:32 A.M. Eastern Daylight Time
From: hoswald@howardcountymd.gov
To: rwaddy420@aol.com

Hello Mr. Waddy:

Attached, you will find information about your well and septic system. Please be sure to include the location of your well on the plan. Please contact me with any questions.


Respectfully,

Hank

Hank Oswald, L.E.H.S.
Howard County Health Department
Well & Septic Program
8930 Stanford BLVD
Columbia, MD 21045
410-313-1786
410-313-2648 (Fax)

PERMIT #

B14001520



Bureau of Environmental Health
7178 Columbia Gateway Drive, Columbia, MD 21046-2147
Main: 410-313-2640 | Fax: 410-313-2648
TDD 410-313-2323 | Toll Free 1-866-313-6300
www.hchealth.org
Facebook: www.facebook.com/hocohealth
Twitter: HowardCoHealthDep

Maura J. Rossman, M.D., Health Officer

May 28, 2014

Ryan Waddy
17810 Old Frederick Road
Mount Airy, MD 21771

**RE: Building Permit B14001520
17810 Old Frederick Road
Proposed Pole Building**

Dear Mr. Waddy:

This office received the above referenced building permit application for construction of a pole building. Upon reviewing the application and drawing, several key items were not included in the plan. In order to verify required setback distances to the proposed pole building, a revised plan showing the location of the well and all septic components (i.e. septic tank, trench etc.) will need to be re-submitted on a scaled plot plan.

At this time, the building permit application has been placed on hold until a revised plan has been received and reviewed for these requirements. Should any questions or concerns arise, please contact me directly at (410) 313 – 1786 or hoswald@howardcountymd.gov.

Sincerely,

Hank Oswald

Hank Oswald, L.E.H.S.
Howard County Health Department
Well & Septic Program

5-17-88
Am

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

P 411657

A 36421

DISTRICT 4th

DATE 5/4/88

DATE SYSTEM APPROVED 5-27-88

INSPECTOR JEN

HOWARD COUNTY
BUREAU OF ENVIRONMENTAL HEALTH
461-9933

01-346068

INDEXED

Dale Fogle Septic Service IS PERMITTED TO INSTALL ALTER

ADDRESS 6430 Woodbine Road, Woodbine, Maryland 21797 PHONE 795-5670

SUBDIVISION Himmel Property ROAD 17810 Old Frederick Rd LOT 2

PROPERTY OWNER Henry Blevins

ADDRESS _____

IF GARBAGE GRINDER IS USED INCREASE SEPTIC TANK CAPACITY BY 50% AND ABSORPTION AREA BY 22%.

GARBAGE GRINDER? YES _____ NO

180
31720
240 ft trench

SEPTIC TANK CAPACITY 1250 GALLONS NUMBER OF BEDROOMS 4

TRENCHES - 180 sq. ft. per bedroom. Trench to be 3 feet wide. Inlet 3.5 feet below original grade. Bottom maximum depth 5.5 feet below original grade. Effective area begins at 3.5 feet below original grade. 2 feet of stone below distribution pipe.

LOCATION - Start the first trench 350 feet down the left (446.31') lot line and 100 feet off the same lot line as seen when facing the lot from Old Frederick Road. Run trenches on contour toward the left lot line.

NOTE - No trench to exceed 100 feet in length. Provide 6" - 8" diameter cleanout and cap to grade or above on septic tank.

OK

PLANS APPROVED BY Sid Abel DATE 2/16/88

COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

NOTE: CLEANOUT REQUIRED EVERY 70 FEET OF SEWER LINE AND/OR AT 90° SWEEPS IN LINES FROM HOUSE TO DRAIN FIELDS.

NOTE: ALL PARTS OF SEPTIC SYSTEMS (I.E., TANK, DISTRIBUTION BOX, TRENCHES) TO BE 100 FEET FROM WELL. (UNLESS OTHERWISE SPECIFICALLY AUTHORIZED)

NOTE: IF DEEP TRENCH(IES) ARE USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH(IES).

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER. NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH.

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 40 PVC OR ABS.

PERMIT VOID AFTER TWO YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA OR PVC OR ABS. ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET, MANHOLE TO GRADE REQUIRED.

NOTE: DISTRIBUTION BOXES MUST HAVE BAFFLES.

***INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT**

*CALL 461-9933 FOR INSPECTION OF SEPTIC SYSTEMS.

EH - 2-1186

A 36421