

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

DISTRICT 4th

DATE 2/1/74

P _____
A 16330
512015

Tuck and Kellum Backhoe Service IS PERMITTED TO INSTALL ALTER

ADDRESS 4360 Eldone Road, Baltimore, Md. 21229, PHONE 646-2746

A SEWAGE DISPOSAL SYSTEM LOCATED AT _____

SUBDIVISION (Daisy Meadows) ROAD Daisy Road LOT 8

PROPERTY OWNER Raymond Wright

ADDRESS 19 St. Agnes Road, Glen Burnie, Md. Phone: 761-6255

SPECIFICATIONS 3 bedrooms

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA _____ SQ. FT.

SEPTIC TANK CAPACITY 1000 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%.

OTHER DRY WELL - 300 sq. ft. sidewall area below the inlet with the inlet no deeper than 4 ft. below grade and the bottom of the dry well no deeper than 12 ft. Place the dry well 209 ft. from the cemetery wall and 130 ft. from the lot line which is 753.19 ft. long with a bearing of So 8 degrees 25 ft. 13 inches W.

NOTE: ALL PIPE FROM HOUSE TO DRY WELL MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL.

PLANS APPROVED BY Raymond Hodges DATE 10/6/71

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

10 x 12

512015