

Pool Upgrade

LAYOUT 12/18/06 INSP 4 _____
 INSP 2 12/20/06 INSP 5 _____
 INSP 3 _____ INSP 6 _____

ISSUE DATE: 12/14/06

PERMIT

P 525685

APPROVAL DATE: 12/21/2006

A 56430-G

**ON-SITE SEWAGE DISPOSAL SYSTEM
 HOWARD COUNTY HEALTH DEPARTMENT
 BUREAU OF ENVIRONMENTAL HEALTH**

Conceptual Building and Landscaping IS PERMITTED TO INSTALL ALTER

ADDRESS: 3258 Bethany Ln, Ellicott City PHONE NUMBER: 443-463-4268

SUBDIVISION: Gaither Hunt LOT NUMBER: 57

ADDRESS: 12009 Open Run Road PROPERTY OWNER: Andrew and Sandra Houen

SEPTIC TANK CAPACITY (GALLONS): _____ OUTLET BAFFLE FILTER REQUIRED

PUMP CHAMBER CAPACITY (GALLONS): _____ COMPARTMENTED TANK REQUIRED

NUMBER OF BEDROOMS: 4

SQUARE FEET PER BEDROOM: 180

LINEAR FEET OF TRENCH REQUIRED: 200 21.6

TRENCHES:	Trench to be 3.0 feet wide. Inlet 5.0 feet below original grade. Bottom maximum depth 7.0 feet below original grade. Effective area begins at 6.0 feet below original grade. 2.0 feet of stone below distribution pipe.
LOCATION:	Put the distribution box in the upper corner of the revised septic easement and install two 100 foot trenches on contour across the uppermost part of the easement.
NOTES:	Abandon existing trenches.

PLANS APPROVED: Brian Baker DATE: 12/12/2006

- NOTE: PERMIT VOID AFTER 2 YEARS
- NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS (410)313-1771
- NOTE: WATERTIGHT SEPTIC TANKS REQUIRED
- NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS UNLESS SPECIFICALLY AUTHORIZED

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS
 RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM
 PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT
 CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM**

