

C1 1257

SEQUENCE NO. (MDE USE ONLY)

STATE OF MARYLAND WELL COMPLETION REPORT

THIS REPORT MUST BE SUBMITTED WITHIN 45 DAYS AFTER WELL IS COMPLETED.

(THIS NUMBER IS TO BE PUNCHED IN COLS. 3-6 ON ALL CARDS)

COUNTY NUMBER 13

DATE RECEIVED MM 12 DD 05 YY 11

DATE WELL COMPLETED MM 08 DD 30 YY 11

DEPTH OF WELL 400 (TO NEAREST FOOT)

PERMIT NO. FROM "PERMIT TO DRILL WELL" HO-95-2108

OWNER CHELSEA RIDGE L.C. WELL SITE ADDRESS LONG CORNER ROAD TOWN MT. AIRY SUBDIVISION CHELSEA KNOLLS SECTION LOT 13

WELL LOG table with columns: DESCRIPTION, FEET (FROM, TO), check if water bearing. Includes entries for Soil, Clay, Brown shale, and Blue slate.

GROUTING RECORD: WELL HAS BEEN GROUTED (Y), TYPE OF GROUTING MATERIAL (CM), NO. OF BAGS (18), NO. OF POUNDS (1645), DEPTH OF GROUT SEAL (0 to 70 ft).

CASING RECORD: MAIN CASING TYPE (PL), Nominal diameter (6 inch), Total depth of main casing (70 feet).

OTHER CASING (if used) section with diameter and depth fields.

SCREEN RECORD: screen type or open hole (ST), insert appropriate code below.

NUMBER OF UNSUCCESSFUL WELLS: 0, WELL HYDROFRACTURED (Y)

CIRCLE APPROPRIATE LETTER: A (well abandoned), E (electric log), P (test well converted to production)

I HEREBY CERTIFY THAT THIS WELL HAS BEEN CONSTRUCTED IN ACCORDANCE WITH COMAR 26.04.04

DRILLERS LIC. NO. MWD 355, DRILLERS SIGNATURE (Marty Dine), LIC. NO. MS D 066

SITE SUPERVISOR (sign. of driller or journeyman responsible for sitework if different from permittee)

C2 DEPTH (nearest ft.) table with columns 1-21 and values 70, 400.


GRAVEL PACK IF WELL DRILLED WAS FLOWING WELL INSERT F IN BOX 68

MDE USE ONLY (NOT TO BE FILLED IN BY DRILLER) T (E.R.O.S.), W Q

C3 PUMPING TEST: HOURS PUMPED (6), PUMPING RATE (1.5), METHOD USED TO MEASURE PUMPING RATE (TIMER/Bucket), WATER LEVEL (58 ft before, 260 ft when pumping), TYPE OF PUMP USED (S submersible)

PUMP INSTALLED: DRILLER INSTALLED PUMP (NO), TYPE OF PUMP INSTALLED (29), CAPACITY: GALLONS PER MINUTE (31-35), PUMP HORSE POWER (37-41), PUMP COLUMN LENGTH (43-47), CASING HEIGHT (above/below land surface)

LATITUDE 39.31647, LONGITUDE 77.15544 (DEFAULT COORD. WGS 84)



B 1 2150

SEQUENCE NO. (MDE USE ONLY)

STATE OF MARYLAND APPLICATION FOR PERMIT TO DRILL WELL please type

STATE PERMIT NUMBER

40-95-2108 fill in this form completely

Date Received (APA)

OWNER INFORMATION

8 MM DD YY 13 15 Last Name Owner First Name 34 36 Street or RFD 55 57 Town 70 State 72 Zip 76


B 3 LOCATION OF WELL

8 COUNTY Howard 21 Chelsea Knolls 23 SUBDIVISION 42 SECTION 44 46 LOT 13 48 50 52 NEAREST TOWN Mt Airy 71 MILES FROM TOWN (enter 0 if in town) 73 4.0 76 77 78

DRILLER INFORMATION

Driller's Name Michael Barrow M D 355 License No. 81 Firm Name Barrow Well Drilling Service Address 520 Underwood Ln, Bel Air, Md Signature Date 3-8-11

B 4 DIRECTION OF WELL FROM TOWN (CIRCLE BOX)



11 NEAR WHAT ROAD Long Corner Rd 30

ON WHICH SIDE OF ROAD (CIRCLE APPROPRIATE BOX) NORTH WEST EAST SOUTH 675 34 37

DISTANCE FROM ROAD ENTER FT OR MI 38 39 TAX MAP: 6 BLK: 22 PARCEL 9

B 2 WELL INFORMATION

APPROX. PUMPING RATE (GAL. PER MIN.) 8 5 12 AVERAGE DAILY QUANTITY NEEDED (GAL. PER DAY) 14 750 20

USE FOR WATER (CIRCLE APPROPRIATE BOX)

- [D] DOMESTIC POTABLE SUPPLY & RESIDENTIAL IRRIGATION [F] FARMING (LIVESTOCK WATERING & AGRICULTURAL IRRIGATION) [I] INDUSTRIAL, COMMERCIAL, DEWATERING [P] PUBLIC WATER SUPPLY WELL [T] TEST, OBSERVATION, MONITORING [G] GEO-THERMAL

NOT TO BE FILLED IN BY DRILLER HEALTH DEPARTMENT APPROVAL

COUNTY NAME Howard COUNTY NO. A 515039 STATE SIGNATURE DATE ISSUED 4/27/11 CO SIGNATURE EXP. DATE 4/23/12 NORTH GRID 50 539 000 55 EAST GRID 57 0756 000 63

APPROXIMATE DEPTH OF WELL 24 250 28 FEET

APPROXIMATE DIAMETER OF WELL 6 NEAREST INCH

METHOD OF DRILLING (circle one)

BORED (or Augered) JETTED Jetted & DRIVEN AIR-ROTary AIR-PERCussion ROTARY (Hydraulic Rotary) CABLE REVERSE-ROTary DRIVE-POINT other

REPLACEMENT OR DEEPEMED WELLS (CIRCLE APPROPRIATE BOX)

- [N] THIS WELL WILL NOT REPLACE AN EXISTING WELL [Y] THIS WELL WILL REPLACE A WELL THAT WILL BE ABANDONED AND SEALED [S] THIS WELL WILL REPLACE A WELL THAT WILL BE USED AS A STANDBY-CONTACT LOCAL APPROVING AUTHORITY FOR POLICY ON STANDBY WELLS [D] THIS WELL WILL DEEPEM AN EXISTING WELL

PERMIT NUMBER OF WELL TO BE REPLACED OR DEEPEMED (IF AVAILABLE) 41 52

Not to be filled in by driller (MDE OR COUNTY USE ONLY)

APPROP. PERMIT NUMBER 40-2007-G-025 (3) PERMIT No. 40-95-2108


SHOW MAJOR FEATURES OF BOX & LOCATE WELL WITH AN X

SOURCES OF DRILLING WATER 1. Well 2. 3.

WRITE THE BOX NUMBER FROM THE MAP HERE

E 7506 N 5309

DRAW A SKETCH BELOW SHOWING LOCATION OF WELL IN RELATION TO NEARBY TOWNS AND ROADS AND GIVE DISTANCE FROM WELL TO NEAREST ROAD JUNCTION



SPECIAL CONDITIONS

NOTE - APPROVING AUTHORITIES SHOULD USE SEPARATE SHEET IF NEEDED



MICHAEL BARLOW WELL DRILLING & SERVICE, INC.

522 Underwood Lane
 (410) 838-6910

Bel Air, Maryland 21014
 Fax (410) 838-3582

WELL YIELD REPORT


Date Test Completed:		August 2, 2011	
Well Depth:		400	feet
Customer	Elm Street Development	Permit #	HO-95-2108
Road	Long Corner Road	Subdivision	Chelsea Knolls
City	Mt. Airy	Section	
State	Maryland	Lot #	13

Time	Water Level feet	Time to Fill 1-gallon bucket seconds	G.P.M.
8:00 AM	58	4	15.00
8:15 AM	142	4	15.00
8:30 AM	237	5	12.00
8:45 AM	255	35	1.71
9:00 AM	260	40	1.50
9:15 AM	260	40	1.50
9:30 AM	260	40	1.50
9:45 AM	260	40	1.50
10:00 AM	260	40	1.50
10:15 AM	260	40	1.50
10:30 AM	260	40	1.50
10:45 AM	260	40	1.50
11:00 AM	260	40	1.50
11:15 AM	260	40	1.50
11:30 AM	260	40	1.50
11:45 AM	260	40	1.50
12:00 PM	260	40	1.50
12:15 PM	260	40	1.50
12:30 PM	260	40	1.50
12:45 PM	260	40	1.50
1:00 PM	260	40	1.50
1:15 PM	260	40	1.50
1:30 PM	260	40	1.50
1:45 PM	260	40	1.50
2:00 PM	260	40	1.50
2:15 PM	260	40	1.50
2:30 PM	260	40	1.50
2:45 PM	260	40	1.50
3:00 PM	260	40	1.50



This yield test report is for informational purposes only. Please note the yield may increase or decrease over time and the GPM indicated above is not a guarantee.

H:\01-009\dwg\Well-Permit\01-009-well.dwg

4-21-11
Well Box
staked by mba.
-kmw



LEGEND

-  WELL AREA
-  SEPTIC AREA


**WELL PERMIT
CHELSEA KNOLLS LOT 13**

FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND

SCALE: 1"=50'	DRAWN BY: MMM	DATE: APRIL 2011	PN: 01-009
---------------	---------------	------------------	------------

**MILDENBERG
BOENDER, & ASSOC., INC.**

Engineers Planners Surveyors
6800 Deerpath Road, Suite 150, Elkridge, Maryland 21075
(410) 997-0296 Ball. (410) 997-0298 Fax.



Bureau of Environmental Health

8930 Stanford Blvd., Columbia, MD 21045
Main: 410-313-2640 | Fax: 410-313-2648
TDD 410-313-2323 | Toll Free 1-866-313-6300
www.hchealth.org
Facebook: www.facebook.com/hocohealth
Twitter: HowardCoHealthDep

Maura J. Rossman, M.D., Health Officer

INTERIM CERTIFICATE OF POTABILITY

Expiration Date – FEBRUARY 21, 2015

August 21, 2015

Homeowner
18342 Chelsea Knolls Drive
Mr. Airy, MD 21771

**RE: Chelsea Knolls, Lot 13
18342 Chelsea Knolls Drive
Building Permit: B15000745
Well Permit: HO-95-2108**

Dear Homeowner:


This is to advise you that the septic system installation and water well construction for the above referenced property have been inspected and approved. Final approval of the septic system was granted on **8/14/2015**. Final approval of the well line connection to the dwelling was granted on **7/7/2015**. The well construction was completed on **8/30/2011**. Water samples were collected on **8/7/2015**.

The water sample results indicate that the water samples submitted for testing were free of coliform and fecal coliform bacteria at the time of sampling and are bacteriologically safe for drinking. This certifies that the initial sampling requirements of COMAR 26.04.04 "Well Regulations" have been met for the water supply system installed under well permit HO-95-2108. Although the submitted sample results are in compliance with COMAR standards, the Health Department does not guarantee water supplies.

This Interim Certificate of Potability will expire **six months** from the date of issuance. Submission of a second bacteriological test indicating the water is free of coliform and fecal coliform bacteria is required prior to the expiration date, after which time a Final Certificate of Potability will be issued. **Failure to submit an additional sample and obtain a Final Certificate of Potability will result in a Notice of Violation and is punishable as a misdemeanor under the Annotated Code of Maryland, Environment Article, 9-1311, subject to a fine of up to \$500 or imprisonment not to exceed three months.**

Please contact (410) 313-1773 to schedule a final water sample appointment or contact a Maryland certified water laboratory to schedule a water sample. A list of laboratories certified by the state of Maryland may be found at the following website:
<http://www.mde.state.md.us/assets/document/WSP-Labs-2010apr16.pdf>

Approving Authority,



Keyin M. Wolf, LEHS, Supervisor
Groundwater Management Section
Well & Septic Program

cc: Howard County Dept. of Inspections, Licenses, and Permits
Community Hygiene Program
File

**HOWARD COUNTY HEALTH DEPARTMENT
BUREAU OF ENVIRONMENTAL HEALTH
WELL & SEPTIC PROGRAM
TEL: (410)313-1771 FAX: (410)313-2648**

Information Form for the Installation of the Well Pump, Pitless Adapter, and Supply Piping

NOTE: The installer is responsible for requesting an inspection prior to 9 am on the day of the desired inspection. No work is to be covered until approved by the Health Department. All installations must comply with the National Standard Plumbing Code (NSPC, as amended locally) and COMAR 26.04.04 (MD Well Construction Regulations). Submission of a complete form is required prior to Use and Occupancy approval.

Company Name: Robert L. Feezer Co. Telephone #: 410-781-4655
Address: 6321 Barnett Avenue
Sykesville, MD 21784

(**Must circle one**) Licensed Plumber Licensed Well Driller Licensed Well Pump Installer
License # and name of individual responsible for the field installation:
Name (Print): Joshua Henricks License# PI0173

***A licensed individual must perform the actual installation. Apprentices must be under the supervision of a licensed journeyman or master plumber, pump installer or well driller. Licenses may be subjected to field verification. Unlicensed individuals may be reported to the appropriate licensing agency.**

Name of Property Owner: Chelsea Knolls LC Telephone #: _____
Subdivision: Chelsea Knolls Lot #: 13 Well Tag #: HO - 95 - 2108 ✓
Site Address: 18342 Chelsea Knolls Drive
Mount Airy, MD 21771

<u>Submersible Pump Data</u>	<u>Pitless Adapter</u>	<u>Well Cap and Electric Conduit</u>
Make: <u>Grundfos</u>	Make: <u>Boshart</u>	Two piece watertight cap: <u>Yes</u>
Model #: <u>15SQE15-290</u>	Model#: <u>P-100-SS</u>	Screened, vented well cap: <u>Yes</u>
Pump Capacity <u>15</u> GPM	Depth: <u>42"</u> (36" min)	Cap secured to casing: <u>Yes</u>
Well Yield: <u>1.50</u> GPM	NSF/WSC approved: <u>Yes</u>	Conduit min 18" B.G.: <u>Yes</u>
Depth of well encountered at time of pump installation: <u>400</u> (feet)		Conduit secured to well cap: <u>Yes</u>

If pump capacity exceeds well yield, a low water cut off switch is required by NSPC 1990 Section 17.8.4
Torque arrestors, Cable guards, or other acceptable method used- Must circle one
Safety rope, if used, attached to brass rope adapter or other acceptable method inside of well casing N/A

<u>Piping to house</u>	<u>House Connection</u>
Type: <u>Poly</u>	PVC sleeve to undisturbed soil at wall penetration: <u>Yes</u>
PSI: <u>200</u> (160 psi min)	Length of sleeve(5' minimum from foundation): <u>10'</u>
Depth of supply line: <u>42"</u> (36" min)	Sleeve sealed properly: <u>Yes</u>

The water supply line is required to be at least ten feet from the septic tank, pump chamber, sewage piping, distribution box, drainfields, and sewage reserve area. If this cannot be accomplished, contact this office for approval prior to installation.

Joshua Henricks October 15, 2014
Signature of company representative responsible for installation date

For Health Department Use Only – Not to be completed by Installer

Date Insp. Requested: 7/2/15 Date Insp. Approved: 7/2/15 Inspector: KW
Inspection Data: Pitless adapter watertight & water supply line at least 36" below grade ✓
Two piece cap installed and attached to casing securely ✓
Elec. conduit extends at least 18" below grade/attached to cap properly ✓
Safety rope not outside of well cap/casing ✓
Correct well tag attached properly and casing 8" above finished grade ✓
Water supply line sleeved adequately at house connection ✓
Adequate grout observed below pitless adapter ✓

FOUNTAIN VALLEY ANALYTICAL LABORATORY, INC.

1413 Old Taneytown Rd. Westminster, MD (410) 848-1014 (410) 876-4554 FAX (410) 848-0298

REPORT OF ANALYSIS

Laboratory ID #: 102408 Account #: 6488
Reference: Ryan Homes Lot 13 Company: Hatfield's Equipment, Inc.
Location: 18342 Chelsea Knolls Requested By: Kenny Hatfield
Mount Airy, MD 21771 Source: Well Water
Date/ Time Collected: 8/7/2015 0954 Site: Pressure Tank
Date/Time Rec'd: 8/7/2015 1239 Treatment: None
Chlorine ppm: Free: ND Total: ND pH: 6.1
Collected By: J. Yeager 6176JY Well #: HO-95-2108

PARAMETERS	RESULTS	UNITS	REFERENCE	METHOD	DATE/TIME/ANALYST
Bacteria, Coliform, Total, MPN	<1.0	MPN/ 100 ml	<1.0	SM18 9223	8/8/2015 / 1000 / LLO
Bacteria, E. coli, MPN	<1.0	MPN/ 100 ml	<1.0	SM18 9223	8/8/2015 / 1000 / LLO
Nitrate	7.67	mg/L	10	601	8/7/2015 / 1414 / CRS
Turbidity	0.47	NTU	<10	SM18 2130B	8/7/2015 / 1440 / CRS
Sand	NS	mg/L	5	Visual/Gravimetric	8/7/2015 / 1440 / CRS

OK
—
kmw

NOTES

- 1 Revised Report to show correct Lot #. 8/18/15 BCD
- 2 mg/L = milligrams per liter (also, parts per million)
- 3 MPN/ 100 ml = Most Probable Number [of viable bacteria] per 100 ml of sample.
- 4 NS = None Seen (NS indicates less than 5 mg/L)
- 5 NTU = Nephelometric Turbidity Units
- 6 Results less than or within the reference range are considered satisfactory and within potable water limits at the time of sampling.
- 7 ND:None Detected
- 8 pH & Chlorine level tested on site
- 9 Visual well check: Sealed, vented cap

Reason for Test : Use & Occupancy
Building Permit # : B15000745

Date Reported: 8/18/2015