

PUB. SEWER STATUS VERIFIED BY _____

ISSUE DATE: 03/02/06

PERMIT

P 524161

APPROVAL DATE: 4/14/06

A REPAIR

ON-SITE SEWAGE DISPOSAL SYSTEM HOWARD COUNTY HEALTH DEPARTMENT BUREAU OF ENVIRONMENTAL HEALTH

Fyock Septic Service IS PERMITTED TO INSTALL ALTER

ADDRESS: PO Box 89, Glenelg, MD 21737 PHONE NUMBER: 410-988-9270

SUBDIVISION: Allnutt Farm Estates LOT NUMBER: 16

ADDRESS: 13421 Allnutt Lane PROPERTY OWNER: John D'Zmura

SEPTIC TANK CAPACITY (GALLONS): 1500 ² *Compartmented, Top Seamed*
PUMP CHAMBER CAPACITY (GALLONS): _____ *Abandon septic tank and dry well*

NUMBER OF BEDROOMS: 4

SQUARE FEET PER BEDROOM: 180

LINEAR FEET OF TRENCH REQUIRED: 112

TRENCHES:	Trench to be 2.0 feet wide. Inlet 4.0 feet below original grade. Bottom maximum depth 9.0 feet below original grade. Effective area begins at 3.5 feet below original grade. 5.0 feet of stone below distribution pipe.
LOCATION:	<i>(2) 56' trenches</i>
PURPOSE:	Existing septic system has failed. Call for inspection when ground is opened so sanitarian can recommend repair.

PLANS APPROVED: *[Signature]* DATE: 3/1/06

- NOTE: PERMIT VOID AFTER 2 YEARS
- NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS
- NOTE: WATERTIGHT SEPTIC TANKS REQUIRED
- NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

NEITHER THE HOWARD COUNTY COUNCIL OR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM

4/6/06 Fax to Ronnie

PUB. SEWER STATUS VERIFIED BY _____

ISSUE DATE: 3/21/2006

PERMIT

P 524161

APPROVAL DATE: _____

A REPAIR - 24728

ON-SITE SEWAGE DISPOSAL SYSTEM HOWARD COUNTY HEALTH DEPARTMENT BUREAU OF ENVIRONMENTAL HEALTH

Fyock Septic Service IS PERMITTED TO INSTALL ALTER

ADDRESS: PO Box 89, Glenelg, MD 21737 PHONE NUMBER: 410-988-9270

SUBDIVISION: Allnutt Farm Estates LOT NUMBER: 16

ADDRESS: 13421 Allnutt Lane PROPERTY OWNER: John D'Zmura

SEPTIC TANK CAPACITY (GALLONS): ~~Ex 1000~~ 1500 comp T.S.

PUMP CHAMBER CAPACITY (GALLONS): — Abandon, S.T. & I.D.W.

NUMBER OF BEDROOMS: ~~3~~ 4

SQUARE FEET PER BEDROOM: ~~160~~ 180

LINEAR FEET OF TRENCH REQUIRED: ~~84'~~ 112'

TRENCHES:	Trench to be 2 feet wide. Inlet ⁴ feet below original grade. Bottom maximum depth 9 feet below original grade. Effective area begins at 3.5 feet below original grade. 5 feet of stone below distribution pipe.
LOCATION:	Keep Dry well, fill w/ stone, new buffer on outside
PURPOSE:	Existing septic system has failed. Call for inspection when ground is opened so sanitarian can recommend repair.

PLANS APPROVED: [Signature] DATE: 3/1/06

- NOTE: PERMIT VOID AFTER 2 YEARS
- NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS
- NOTE: WATERTIGHT SEPTIC TANKS REQUIRED
- NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

NEITHER THE HOWARD COUNTY COUNCIL OR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT CALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM

FILE INQUIRY FORM

Property Address: _____

Owner called & wanted to
wax easment, so that an addition
can be built.

Site inspection checking dry well
must be done.

- Also Auger towards rear of easment
if augering fails, perc. must be done.
1-10-05 P.A.Y.

01-24-2005 Septic easment has
changed/northern area deleted & added
to southern part of easment, to
accommodate addition to house, 16'00
sq feet removed & added to rear of easment.

On site owner sounded as if wanted to
get rid of dry well & switch to
conventional trenches (P.A.Y.)

Fee Paid \$
Receipt #P

SEPTIC SYSTEM REPAIR / UPGRADE / EVALUATION REQUEST

Please fill out this form completely and check off the reason for the request:

Date requested: 2-28-06

Reason for Request

Failing System (includes surface discharge or inadequate treatment zone)

Has the contractor verified through excavation/pumping evaluation, that there are no pipe blockages? yes

In support of a building permit. Type of building addition: _____

*System relocation for proposed addition for setback compliance

*Verification of adequate system capacity per COMAR 26.04.02.02D (4)

To replace collapsed septic tank or upgrade tank capacity

To replace collapsed drywell

Septic Contractor: Flock

Contractor's Address: _____

Contractor's Phone #: 410-988-9270

Property Address: 13421 Allnutt Ln., Highland, MD 20777

Property (Subdivision) & Lot #: Lot 16 Allnutt Farm Estates

Owner's Name: John & Sandra D'Zmura

Is public sewer available/nearby: No

Names of Any Previous Owners: Giannantonio

Year House Built: 1978

of Existing Bedrooms: 3

of Bedrooms after completion of addition: 4

Has this request been discussed previously with a Sanitarian, who? _____

If public sewer is close, further research will be performed to verify availability and possible hook up to public sewer.

A Sanitarian will be in contact within three business days depending upon the urgency of the situation to coordinate the scheduling of the repair /upgrade/evaluation. No inspection will be performed without fee collection at the office.

Environmental Sanitarian tentatively assigned _____

FAX TO 410-313-2648

2/28/06

TO WHOM IT MAY CONCERN,

MY EXISTING DRYWELL SEPTIC SYSTEM IS COMING TO IT'S END OF LIFE. THERE HAS BEEN SOME PONDING ABOVE THE DRYWELL IN THE LAST WEEK OR SO. ON 2/27/06 I HAD A SEPTIC CONTRACTOR (FYOCK) COME OUT AND ASSESS THE SITUATION. FYOCK OPENED THE PIPE THAT IS ABOVE THE DRYWELL AND THE PIPE IS FULL OF WATER.

ABOUT A YEAR AGO I HAD PETER YENCSEK COME OUT AND TEST THE SOIL AND MODIFY THE SHAPE OF THE SEPTIC EASEMENT TO ACCOMODATE AN ADDITION. HE DID THIS AND YOU SHOULD HAVE THIS INFORMATION ON FILE. AT THAT TIME WE WERE CONSIDERING ADDING A BEDROOM TO OUR HOUSE BUT WE HAVE NOW PUT THAT PLAN ON HOLD.

THE HOUSE IS CURRENTLY A 3 BEDROOM 2 FULL BATHROOM HOUSE. WE MIGHT ADD AN EXTRA BEDROOM IN THE FUTURE SO PLEASE CONSIDER THE EXTRA BEDROOM IN YOUR SEPTIC DESIGN.

PLEASE CALL JOHN D'ZMURA WITH ANY QUESTIONS..... 240-832-0316

PROPERTY ADDRESS...

13421 ALLNUTT LANE, HIGHLAND, MD 20777

D'Zmura Properties
13421 Allnutt Lane
Highland, Maryland 20777

office: 301-854-9805
fax: 301-854-9806

FAX TRANSMISSION

Date: 2-28-06

To: Howard County Health Dept.
410.313.2648

From: John D'Zmura

Pages: 3, including cover sheet

Comments: