

LAYOUT _____ INSP 4 _____

INSP 2 _____ INSP 5 _____

INSP 3 _____ INSP 6 _____

ISSUE DATE: _____

PERMIT

P _____

APPROVAL DATE: _____

A 520847

TAX ID # _____

ON-SITE SEWAGE DISPOSAL SYSTEM HOWARD COUNTY HEALTH DEPARTMENT BUREAU OF ENVIRONMENTAL HEALTH

_____ IS PERMITTED TO INSTALL ALTER

ADDRESS: _____ PHONE NUMBER: _____

SUBDIVISION: A.E. Mullinix LOT NUMBER: _____

ADDRESS: 16780 A.E. Mullinix Rd PROPERTY OWNER: Rachuba Homes

SEPTIC TANK CAPACITY (GALLONS): 2000 OUTLET Baffle FILTER REQUIRED

PUMP CHAMBER CAPACITY (GALLONS): _____ COMPARTMENTED TANK REQUIRED

NUMBER OF BEDROOMS: 4

SQUARE FEET PER BEDROOM: _____

LINEAR FEET OF TRENCH REQUIRED: 208

TRENCHES:	Trench to be 3.0 feet wide. Inlet 3.0 feet below original grade. Bottom maximum depth 5.0 feet below original grade. Effective area begins at 4.0 feet below original grade. 2.0 feet of stone below distribution pipe.
LOCATION:	
NOTES:	Install per plan unless directed by HCHD. Layout inspection required. Existing house, well & septic system to be abandoned prior to U&O of new house on preservation parcel.

PLANS APPROVED: Sara Sappington DATE: 6/12/08

NOTE: PERMIT VOID AFTER 2 YEARS

NOTE: CONTRACTOR RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS

NOTE: WATERTIGHT SEPTIC TANKS REQUIRED

NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL

NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS UNLESS SPECIFICALLY AUTHORIZED

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS
RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM
PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT
CALL 410-313-1771 FOR INSPECTION OF SEPTIC SYSTEM**

NOT TO SCALE

TRENCH/DRAINFIELD DATA

WIDTH _____ INLET _____ BOTTOM _____

NUMBER OF TRENCHES _____

TOTAL LENGTH _____

ABSORPTION AREA _____

DISTRIBUTION BOX LEVEL _____

DISTRIBUTION BOX BAFFLE _____

DISTRIBUTION BOX PORT _____

SEPTIC TANK DATA

SEPTIC TANK 1 LEVEL _____

CAPACITY _____ GAL

SEAM LOC _____

TANK LID DEPTH _____

BAFFLES _____

BAFFLE FILTER _____

MANHOLE LOC _____

6" PORT LOC _____

WATERTIGHT TEST _____

SEPTIC TANK 2 LEVEL _____

CAPACITY _____ GAL

SEAM LOC _____

TANK LID DEPTH _____

BAFFLES _____

BAFFLE FILTER _____

MANHOLE LOC _____

6" PORT LOC _____

WATERTIGHT TEST _____

ROAD

PRE-CONSTRUCTION _____

INSTALLATION _____

FINAL INSPECTOR _____ DATE OF APPROVAL _____

WOODBINE ROAD
MARYLAND ROUTE 94
(STATE ROAD)

TAX MAP PARCEL 249
GENE W. & CHARLOTTE A.
MULLINX
LIBER 38021 FOLIO 377
ZONED: RC-BEO

VEHICULAR INGRESS & EGRESS RESTRICTED

PRESERVATION
(BUILDABLE)
TO BE DONATED TO THE
AGRICULTURAL LAND
PRESERVATION PROGRAM

LOT 2
1.127 AC±

PREVIOUS PARCEL LINE TO BE ABANDONED
BY THE RECORDING OF THIS PLAT

APPROXIMATE
LOCATION
OF EX SEPTIC
FIELD

EX HOUSE
TO BE RAZE

PRIVATE 24' USE IN COMMON ACCESS
EASEMENT TO BENEFIT LOT 1 AND
PRESERVATION PARCEL A'

PRESERVATION
(BUILDABLE)
20.004 AC ±
TO BE DONATED TO THE
AGRICULTURAL LAND
PRESERVATION PROGRAM

A E MULLINX ROAD
LOCAL ROAD
(60' RIGHT-OF-WAY)

WARD COUNTY
PURPOSE OF

