

04-337697

4/22/77

PERMIT

P 28039

A 23875

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH*

HOWARD COUNTY

ELLICOTT CITY

INDEXED

DISTRICT 4th

DATE 5/1/78

7/10/78 final

Jim Brittingham IS PERMITTED TO INSTALL X ALTER _____

ADDRESS Ellicott City, Md. PHONE _____

SUBDIVISION Brantly ROAD 3337 Brantly Road LOT 25

PROPERTY OWNER Brantly Associates

ADDRESS Columbia, Md.

**BUILDING PERMIT SIGNED
AND RETURNED**

SPECIFICATIONS 4 bedrooms

4/22/77 BOON 147646-Deck + Sun Room

SEPTIC TANK CAPACITY 1250 GALLONS

DRAIN FIELD _____ DEPTH _____ FEET. BOTTOM AREA _____ SQ. FT.

DEEP TRENCH _____ DEPTH _____ FEET. BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA 125 SQ. FT. per bedroom

INLET PIPE 4 FT. BELOW ORIGINAL GRADE. MAXIMUM DEPTH 10 FT. BELOW ORIGINAL GRADE

EFFECTIVE DEPTH AT _____ FT. BELOW ORIGINAL GRADE.

LOCATE DISPOSAL AREA 15 FT. FROM 125' LOT LINE AND 115 FT. FROM front LOT LINE AS SEEN WHEN FACING LOT FROM road.

Begin the trench 5 ft. from the edge of the dry well and follow the contour of the land.

The trench will be 2 ft. wide, 10 ft. deep, and contain 6 ft. of stone.

PLANS APPROVED BY Robert Moorefield DATE 8/22/77

COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

NOTE: IF TRENCH IS USED CALL FOR INSPECTION BEFORE PLACING GRAVEL IN TRENCH.

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER, CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED.

***INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT.**

A 23875