

W.P.I. 3/15/85  
P.M. Frspt.

3/18/85 CWeller

3/18/85  
2 Insects  
10:30 AM - P.M.

# PERMIT

P 35099  
A 34115

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH\*

HOWARD COUNTY  
BUREAU OF ENVIRONMENTAL HEALTH  
992-2330

05-352053  
**INDEXED**

ELLICOTT CITY  
DISTRICT 5th  
DATE 3/6/85

Merit Construction Company IS PERMITTED TO INSTALL  ALTER

ADDRESS 2526 Tolley Street, Baltimore, Maryland 21230 PHONE 525-3884

SUBDIVISION Hallowell's Addition ROAD 7029 Mink Hollow Road LOT 3

PROPERTY OWNER Stanley & Harriet Levy

ADDRESS \_\_\_\_\_

IF GARBAGE GRINDER IS USED INCREASE SEPTIC TANK CAPACITY BY 50% AND ABSORPTION AREA BY 22%.

GARBAGE GRINDER? YES \_\_\_\_\_ NO

SEPTIC TANK CAPACITY 1500 GALLONS NUMBER OF BEDROOMS 3

TRENCHES - 158 sq. ft. per bedroom. Trench to be 3 feet wide. Inlet 3½ feet below original grade. Bottom maximum depth 8 feet below original grade. Effective area begins at 3½ feet below original grade. 4½ feet of stone below distribution pipe. LOCATION: Start the first trench 240 feet from the front (321.44') lot line and 165' from the right (1220.94') lot line as seen when facing the property from the pipestem. Run trench(s) along level ground toward the right lot line. NOTE: No trench to exceed 100 feet in length. If more than one trench used, a distribution box is required. Call for inspection of trench(s) before and after gravel is installed. Provide 6" - 8" diameter cleanout and cap to grade or above on septic tank.

PLANS APPROVED BY C. Williams DATE 8/7/84

COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

NOTE: IF TRENCH IS USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH.

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER. NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH.

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 40 PVC OR ABS.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA, OR PVC OR ABS ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET MANHOLE TO GRADE REQUIRED.

**BUILDING PERMIT SIGNED AND RETURNED**

12/16/2002 B00139749 ELEVATOR  
11-8-83 B00144876-46 PROpane TANK

A 34115

**\*INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT**

\*CALL 992-2330 FOR INSPECTION OF SEPTIC SYSTEMS.



