

7/18/96
A.M. c/o
7/11/96
Anytime (permits
card at site)

Tax ID 03-279561

PERMIT

SEWAGE DISPOSAL SYSTEM

DEPARTMENT OF HEALTH AND MENTAL HYGIENE

INDEXED

P 56981

A 45330

DISTRICT 3rd

DATE 4/2/96

DATE SYSTEM APPROVED 7/11/96

INSPECTOR ALM

HOWARD COUNTY HEALTH DEPARTMENT

BUREAU OF ENVIRONMENTAL HEALTH

313-2640

William C. Arrington

IS PERMITTED TO INSTALL ALTER

ADDRESS 1546 Henryton Road, Marriottsville, MD 21104 PHONE _____

SUBDIVISION R. Neville Arrington LOT 1 ROAD 2500³ Pfefferkorn Road

PROPERTY OWNER Bill and Judy Arrington

ADDRESS _____

SEPTIC TANK CAPACITY 1250 GALLONS

NUMBER OF BEDROOMS 4

180 SQUARE FEET PER BEDROOM

LINEAR FEET OF TRENCH REQUIRED 180

TRENCHES - Trench to be 2 feet wide. Inlet 4.5 feet below original grade. Bottom maximum depth 8.5 feet below original grade. Effective area begins at 4.5 feet below original grade. 4 feet of stone below distribution pipe.

LOCATION - Start the first trench 120' from the 150.00' lot line and 130' from the 307.90' lot line. Run trenches on contour toward rear of lot.

NOTES - No trench to exceed 100 feet in length. Provide 6" - 8" diameter cleanout and cap to grade or above on septic tank. *PP 9/17/96*

PLANS APPROVED BY Amy McMillen DATE 3/27/96

COVER NO WORK UNTIL INSPECTED AND APPROVED

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM

NOTE: CLEANOUT REQUIRED EVERY 70 FEET OF SEWER LINE AND/OR AT 90° SWEEPS IN LINES FROM HOUSE TO DRAIN FIELDS, 90° ELBOWS NOT ACCEPTABLE.

NOTE: ALL PARTS OF SEPTIC SYSTEMS (I.E. TANK, DISTRIBUTION BOX TRENCHES) TO BE 100 FEET FROM WELL (UNLESS OTHERWISE SPECIFICALLY AUTHORIZED)

NOTE: IF DEEP TRENCH(ES) ARE USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH(ES)

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 35/40 PVC OR ABS

PERMIT VOID AFTER TWO YEARS

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL STAND PIPES MUST BE 8 INCHES IN DIAMETER CAST IRON. CONCRETE OR TERRA COTTA OR PVA OR ABS ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET. MANHOLE TO GRADE REQUIRED.

NOTE: DISTRIBUTION BOXES MUST HAVE BAFFLES

***INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT**

HD-260(6-90)

***CALL 461-8933 FOR INSPECTION OF SEPTIC SYSTEM.**

A 45330

HOWARD COUNTY HEALTH DEPARTMENT
Completed Septic System

P 56981 A 45330

DATE 6/12/96

LOCATION	<u>R. Neville Arrington Prop.</u>	APPLICATION	
	<u>2500 Pfefferkorn Road</u>	HOLD	()
		APPROVED	(<input checked="" type="checkbox"/>)
		REJECTED	()
LOT	<u>1</u>		
APPLICANT		INSTALLATION	
OWNER	<u>Bill Arrington</u>	HOLD	()
PERMITTEE	<u>" "</u>	APPROVED	(<input checked="" type="checkbox"/>)
HD-11		APPROVED	
		DATE	<u>7/11/96</u>