



Howard County  
Health Department

**Bureau of Environmental Health**

8930 Stanford Boulevard, Columbia, MD 21045

Main: 410-313-2640 | Fax: 410-313-2648

TDD 410-313-2323 | Toll Free 1-866-313-6300

www.hchealth.org

Facebook: www.facebook.com/hocohealth

Maura J. Rossman, M.D., Health Officer

RECEIPT DATE: 3/1/17

**ONSITE SEWAGE DISPOSAL SYSTEM**

P 560563-D

APPROVAL DATE: 10/16/17 (SEC)

**PERMIT: CONSTRUCTION**

A

PROPERTY ADDRESS: 17044 Hardy Road

SUBDIVISION: Shears Property

LOT: 1

TAX ID: 04-598968

CONTRACTOR: South Carroll Backhoe

EMAIL: scbackhoe@comcast.net

CONTRACTOR ADDRESS: 4410 Salem Bottom Road, Westminster, MD 21157

PHONE: 410-596-3618

CONTRACTOR CERTIFIED FOR BAT INSTALLATION:

MDE

MANUFACTURER:

PROPERTY OWNER: M & O Properties LLC

EMAIL: badavidson@uavsolutions.com

OWNER ADDRESS: 13805 Forsythe Road,

PHONE: 410-259-9303

BAT UNIT MODEL: Hoot 600 BNR

PUMP SIZE: 0.5

PUMP TANK CAPACITY: 1500

OPERATION & MAINTENANCE AGREEMENT DATE SIGNED:

DATE RECORDED:

DISTRIBUTION SYSTEM:  GRAVITY

PRESSURE DOSED

BEDROOMS: 5

APPLICATION RATE: 0.8

|           |  |  |
|-----------|--|--|
| TRENCHES: | LINEAR FEET REQUIRED: <u>224</u>   | INLET DEPTH: <u>2.5</u>                    |
|           | TRENCH WIDTH: <u>3</u>   | MAXIMUM BOTTOM DEPTH: <u>4 to 5</u>        |
|           | MINIMUM SPACE BETWEEN TRENCHES: <u>10</u>  | EFFECTIVE AREA BEGINNING DEPTH: <u>2.5</u> |
| LOCATION: | PER APPROVED SITE PLAN. SEWAGE DISPOSAL AREA AND BAT UNIT LOCATION MUST BE STAKED BY LICENSED SURVEYOR PRIOR TO PRE-CONSTRUCTION INSPECTION. |  |
| NOTES:    |  |  |

ISSUED BY: Robert Bricker

ISSUE DATE: 3-1-17

EXPIRATION DATE: 3-1-18

NOTE: CONTRACTOR MUST SCHEDULE A PRE-CONSTRUCTION INSPECTION PRIOR TO BEGINNING ANY INSTALLATION

NOTE: CONTRACTOR MUST SCHEDULE AN INSPECTION AND GAIN APPROVAL OF ALL COMPONENTS PRIOR TO COVERING

NOTE: STONE MUST BE APPROVED BY HEALTH DEPARTMENT AND GRAVEL TICKET MUST BE AVAILABLE FOR REVIEW.

NOTE: WATERTIGHT SEPTIC TANKS REQUIRED

NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE AT LEAST 100 FEET DOWNGRADIENT FROM ANY WATER WELL

NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS

NOTE: AN ELECTRICAL PERMIT IS REQUIRED FOR INSTALLATION OF ANY ELECTRICAL COMPONENTS OF THE SYSTEM

ELECTRICAL PERMIT ISSUED E 1700534

NOTE: AN INDIVIDUAL CERTIFIED BY MDE AND THE MANUFACTURER FOR BAT INSTALLATION MUST BE PRESENT AT ALL TIMES DURING BAT INSTALLATION.

NOTE: MDE RECOMMENDS SEPTIC TANKS, BAT, AND OTHER PRETREATMENT UNITS BE PUMPED AT A FREQUENCY ADEQUATE TO ENSURE THAT SOLIDS ARE NOT DISCHARGED TO THE DISPOSAL AREA


**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.**

**PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT.**

**CALL 410-313-1771 TO SCHEDULE INSPECTIONS.**


NOT TO SCALE

(W) H0-15-0099



| TRENCH/DRAINFIELD DATA  |               |        |
|-------------------------|---------------|--------|
| WIDTH                   | INLET         | BOTTOM |
| 3'                      | 2.5'          | 4'     |
| NUMBER OF TRENCHES      | 7             |        |
| TOTAL LENGTH            | 210'          |        |
| ABSORPTION AREA         | 630' SIDEWALL |        |
| DISTRIBUTION BOX LEVEL  | _____         |        |
| DISTRIBUTION BOX Baffle | _____         |        |
| DISTRIBUTION BOX PORT   | _____         |        |

| SEPTIC TANK DATA             |                  |
|------------------------------|------------------|
| SEPTIC TANK I LEVEL          | YES              |
| MANUFACTURER                 | Meyer Bro / HOOT |
| CAPACITY                     | 1000 GAL         |
| SEAM LOC                     | Top              |
| TANK LID DEPTH               | 2'               |
| BAFFLES                      | Yes              |
| BAFFLE FILTER                | NO               |
| MANHOLE LOC                  | Front            |
| 6" PORT LOC                  | NONE             |
| WATERTIGHT TEST              | ---              |
| SLOTTED                      | NO               |
| DATE ON LID                  | ---              |
| PUMP/SEPTIC TANK LEVEL _____ |                  |
| MANUFACTURER                 | Meyer Bro        |
| CAPACITY                     | 1500 GAL         |
| SEAM LOC                     | TOP              |
| TANK LID DEPTH               | 2'               |
| BAFFLES                      | YES              |
| BAFFLE FILTER                | ---              |
| MANHOLE LOC                  | Front/Back       |
| 6" PORT LOC                  | NONE             |
| WATERTIGHT TEST              | NO               |
| SLOTTED                      | No               |
| DATE ON LID                  | ---              |



PRE-CONSTRUCTION: 5/10/17 Met with S. Carroll on site for layout. Tank stakes and SDA corner stakes present. Some trench stakes missing. Okay to set tanks - need trenches staked prior to layout of trenches. (S) 5/12/17 Lay out trenches from Manifold of first 6 trenches (R)

INSTALLATION: 5/12/17 Connection under footer (S) shot elevations on laterals. Top 3 1A, B, C all w/ in 3" to grade. Need to check area below trench C and re-shoot D. (P) 5/15/2017 on site to see setting of second tank. Marked Top. Goulds WEOST14 pump 1/2 HP. (R) 5/18/2017 Onsite for the installation of french pipes at manifold (S) 5/19/2017 Continuing installation of LPD pipes. (R) Contractors to cover trenches for weekend (S) 5/22/17 Trenches + laterals complete. Got measurements of obs. pipes to house. Need BAT startup + pump and alarm test. (S) 8/10/17 on site for Hoot startup + pump and alarm. Hoot alarm + (See pg. 2)

FINAL INSPECTOR Sarah Collins DATE OF APPROVAL 10/16/17  
8/25/17

Septic Installation Notes Cont'd  
17044 Hardy Rd.

## FILE INQUIRY NOTES

| DATE              | RESULTS OF REVIEW FOR FILE  |
|-------------------|---|
| 8/10/17<br>cont'd | recirculation good. Measured head heights @ lateral turn-ups:<br>IA1 = 12", IA2 = 12", IB1 = 31", IB2 = 30", IC1 = 36", IC2 = 36", ID1 = 36".<br>Called Kenny @ S. Carroll to verify model of pump installed;<br>IA1 and IA2 spec'd to be 2' lateral head. Pump alarm sounds. (S)   |
| 9/5/17            | S. Carroll switched pumps to 1/2 hp high head. Only 10" distal head at upper two lateral turnups.   |
| 10/2/17           | After discussion w/ Engineer, solution was to select different pump make all together. I expressed "valving" the system to break the multiple segments into 2 zones. Informed contractor that 1/2 HP pump to be used, OK to "value" system in manifold or inside tank. (Hand)   |
| 10/11/17          | South Carroll uncovered T at manifold and found it was cracked. Replaced T and started up with original 1/2 hp pump - 18-20" lateral head at TIA1 + TIA2 lateral turnups. S. Carroll will split laterals into zones + install a gate valve at lower zone. (SC)  |
| 10/11/17          | S. Carroll installed a Y in the tank and a gate valve at lower zone. 3" PVC run parallel to original line to lower zone. Gate valve turns 7.5 turns to close; set at 5.75 turns closed. TIA1 + TIA2 lateral heights = 24-26"; IB1 + IB2 = 3'+; IC1 + IC2 = 34"; ID1 = 3'+. Need BAT startup certification. (SC) 10/16/17 BAT startup certification received. (SG) |



**MAYER BROS., INC.**  
 Precast Concrete Products  
 6264 Race Rd. Elkridge, MD 21075

## Letter of Satisfaction Hoot System Installation

Address of Property: 17044 Hardy Rd.  
Mt. Airy, MD, 21771

Date of Final Inspection: 10/13/17

Installer: South Carroll Backhoe Service

Hoot Technician/Inspector: Mike Sample

I hereby certify that the Hoot system installed at the property listed above has been installed according to proper Hoot installation practices. I have also verified the startup of the system and it is in proper working order.

Sincerely,

R. Michael Dwyer  
 Name of Inspector  
 Mayer Bros., Inc.

PH: 410-796-1434

WBE

FX: 410-796-1438

[www.mayerbrosprecast.com](http://www.mayerbrosprecast.com)

Grease Interceptors, Grease Solutions, Aerobic Treatment Units, Septic Tanks, Holding Tanks, Storm Water Structures, Hydroceptors,  
 Bench Barrier, Water Meter Vaults, Sectional Valve Vaults, Top Stalls, Curb Beads, Curb Bumpers,  
 Custom Precast Products

## Wolf, Kevin

---

**From:** Wolf, Kevin  
**Sent:** Monday, August 28, 2017 10:36 AM  
**To:** 'Stephanie Tuite'  
**Subject:** RE: 17044 Hardy Road

Hey Stephanie,

Sorry to hear about all that.

No nothing was resolved. I have had communication with the septic contractor only. I think before we start selecting different pumps, we wanted something from you on the design calcs first.

---

**From:** Stephanie Tuite [mailto:Stephanie@fcc-eng.com]  
**Sent:** Monday, August 28, 2017 9:55 AM  
**To:** Wolf, Kevin  
**Subject:** RE: 17044 Hardy Road

Sorry, I was out Friday with issues with both kids, one getting a cast off and the other being tested for concussion after staples in her head. Crazy.

Did this get resolved Friday?

Steph

Stephanie Tuite, RLA, PE, LEED AP BD&C  
FISHER, COLLINS & CARTER, INC.


**From:** Wolf, Kevin [mailto:KWolf@howardcountymd.gov]  
**Sent:** Friday, August 25, 2017 11:40 AM  
**To:** Stephanie Tuite <Stephanie@fcc-eng.com>  
**Subject:** 17044 Hardy Road

Stephanie,

We have an issue at the above referenced property. The septic system was installed per design specifications but the pressure test revealed only 12" distal head on trenches 1A1, 1A2. Trenches 1B1, 1B2 only got 30" distal head which the plan calls for 33" which is close but I am fine with this. The other trenches got 36"+. The pump that is installed is the one selected on the plan, Goulds WE051H. ½ hp. They recommended going to the ¾ hp pump but I thought that would be too much head. At nearly 70 gpm @ 11' TDH the ¾ hp pump is rated to 40' of head. The builder and septic contractor are both aware.

Thanks,

Kevin M. Wolf, LEHS, REHS/RS  
Groundwater Mgmt. Sec. Supervisor  
Well & Septic Program  
Bureau of Environmental Health  
8930 Stanford Blvd.  
Columbia, MD 21045  
(c) 410-313-2645  
(f) 410-313-2648




Approved Septic System Plan  
 Howard County Health Department  
 Convert kitchen & dining rm.  
 to kitchen, 1/2-bath & pantry  
 300 sq ft modified  
 J. Bricker 11/10/2016  
 Signature Date  
 800 River Road  
 #16004208  
 (online permit)










*Handwritten note:* 4 bedrooms  
OK - YES



**SECOND FLOOR FRAMING PLAN**

SCALE: 1/4" = 1'-0"

1000 SQUARE FEET

7' FLOOR TO FLOOR CLEAR

PERMISSION FROM ARCHITECT: SHALL HAVE OTHER APPROVALS

*Handwritten address:* 17040 Hardy Rd.  
Blanco 3306

THIS DRAWING IS THE PROPERTY OF GBL CUSTOM HOME DESIGN, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. WITHOUT THE WRITTEN PERMISSION OF GBL CUSTOM HOME DESIGN, INC. ALL RIGHTS ARE RESERVED. © 2010 GBL CUSTOM HOME DESIGN, INC.

DATE: 1/4/10

REV: 2/2010

REV: 10/10

GBL CUSTOM HOME DESIGN INC.  
70 BOX 227 FERRISBURG, MO 20948  
PHONE: 417-833-8338

SHEARS PROPERTY  
DAVIDSON SPEC HOME  
ALDER CREEK CONSTRUCTION



Bureau of Environmental Health

8930 Stanford Boulevard, Columbia, MD 21045

Main: 410-313-2640 | Fax: 410-313-2648

TDD 410-313-2323 | Toll Free 1-866-313-6300

[www.hchealth.org](http://www.hchealth.org)

Facebook: [www.facebook.com/hocohealth](https://www.facebook.com/hocohealth)

Twitter: HowardCoHealthDep

Maura J. Rossman, M.D., Health Officer

---

MEMORANDUM

TO: *Charles Alder, Alder Creek, LLC*

FROM: *Robert Bricker, REHS/RS, L.E.H.S.*  
Well & Septic Program

RE: *(17040)*  
*17044 Hardy Road, Potential Basement Bedroom*

DATE: August 23, 2016

---

I have reviewed the floor plans in support of Building Permit *B16003306* for a new home at 17044 Hardy Road and noted that there is a rough-in for a full bathroom in the unfinished basement. Please note that this makes it very likely for one or more rooms to be considered bedrooms upon conversion of the basement to finished living space.


For reference, the following is the bedroom definition in Howard County Code Section 3.801(b):

- (1) Except as provided in paragraph (2) of this subsection, a bedroom is any space in the conditioned area of a dwelling unit or accessory structure that:
  - (i) Is 90 square feet or greater in size;
  - (ii) May be used as a private sleeping area; and
  - (iii) Has at least one window and one interior door.
- (2) If a home office, library, or similar room is proposed, it may not be a bedroom if there is no closet; and
  - (i) The room contains permanently built-in bookcases around the perimeter of the room, desks, and other features that encumber the room;
  - (ii) A minimum 4 foot-wide opening, without doors, into another room;
  - (iii) A half wall (4 foot maximum height) between the room and another room; or
  - (iv) The room is a first floor room or basement area that does not have direct access to full bathrooms or "roughed in" plumbing that would provide direct access to future full bathroom facilities.

The Health Department strongly recommends sizing the onsite sewage disposal system at least one bedroom larger than the existing *five (5)*- bedroom design to accommodate a future finished basement. If you choose to only size for the existing design, any future building permit for a finished basement may be placed on hold until the system is upgraded to accommodate the proposed number of bedrooms. This memo will be retained in the Health Department file for future reference.

**GENERAL NOTES:**

- 1) THIS LOCATION DRAWING IS PREPARED FOR THE BENEFIT OF THE CLIENT SIGNING THE HOUSE LOCATION SURVEY APPROVAL FORM INSOFAR AS IT IS REQUIRED BY A LENDER OR TITLE INSURANCE COMPANY OR ITS AGENTS IN CONNECTION WITH THE CONTEMPLATED TRANSFER, FINANCING OR REFINANCING OF THE PROPERTY SHOWN HEREON. UNLESS INDICATED AS BEING A BOUNDARY SURVEY, THIS LOCATION DRAWING IS NOT INTENDED FOR USE IN THE ESTABLISHMENT OF PROPERTY LINES AND IS NOT TO BE RELIED UPON FOR THE ESTABLISHMENT OR LOCATIONS OF FENCES, GARAGES, BUILDINGS OR OTHER EXISTING OR FUTURE IMPROVEMENTS. AS A RESULT, THIS LOCATION DRAWING DOES NOT PROVIDE FOR ACCURATE IDENTIFICATION OF PROPERTY LINES, BUT SUCH IDENTIFICATION MAY NOT BE REQUIRED FOR THE TRANSFER OF TITLE OR SECURING FINANCING FOR RE-FINANCING.
- 2) SUBJECT PROPERTY IS SHOWN IN ZONE X ON THE NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP OF HOWARD COUNTY, MARYLAND, COMMUNITY PANEL No. 24027C00300 EFFECTIVE NOV. 6, 2013.
- 3) THE OFFSETS FROM BUILDING LINE TO PROPERTY LINE AS SHOWN ON THE PLAT HEREON ARE TO AN ACCURACY OF PLUS OR MINUS 1' (+)
- 4) NO TITLE REPORT FURNISHED. SUBJECT TO ALL EASEMENTS, RIGHTS OF WAY AND CONDITIONS OF RECORD.
- 5) THE EXISTING WELL(S) SHOWN ON THIS PLAN (IDENTIFIED WITH THE ATTACHED WELL TAG NUMBER HO-15-0099 HAS BEEN FIELD LOCATED BY FISHER, COLLINS AND CARTER, INC. PROFESSIONAL LAND SURVEYORS AND IS ACCURATELY SHOWN.
- 6) PROFESSIONAL CERTIFICATION: I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED BY ME OR UNDER MY RESPONSIBLE CHARGE, AND THAT I AM A DULY LICENSED PROPERTY LINE SURVEYOR UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 339, EXPIRATION DATE 10/04/2018.
- 7) BUILDING PERMIT #B-16003306




DETAIL:  
1" = 20'

RICHARD C. RIDGEWAY  
JOAN C RIDGEWAY  
LIBER 3805 FOLIO 680  
LOT "J" POPLAR HEIGHTS SUBDIVISION  
PLAT BOOK 3, FOLIO 26

PHILLIP R. HOWARD  
MEREDITH J.V. HOWARD  
LIBER 2043 FOLIO 207  
PART OF LOT "I"  
POPLAR HEIGHTS SUBDIVISION  
PLAT BOOK 3, FOLIO 26

RALPH E. MAYNE  
INA M. MAYNE  
LIBER 1286, FOLIO 162  
LOTS 37 THRU 40  
POPLAR HEIGHTS SUBDIVISION  
PLAT BOOK 3, PAGE 26



(DEED B&D APPEARS TO CONTAIN MATHEMATICAL ERRORS)  
N16°20'14"W 60.32'  
N68°11'47"W 60.32 (COMPUTED)

3/1/17  
Wall check  
okay - H.O.

#17044 HARDY ROAD  
(DEED REFERENCE: LIBER 16709, FOLIO 034)  
FOURTH ELECTION DISTRICT  
HOWARD COUNTY, MARYLAND

**HOUSE LOCATION DRAWING**

FOUNDATION LOCATION: 1/31/17  
FINAL LOCATION: \_\_\_\_\_  
BOUNDARY SURVEY: \_\_\_\_\_  
SCALE: 1" = 50'  
DATE: 2/6/17  
DRAWN BY: J.M.P.  
CHECKED BY: M.L.R.  
PROJECT No.: 05075-6005



Mark L. Robel  
PROPERTY LINE SURVEYOR  
REG. #339  
DATE 2/06/17

#17044 HARDY ROAD  
B.R.L. = BUILDING RESTRICTION LINE  
TOP OF FOUNDATION ELEVATION = 731.1'±

| LOW PRESSURE DOSING SYSTEM - INITIAL INSTALLATION |              |                   |                    |                          |                           |           |                             |                          |                    |                        |
|---|--------------|-------------------|--------------------|--------------------------|---------------------------|-----------|-----------------------------|--------------------------|--------------------|------------------------|
| TRENCH  | GROUND ELEV. | PIPE INVERT ELEV. | TRENCH LENGTH (FT) | LATERAL PIPE LENGTH (FT) | PERFORATION DIAMETER (IN) | HEAD (FT) | PERFORATION FLOW RATE (GPM) | PERFORATION SPACING (FT) | NUMBER OF ORIFICES | TRENCH FLOW RATE (GPM) |
| 1A1   | 723.0        | 720.5             | 32                 | 29.34                    | 5/16                      | 2         | 1.63                        | 5.33                     | 6                  | 9.78                   |
| 1A2   | 723.0        | 720.5             | 32                 | 29.34                    | 5/16                      | 2         | 1.63                        | 5.33                     | 6                  | 9.78                   |
| 1B1   | 722.2        | 719.7             | 32                 | 28.80                    | 5/16                      | 2.8       | 1.92                        | 6.40                     | 5                  | 9.60                   |
| 1B2   | 722.2        | 719.7             | 32                 | 28.80                    | 5/16                      | 2.8       | 1.92                        | 6.40                     | 5                  | 9.60                   |
| 1C1   | 721.3        | 718.8             | 32                 | 29.72                    | 1/4                       | 3.7       | 1.42                        | 4.57                     | 7                  | 9.94                   |
| 1C2   | 721.3        | 718.8             | 32                 | 29.72                    | 1/4                       | 3.7       | 1.42                        | 4.57                     | 7                  | 9.94                   |
| 1D1   | 720.3        | 717.8             | 32                 | 29.34                    | 1/4                       | 4.7       | 1.60                        | 5.33                     | 6                  | 9.60                   |
| TOTAL TRENCH FLOW RATE                            |              |                   |                    |                          |                           |           |                             |                          |                    | 68.20                  |

| TRENCH DESIGN |              |                    |                   |                            |                |                        |                           |                     |                       |                |
|---------------|--------------|--------------------|-------------------|----------------------------|----------------|------------------------|---------------------------|---------------------|-----------------------|----------------|
| TRENCH        | GROUND ELEV. | TOP OF STONE ELEV. | PIPE INVERT ELEV. | DEPTH TO STONE FROM GROUND | DEPTH OF STONE | BOTTOM OF TRENCH ELEV. | EFFECTIVE DEPTH STARTS AT | EFFECTIVE DEPTH (D) | WIDTH OF TRENCHES (W) | TRENCH SPACING |
| 1A1           | 723.0        | 721.0              | 720.5             | 2.0'                       | 2.0'           | 719.0                  | 2.5'                      | 1.5'                | 3.0'                  | 10'            |
| 1A2           | 723.0        | 721.0              | 720.5             | 2.0'                       | 2.0'           | 719.0                  | 2.5'                      | 1.5'                | 3.0'                  | 10'            |
| 1B1           | 722.2        | 720.2              | 719.7             | 2.0'                       | 2.0'           | 718.2                  | 2.5'                      | 1.5'                | 3.0'                  | 10'            |
| 1B2           | 722.2        | 720.2              | 719.7             | 2.0'                       | 2.0'           | 718.2                  | 2.5'                      | 1.5'                | 3.0'                  | 10'            |
| 1C1           | 721.3        | 719.3              | 718.8             | 2.0'                       | 3.0'           | 716.3                  | 2.5'                      | 1.5'                | 3.0'                  | 10'            |
| 1C2           | 721.3        | 719.3              | 718.8             | 2.0'                       | 3.0'           | 716.3                  | 2.5'                      | 1.5'                | 3.0'                  | 10'            |
| 1D1           | 720.3        | 718.3              | 717.8             | 2.0'                       | 3.0'           | 715.3                  | 2.5'                      | 1.5'                | 3.0'                  | 10'            |


\* THE RANGE OF EFFECTIVE DEPTH IS ANTICIPATED TO BE 1 FT TO 2 FT, OR GREATER.

**SEWAGE DISPOSAL SYSTEM DATA**  
 2 BEDROOMS  
 LOADING RATE = 5 BEDROOMS X 150 GPD/BEDROOM = 750 GPD  
 APPLICATION RATE = 0.8  
 EFFECTIVE SIDEWALL BEGINS AT 2.5 FEET  
 TRENCH DEPTH = 4 FEET  
 TRENCH WIDTH (W) = 3 FEET  
 EFFECTIVE DEPTH (D) = 1.5 FEET  
 SF OF DRAINFIELD = 750 GPD / 0.8 = 937.5 SF  
 COEFFICIENT OF REDUCTION OF TRENCH LENGTH =  $(W+2)/(W+1+2D) = (3+2)/(3+1+(2x1.5)) = 0.714$   
 TRENCH LENGTH =  $937.5 SF \times 0.714 / 3 = 223.1$  FEET (USE 224 FEET)  
 TRENCH SPACING =  $2D+W = ((2x1.5) + 3) = 6$  USE 10'

**SEPTIC SYSTEM ELEVATIONS**  
 FFE = 731.60  
 BSE = 721.76  
 INV. OUT OF HOUSE = 718.91  
 PROP. GROUND AT CO = 723.00  
 INV. INTO CO = 718.80  
 INV. OUT OF CO = 718.78  
 EX. GROUND AT BAT = 721.16  
 TOP OF BAT = 719.22  
 COVER OVER BAT = 2.05  
 INV. INTO BAT = 718.28  
 INV. OUT OF BAT = 717.78  
 EX. GROUND AT PUMP TANK = 721.6  
 TOP OF PUMP TANK = 718.61  
 COVER OVER PUMP TANK = 3 FT  
 INV. INTO PUMP TANK = 717.78

- BAT NOTES**
- ANY CHANGE TO THE LOCATIONS OR DEPTHS TO ANY COMPONENTS MUST BE APPROVED BY THE ENGINEER AND THE HOWARD COUNTY HEALTH DEPARTMENT PRIOR TO INSTALLATION. A REVISED SITE PLAN MAY BE REQUIRED.
  - THE MAXIMUM COVER OVER THE BAT SHALL BE 3 FEET.
  - THE BAT SYSTEM SHALL BE MAINTAINED AND OPERATED FOR THE LIFE OF THE SYSTEM.
  - THE BAT SYSTEM SHALL BE OPERATED BY A PERSON TRAINED BY A CERTIFIED SERVICE PROVIDER.
  - WITHIN ONE MONTH OF INSTALLATION, A PERSON INSTALLING THE BAT SYSTEM SHALL REPORT TO THE MARYLAND DEPARTMENT OF THE ENVIRONMENT (MDE) IN A MANNER ACCEPTABLE TO MDE, THE ADDRESS AND DATE OF COMPLETION OF THE BAT INSTALLATION AND THE TYPE OF BAT INSTALLED.
  - ANY ELECTRICAL WORK FOR THE BAT INSTALLATION MUST BE PERFORMED BY A LICENSED ELECTRICIAN. AN AGREEMENT AND EASEMENT HAS BEEN COMPLETED AND SIGNED BY ALL APPLICABLE PARTIES, AND RECORDED IN THE LAND RECORDS OF HOWARD COUNTY.
  - THE HEALTH DEPARTMENT REQUIRES DOCUMENTATION FOR THE START-UP CERTIFICATION FROM THE MANUFACTURER PRIOR TO FINAL APPROVAL OF THE INSTALLATION.
  - SURFACE RUNOFF SHALL BE DIRECTED AROUND THE BAT TANK.


- LEGEND**
- EXISTING 2' CONTOURS
  - EXISTING 10' CONTOURS
  - EXISTING TREE LINE
  - SOIL LINES AND TYPES
  - ⊙ DENOTES PROPOSED WELL
  - ⊙ DENOTES 1500 sq.ft. ALTERNATE WELL SITE
  - DENOTES FAILED PERC
  - DENOTES PASSED PERC



| SOILS LEGEND |   |       |
|--------------|---|-------|
| SOIL         | NAME  | CLASS |
| GgA          | Glenelg loam, 0 to 3 percent slopes               | B     |
| GgB          | Glenelg loam, 3 to 8 percent slopes               | B     |
| GgC          | Glenelg loam, 8 to 15 percent slopes              | B     |
| GnB          | Glenville-Balle silt loams, 0 to 8 percent slopes | C     |

**FISHER, COLLINS & CARTER, INC.**  
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS  
 CENTENNIAL SQUARE OFFICE PARK - 10272 BALTIMORE NATIONAL PIKE  
 ELLICOTT CITY, MARYLAND 21042  
 (410) 461-3995

**OWNER AND DEVELOPER**  
 M&O PROPERTIES, LLC  
 13805 FORSYTHE ROAD  
 SYKESVILLE, MARYLAND 21784



**VICINITY MAP**  
 SCALE: 1" = 1200'  
 MAP PAGE 4691 GRID B6

- GENERAL NOTES**
- SUBJECT PROPERTY ZONED: RC-DEO
  - TOTAL AREA OF PROPERTY: 40,000 SQ.FT. OR 0.92 AC.
  - SEPTIC EASEMENT SUBJECT TO HOWARD COUNTY HEALTH DEPARTMENT REVIEW.
  - CONTRACTOR/BUILDER TO VERIFY ELEVATION IN THE FIELD BEFORE BEGINNING ANY CONSTRUCTION.
  - BOUNDARY IS BASED ON A FIELD RUN BOUNDARY CONDUCTED BY FISHER, COLLINS & CARTER, INC. DATED APRIL, 2010.
  - TOPOGRAPHY SHOWN HEREON BASED ON FIELD RUN SURVEY CONDUCTED BY FISHER, COLLINS & CARTER, INC. DATED APRIL, 2010. TOPOGRAPHY IN NON-DEVELOPED AREAS IS BASED ON HOWARD COUNTY 200 SCALE TOPOGRAPHY.
  - NO WETLANDS EXIST ON THIS LOT.
  - SURFACE RUNOFF SHALL BE DIRECTED AROUND THE BAT TANK.
  - AT HIGH WATER ALARM PROBE, PUMP WILL HAVE CONTINUOUS OPERATION UNTIL LEVEL GOES BENEATH PROBE.
  - IF WATER LEVEL RISES ABOVE THE ALARM PROBE, AN AUDIBLE AND VISUAL ALARM WILL SOUND. SEE MANUFACTURER SPECS FOR ADDITIONAL INFORMATION.
  - ALARM TO BE WIRED TO A CIRCUIT SEPARATE FROM THE PUMP CIRCUIT.

- NOTE**
- THE EXISTING WELLS SHOWN ON THIS PLAN, HO-15-0099 AND WELL WITH NO TAG NUMBER, HAVE BEEN FIELD LOCATED BY FISHER, COLLINS & CARTER, INC., PROFESSIONAL LAND SURVEYORS AND IS ACCURATELY SHOWN.
  - THE MANUFACTURER HAS CERTIFIED THE PROPOSED BAT UNIT, THE HOOT BINK WITH 1500 GALLON PUMP CHAMBER, TO BE APPROPRIATE FOR THIS 6-BEDROOM HOMES AS LONG AS THERE ARE NO MORE THAN 7 FULL TIME OCCUPANTS IN THE HOME.

**FRICTION LOSS IN 3" PIPE FITTINGS:**

|             |                         |                               |
|-------------|-------------------------|-------------------------------|
| 1 UNION     | x 4 FEET PER FITTING =  | 4 EQUIVALENT FEET OF 3" PIPE  |
| 1 1/2" HB   | x 6 FEET PER FITTING =  | 6 EQUIVALENT FEET OF 3" PIPE  |
| 5 ELBOWS    | x 12 FEET PER FITTING = | 60 EQUIVALENT FEET OF 3" PIPE |
| 2 TEE/CROSS | x 17 FEET PER FITTING = | 34 EQUIVALENT FEET OF 3" PIPE |

**TOTAL LINEAR FEET OF 3" SCH. 40 PVC = 104 LF (EQUIVALENT FEET)**  
 3" PIPE TOTAL = 104 LF + 73.2 LF = 177.2 LF

**DYNAMIC HEAD**  
 177.2 LF X 0.73 FT PER 100 LF OF 3" PIPE = 1.3 FT OF FRICTION HEAD  
 DIST. HEAD = 2.0 FT  
 TOTAL DYNAMIC HEAD = 3.3 FT OF FRICTION HEAD

**VERTICAL FROM PUMP OFF TO HIGH POINT IN PUMP CHAMBER = 5.9 FT OF FRICTION HEAD**  
 HIGH POINT IN PUMP CHAMBER TO HIGHEST ELEV OF SYSTEM = 0.5 FT  
 SAFETY FACTOR FOR FRICTION IN LATERALS NOT CALCULATED = 1.5 FT  
**TOTAL DYNAMIC HEAD = 11.2 FT**

**PIPE VOLUMES**  
 91 LF (3" SCH. 40 PIPE) X 38.4 GALLONS PER 100 LF = 34.9 GALLONS  
 200.3 LF (1.5" SCH. 40 PIPE) X 10.6 GALLONS PER 100 LF = 21.2 GALLONS


**MINIMUM DOSE**  
 MINIMUM DOSE = (5 X LATERAL PIPE VOLUME) + (FORCE MAIN & MANIFOLD)  
 = (5 X 21.2) + (34.9)  
 = 140.5 GALLONS

140.5 GALLONS IS MORE THAN 1/6 DESIGN FLOW (750/6=125)  
 USE 272.8 GALLON DOSE (140.5 GALLON MINIMUM)  
 (RUN TIME = 4 MIN (68.2 GPM X 4 = 272.8 GALLON DOSE))

PUMP NEEDS TO HANDLE 68.2 GPM AT 11.2 FT OF HEAD  
 USE 3/8 HP (WED99H PUMP)


*Approved System Plan  
 Howard County Health Department  
 AOST 600 BNR w/ 1500-gal Pump Chamber  
 3.0.5hp Pump or equiv.  
 R. Bickler 11/9/2016  
 17240 Hardy Rd  
 316003306*

**PROFESSIONAL CERTIFICATION**  
 I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 38386, EXPIRATION DATE: 01/12/2018.




**BAT PLAN  
 SHEARS PROPERTY  
 LOT 1**  
 A RESUBDIVISION OF POPLAR HEIGHTS SUBDIVISION  
 LOT 41-44 A5 RECORDED IN THE LAND RECORDS AS  
 PLAT No. 3, FOLIO 26

TAX MAP #7 GRID: 8 PARCEL: 31  
 FOURTH ELECTION DISTRICT HOWARD COUNTY, MARYLAND  
 SCALE: 1" = 30' DATE: NOVEMBER, 2016  
 SHEET 1 OF 2



NOTE: ALARM PROBE SHOWN IS BASED ON A STANDARD SEPARATION BETWEEN PUMP ON, PUMP OFF, AND THE HIGH WATER ALARM. THESE ARE PRESET AT TIME OF MANUFACTURING. BOTH RECIRCULATING PUMP AND DISCHARGE PUMP TO BE LINKED TO THE SAME ALARM. FLOATS TO BE PROVIDED FOR DISCHARGE PUMP.




NOTE: PLACE AN OBSERVATION PIPE IN THE GRAVEL BED AT THE DISTAL END OF EACH TRENCH SEGMENT.

**PUMP TANK ELEVATIONS**



|     |                                       |
|-----|---------------------------------------|
| A = | 721.0                                 |
| B = | 717.70 (INV. INTO TANK)               |
| C = | 713.53                                |
| D = | 713.06                                |
| E = | 715.11                                |
| F = | 716.36                                |
| G = | 716.06                                |
| H = | 710.61                                |
| I = | 719.6 (INV. OUT OF TANK)              |
| J = | 720.0 (HIGHEST POINT IN PUMP CHAMBER) |

COVER OVER PUMP TANK = 3 FT


NOTE: SEPTIC SYSTEM ALARM WILL BE ON A CIRCUIT SEPARATE FROM ANY OTHER SEPTIC SYSTEM COMPONENTS OR ALARMS.




NOTE: CONFIGURATION SHOWN FOR ILLUSTRATIVE PURPOSES. FLOATS TO BE SET TO SAME ELEVATIONS OF ALARM PROBE.




**PUMP DISCHARGE DETAIL**  
 NOT TO SCALE



\* THE RANGE OF EFFECTIVE DEPTH IS ANTICIPATED TO BE 1 FT TO 2 FT, OR GREATER FOR TRENCHES 1C1, 1C2, AND 1D1.



NOTE: USE BLASTER PUMP (EPO 511) FOR RECIRCULATION TO BAT TANK



**GOULDS PUMPS**  
 Wastewater



Wastewater

**APPLICATIONS**  
 Specifically designed for the following uses:  
 • Homes, Farms, Trailer Courts, Motels, Schools, Hospitals, Industry, Effluent Systems

**SPECIFICATIONS**  
 Pump  
 • Solids handling capabilities: 1/2" maximum.  
 • Discharge size: 2" NPT.  
 • Capacity: up to 140 GPM.  
 • Total heads: up to 128 feet TDH.  
 • Temperature: 104°F (40°C) continuous, 140°F (60°C) intermittent.  
 • See order numbers on reverse side for specific HP, voltage, phase and RPM's available.

**MOTORS**  
 • Fully submerged in high-grade turbine oil for lubrication and efficient heat transfer.  
 • Class B insulation on 1/2 - 1 1/2 HP models.  
 • Class F insulation on 2 HP models.  
 • Single phase (60 Hz):  
 • Capacitor start motors for maximum starting torque.  
 • Built-in overload with automatic reset.  
 • SITOW or SITOW severe duty oil and water resistant power cords.

• 1/2 - 1 HP models have NEMA three prong grounding plugs.  
 • 1 1/2 HP and larger units have bare lead cord ends.  
 • Three phase (60 Hz):  
 • Class 1D overload protection must be provided in separately ordered starter unit.  
 • SITOW power cords all have bare lead cord ends.  
 • Designed for Continuous Operation: Pump ratings are within the motor manufacturer's recommended working limits, can be operated continuously without damage when fully submerged.  
 • Bearings: Upper and lower heavy duty ball bearing construction.  
 • Power Cable: Severe duty rated, oil and water resistant. Epoxy seal on motor end provides secondary moisture barrier in case of outer jacket damage and to prevent oil wicking. Standard cord is 20'. Optional lengths are available.  
 • O-ring: Assures positive sealing against contaminants and oil leakage.



**AGENCY LISTINGS**  
 Listed to ITT and Class 213 198 Standards by Canadian Standards Association File #183889  
 Goulds Pumps is ISO 9001 Registered

**PERFORMANCE RATINGS (gallons per minute)**

| Model | 1150 | 1750 | 2500 | 3500 | 3500 | 3500 | 3500 | 3500 | 3500 |
|-------|------|------|------|------|------|------|------|------|------|
| 1150  | 1150 | 1150 | 1150 | 1150 | 1150 | 1150 | 1150 | 1150 | 1150 |
| 1750  | 1750 | 1750 | 1750 | 1750 | 1750 | 1750 | 1750 | 1750 | 1750 |
| 2500  | 2500 | 2500 | 2500 | 2500 | 2500 | 2500 | 2500 | 2500 | 2500 |
| 3500  | 3500 | 3500 | 3500 | 3500 | 3500 | 3500 | 3500 | 3500 | 3500 |

**COMPONENTS**

| Part No. | Description     |
|----------|-----------------|
| 1        | Motor           |
| 2        | Casing          |
| 3        | Mechanical Seal |
| 4        | Motor Shaft     |
| 5        | Motor           |
| 6        | Ball Bearing    |
| 7        | Power Cable     |
| 8        | Casing Outlet   |




GOULDS PUMPS  
 Goulds Pumps and the ITT Engineered B&S Symbol are registered trademarks and trademarks of ITT Corporation. SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE.

Engineered for life

**OWNER AND DEVELOPER**

M&O PROPERTIES, LLC  
 13805 FORSYTHE ROAD  
 SYKESVILLE, MARYLAND 21784



LPD PUMP

**FISHER, COLLINS & CARTER, INC.**  
 CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS  
 CENTRAL SQUARE OFFICE PARK - 10272 BALTIMORE NATIONAL FILE  
 ELICOTT CITY, MARYLAND 21042  
 410.451.1000

NOTE: SEE PLAN VIEW FOR LATERAL PIPE CONFIGURATION / HORIZONTAL BENDS, DETAIL TO SHOW SPACING AND TURN UPS ONLY.

FIGURE 4.1 MANIFOLD DISTRIBUTION NETWORK

**PROFESSIONAL CERTIFICATION**

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 38386, EXPIRATION DATE: 01/12/2016.

*Stephanie J. Jurek* 11/4/16  
 Signature Of Professional Engineer DATE

Approved Septic System Plan  
 Howard County Health Department  
 HOOT 600 BNR w/1500 gal Pump Chamber  
 ± 0.5' up Pump or equivalent to LPD  
 Signature: *R. Bricker* 11/4/2016  
 Date: 11/4/2016  
 17040 Hardy Rd.  
 B16003304

**SEPTIC SYSTEM PROFILE**

SCALE: HORIZ. 1" = 30'  
 VERT. 1" = 3'

**BAT PLAN**

**SHEARS PROPERTY**  
 LOT 1

A RESUBDIVISION OF POPLAR HEIGHTS SUBDIVISION  
 LOT 41-44 AS RECORDED IN THE LAND RECORDS AS  
 PLAT No. 3, FOLIO 26

TAX MAP #7 GRID: 8 PARCEL: 31  
 FOURTH ELECTION DISTRICT - HOWARD COUNTY, MARYLAND  
 SCALE: 1"=30' DATE: NOVEMBER, 2016  
 SHEET 2) OF 2

