



HOWARD COUNTY HEALTH DEPARTMENT

63987-A

DATE 8/21/18

05

Received From

South Carroll Bank

PHONE #

410-596-3010

CASH
 CHECK

For

Septric Service - 13520 Arden Drive

BAT System BCF - 7510 Browns Boogie Rd

NO.

53456


Five thousand six hundred one ⁰⁰/₁₀₀ Dollars

\$

561.00

Received By

[Signature]



Bureau of Environmental Health
 8930 Stanford Boulevard, Columbia, MD 21045
 Main: 410-313-2640 | Fax: 410-313-2648
 TDD 410-313-2323 | Toll Free 1-866-313-6300
www.hchealth.org
 Facebook: www.facebook.com/hocohealth

Maura J. Rossman, M.D., Health Officer

RECEIPT DATE: 8/21/2018 **ONSITE SEWAGE DISPOSAL SYSTEM** P 563987

APPROVAL DATE: 1/2/19 SEC **PERMIT: BRF REPAIR** A 563006

PROPERTY ADDRESS: 7510 Browns Bridge Road

SUBDIVISION: Greenwood Farms LOT: 11 TAX ID: 05-355346

CONTRACTOR: South Carroll Backhoe EMAIL: skbackhoe@comcast.net

CONTRACTOR ADDRESS: 4410 Salem Bottom Road, Westminster MD PHONE: 410-596-3618

CONTRACTOR CERTIFIED FOR BAT INSTALLATION: MDE MANUFACTURER: Hoot

PROPERTY OWNER: Carol Hill EMAIL: Carolann663@gmail.com

OWNER ADDRESS: 7510 Browns Bridge Road PHONE: 301-704-4787

BAT UNIT MODEL: HOOT BNR 600 PUMP SIZE: _____ PUMP TANK CAPACITY: _____

OPERATION & MAINTENANCE AGREEMENT DATE SIGNED: 8/24/2018 DATE RECORDED: 8/24/2018


DISTRIBUTION SYSTEM: GRAVITY PRESSURE DOSED BEDROOMS: 4 APPLICATION RATE: 1.2

TRENCHES:	LINEAR FEET REQUIRED: <u>104</u>	INLET DEPTH: <u>2.5'</u>
	TRENCH WIDTH: <u>2</u>	MAXIMUM BOTTOM DEPTH: <u>7.5'</u>
	MINIMUM SPACE BETWEEN TRENCHES: <u>n/a</u>	EFFECTIVE AREA BEGINNING DEPTH: <u>5.5</u>
LOCATION:	TO BE STAKED BY SANITARIAN DURING PRE-CONSTRUCTION INSPECTION.	
NOTES:	Trenches and BAT location staked in field. Must have start-up certification letter from BAT manufacturer and startup of system prior to septic permit approval. <u>4x26' Trenches.</u>	

ISSUED BY: Kevin Wolf ISSUE DATE: 8/21/2018 EXPIRATION DATE: 8/21/2019

- NOTE: CONTRACTOR MUST SCHEDULE A PRE-CONSTRUCTION INSPECTION PRIOR TO BEGINNING ANY INSTALLATION
- NOTE: CONTRACTOR MUST SCHEDULE AN INSPECTION AND GAIN APPROVAL OF ALL COMPONENTS PRIOR TO COVERING
- NOTE: STONE MUST BE APPROVED BY HEALTH DEPARTMENT AND GRAVEL TICKET MUST BE AVAILABLE FOR REVIEW.
- NOTE: WATERTIGHT SEPTIC TANKS REQUIRED
- NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE AT LEAST 100 FEET DOWNGRADE FROM ANY WATER WELL
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS
- NOTE: AN ELECTRICAL PERMIT IS REQUIRED FOR INSTALLATION OF ANY ELECTRICAL COMPONENTS OF THE SYSTEM
 ELECTRICAL PERMIT ISSUED E 1800445
- NOTE: THE HCHD DOES NOT WARRANTY ANY SYSTEM AND CANNOT GUARANTEE THE PERFORMANCE OF THIS SYSTEM AS DESIGNED. BY ACCEPTING THIS PERMIT, THE OWNER AND/OR APPLICANT ACKNOWLEDGE THAT THE SPECIFICATIONS DETAILED IN THIS DESIGN ARE ONE POSSIBLE OPTION AND THAT THE HCHD WILL REVIEW OTHER PROPOSALS. YOU HAVE THE OPTION TO SEEK THE ADVICE OF A QUALIFIED DESIGN CONSULTANT OR PROFESSIONAL ENGINEER FOR FURTHER GUIDANCE.
- NOTE: AN INDIVIDUAL CERTIFIED BY MDE AND THE MANUFACTURER FOR BAT INSTALLATION MUST BE PRESENT AT ALL TIMES DURING BAT INSTALLATION.
- NOTE: MDE RECOMMENDS SEPTIC TANKS, BAT, AND OTHER PRETREATMENT UNITS BE PUMPED AT A FREQUENCY ADEQUATE TO ENSURE THAT SOLIDS ARE NOT DISCHARGED TO THE DISPOSAL AREA

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.
 PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT.
 CALL 410-313-1771 TO SCHEDULE INSPECTIONS.**



TRENCH/DRAINFIELD DATA		
WIDTH	INLET	BOTTOM
2'	2.5'	7.5'
NUMBER OF TRENCHES	4	
TOTAL LENGTH	102'	
ABSORPTION AREA	204' + SIDEWALL	
DISTRIBUTION BOX LEVEL	YES	
DISTRIBUTION BOX BAFFLE	YES	
DISTRIBUTION BOX PORT	YES	

SEPTIC TANK DATA	
SEPTIC TANK I LEVEL	YES
MANUFACTURER	MAYER BROS./HOOT
CAPACITY	1500 GAL
SEAM LOC	TOP
TANK LID DEPTH	1.5-2'
BAFFLES	YES
BAFFLE FILTER	NO
MANHOLE LOC	FRONT + REAR
6" PORT LOC	NONE
WATERTIGHT TEST	NO
SLOTTED	NO
DATE ON LID	—

PUMP/SEPTIC TANK LEVEL	
MANUFACTURER	—
CAPACITY	— GAL
SEAM LOC	—
TANK LID DEPTH	—
BAFFLES	—
BAFFLE FILTER	—
MANHOLE LOC	—
6" PORT LOC	—
WATERTIGHT TEST	—
SLOTTED	—
DATE ON LID	—

PRE-CONSTRUCTION:

6/7/18 No real layout given. Tried to make something work around perc A but not conventional (will be non-conventional). Owners wanted to try front yard but limited area (i.e. power lines, well etc, etc). Will have more utility mark lines set first. (KMD)

8/10/18 New contractor selected from owner. Laid out trenches (4x26') in upper left part of property. Will be placed inside both well areas.

INSTALLATION: Got BAT unit off to side of house. Call for signature (KMD)

12/17/18 S. Carroll installing sewer line. Tank hole partially dug, water @ 8' and seepage 6.5-7' (depths measured at inlet end). (SC) 12/18/18 Tank set, S. Carroll connecting Hoot system. (SC)

12/18/18 T4 installed and left open at ends for inspection. 2' wide - 2-2.5' to stone. S. Carroll digging T3. 7.5' bottom and soil slightly moist at bottom. Using laser to check depths. (SC)

12/19/18 Trenches complete. T1 left open for inspection. T2 left open @ ends. 2' wide, 2-2.5' to stone. Drywells + old tank to be abandoned today. Need Hoot startup and pump + alarm test. (SC) 12/20/18 On site with Mike Sample + S. Carroll for Hoot startup. Hoot system is running, pump pumps effluent to D-box. Alarm sounds. Need BAT startup certification + drywells abandoned. (SC)

FINAL INSPECTOR Sarah Collins DATE OF APPROVAL 1/2/19

1/2/19 Drywells abandoned. BAT startup certification received (SC)



MAYER BROS., INC.

Precast Concrete Products

6264 Race Rd. Elkridge, MD 21075

Letter of Satisfaction Hoot System Installation

Address of Property: 7510 Browns Bridge Rd.
Highland, MD. 20777

Date of Final Inspection: 12/20/10

Installer: South Carroll Backhoe Service

Hoot Technician/Inspector: Mike Sample

I hereby certify that the Hoot system installed at the property listed above has been installed according to proper Hoot installation practices. I have also verified the startup of the system and it is in proper working order.

Sincerely,

H. Michael Mayer

Name of Inspector
Mayer Bros., Inc.

PH: 410-796-1434

FX: 410-796-1438

WBE

www.mayerbrosprecast.com

Clerk of the Circuit Court for
Howard County
Land Records/Licensing

The Thomas Dorsey Building
9250 Bendix Road
Columbia, MD 21045
410-313-5850

=====

LR - Agreement Recording Fee			
	1x	20.00	20.00

Name: Hill
Ref: 10

LR - Agreement Surcharge

	1x	40.00	40.00
--	----	-------	-------

=====


SubTotal:			60.00
Total:			60.00

=====

REV-Check-BOA			60.00
Number : 2035			

08/24/2018 12:24 CC13-DS
#10880434/1246/109

~ Thank you for visiting us today ~



Bureau of Environmental Health

8930 Stanford Boulevard, Columbia, MD 21045

Main: 410-313-2640 | Fax: 410-313-2648

TDD 410-313-2323 | Toll Free 1-866-313-6300

www.hchealth.org

Facebook: www.facebook.com/hocohealth

Twitter: HowardCoHealthDep

Maura J. Rossman, M.D., Health Officer

**AGREEMENT AND EASEMENT FOR INSTALLATION
OF BEST AVAILABLE TECHNOLOGY SYSTEMS
WITH BAY RESTORATION FUNDS.**

THIS AGREEMENT is made this 24th day of August, 2018, among CHRISTOPHER & CAROL HILL hereinafter referred to as "Owner," the Howard County Health Department hereinafter collectively referred to as the "County," and the Department of the Environment, hereinafter referred to as the "Department."

WHEREAS, Owner owns a tract of land located on 7510 Browns Bridge Rd. HIGHLAND, in the Election District of Howard County, Maryland, and the deed to same is recorded among the Land Records of Howard County, Maryland, in Columbia and in Liber _____ Folio _____.

WHEREAS, the Bay Restoration Fund (BRF) may provide a grant for the cost attributable to upgrading an onsite sewage disposal system to the Best Available Technology (BAT) for the removal of nitrogen.

WHEREAS, the BRF may also provide a grant for the cost difference between a traditional onsite sewage disposal system and a system that utilizes the BAT for the removal of nitrogen.

WHEREAS, Owner understands that participation in the Bay Restoration Fund is voluntary.

NOW, THEREFORE, the parties hereto agree as follows:

- A. Owner hereby grants to the Department and the County the right to enter upon the property at any reasonable time for access to the system to make periodic inspections and the Owner agrees to provide any information and data requested and needed by the Department to develop accurate and thorough test results.
- B. Owner acknowledges and agrees that a MDE certified and manufacturer-approved installer will install the BAT system.
- C. Owner acknowledges and agrees the manufacturer or manufacturer's authorized service provider will provide for Operation and Maintenance of the BAT for a period of 5 years as a condition of sale of the BAT. After the initial 5 year period an Operation and Maintenance contract with a certified service provider must be maintained in perpetuity by the property owner.
- D. Owner acknowledges and agrees that the manufacturer appointed Operation and Maintenance provider will have access to the BAT system at all times.
- E. Owner acknowledges and agrees that the manufacturer or manufacturer's authorized service provider will have access to sample the effluent of the BAT system. Owner acknowledges and agrees that the proposed installation of a BAT system funded by the BRF is voluntary. Owner agrees that there shall be no liability on the part of the County or Department to Owner if this BAT system fails, and that the County and the Department do not warrant or guarantee that the BAT system will adequately or properly function.
- F. Owner acknowledges and agrees that neither the County nor the Department nor any of its

agents or employees, either officially or individually, underwrites the operation of any system approved by them.

- G. The Owner will devote such care and effort to the maintenance of the BAT system so that any malfunction is not the result of poor maintenance, faulty operation, or neglect.
- H. The Canaan Valley Institute agrees to grant up to \$_____ toward the cost of installation of the BAT system, and financial responsibility is limited to this amount. Operating costs will be at the Owners expense.
- I. The Owner acknowledges that the BRF grant can only be used for that portion of the OSDS attributable to (BAT) for the removal of nitrogen.
- J. Owner acknowledges in the event the total project cost is greater than \$25,000 the proposal will have to be approved by the Maryland State Board of Public Works.
- K. The Owner agrees to contact both the Water Management Administration, On-Site Systems Division of the Wastewater Permits Program and the County at least forty-eight (48) hours prior to system installation, so that the Department has the opportunity to be present at the time of installation or thereafter for inspection.
- L. The Owner must install BAT system according to the manufacturer recommended plans and specifications approved by the Department.
- M. The Owner agrees and acknowledges that if installation deviates substantially from the approved plans or changes such that performance of the system is compromised or reduced, BRF funding will not be provided.
- N. This agreement shall run with the land and binds the Owner, his heirs, successors, assigns. Owner further agrees that he shall inform in writing any purchaser or lessee of the property that the system may require maintenance or other attention. The Owner agrees to record this agreement in the land records of Howard County.
- O. This agreement shall not be construed to limit any authority of the Department to protect the public health, safety or comfort or to issue any other orders to take any other action that is now or may hereafter be within its authority.
- P. This agreement may be voided at the discretion of the Department if the system construction is not completed within six (6) months of the effective date of this agreement.
- Q. This agreement contains the entire agreement and understanding between the County and the Owner and the Department. There are no additional terms other than as contained in this agreement. This agreement may not be modified except in writing signed by each of the parties or by their authorized representatives.
- R. The laws of the State of Maryland govern the provisions of all transactions pursuant to this agreement.

IN WITNESS WHEREOF, the parties have signed and sealed this agreement on the date indicated above.

DATE: 8.21.18

Christina Hill
Caree Ann Hill
Owner

DATE: 8/24/2018

Paul Nifon
Howard County Health Department

Wolf, Kevin

From: Al Hill <alhill082159@gmail.com>
Sent: Thursday, August 09, 2018 2:14 PM
To: Wolf, Kevin
Cc: Carol Hill
Subject: Re: 7510 Browns Bridge road

I called BG&E and couldn't get anyone to tell me how close to the pole we can dig. I called Miss utility and they said stay 10 feet from it. I called about the road and the state said it wasn't theirs and to call the county. I called Howard County and was sent to at least 6 different departments and no one could tell me how close to the road. I would say at least 10 or 15 feet off the road because of the gas line

On Thu, Aug 9, 2018, 1:27 PM Wolf, Kevin <KWolf@howardcountymd.gov> wrote:

Carol,
Thanks for the update. I will coordinate efforts with South Carrol. I will see what we can fit in the upper most corner of the front yard, avoiding easements.

----- Original message -----

From: Carol Hill <carolann663@gmail.com>
Date: 8/9/18 1:07 PM (GMT-05:00)
To: "Wolf, Kevin" <KWolf@howardcountymd.gov>
Cc: Al Hill <alhill082159@gmail.com>, Carol Hill <carolann663@gmail.com>
Subject: 7510 Browns Bridge road

Hi Kevin,

I got your call, but was on a wagon tour at my work. We've contracted with South Carroll. I haven't heard anything from them yet. I sent the contract to them on July 18th. My husband is on this email too.

Miss Utility came out a couple of weeks ago and marked the front yard. Please let us know what we can do to keep this moving along.

Peace, Carol
Never get so busy making a living that you forget to make a life.

4 Trucks @ $\approx 26'$
1 word total
Inlet @ 2' - 2 1/2'
Bottom @ 7 1/2'
(40)

$\frac{600 \text{ gpd}}{1,200 \text{ (ft}^3\text{)}} =$
 $500 \text{ ft}^3 \div 2 = 250 \text{ (5')} \text{ (}.31) = \underline{\underline{78'}}$
3 x 26' trucks
Inlet @ 2 2 1/2'
Bottom @ .9

FILE INQUIRY NOTES

2310 Brown Bridge Rd.

DATE	RESULTS OF REVIEW FOR FILE
6/12/18	Phone discussion w/ owner of results. Email sent 6/13/18. Will have to drill new well in back yard and put septic in front. List of Drillers sent to owner via email. (KMD)
6/15/18	Owner confirmed meeting w/ J. Mayne well drilling on Friday 6/15/18 @ 11:30 am (KMD)
6/15/18	Onsite w/ property owners and J. Mayne well drilling. Confirmed access w/ drill rig to back of property should be fine. Went over well construction and drilling process w/ owner. Also talked about my pre test results as well as how the sizing of the system will be in front yard. (KMD)
6/22/18	Ordered 2 BR but owner has 1 BR. After in basement Design will be for 4 BR (600gpd in back yard) spec Preliminary spec's sent over via email (KMD) Waiting from coordination of owner on which way to proceed (→ Front yard septic, back yard proposed well)
7/13/18	Site map made w/ Kenny Shetter w/ S. Carroll. Owners onsite went over layout w/ Kenny. Owner expressed new families to be installed in upper SW corner of property >100' will oc. under Power line. I told owner will need something from O&E / mass utility oking this before I can design and break a septic plan in this area (KMD)

→ owner to let me know when the occurs.



CANAAN VALLEY INSTITUTE

July 10, 2018

Christopher & Carol Hill
7510 Browns Bridge Road
Highland, MD 20777

RE: FY 2019 Howard County Bay Restoration Fund OSDS Upgrade Program

Dear Mr. and Mrs. Hill:

Thank you for your application to participate in the Howard County Bay Restoration Fund OSDS Upgrade Program. The Howard County Health Department has verified that your existing septic system is failing and in need of repair. Based on your 2017 income tax return form, you are eligible to receive funding to cover **100%** of the cost to upgrade your system to one of the MDE approved BAT units listed below. The approved price includes the cost of the unit, installation of the unit, and 5 years of operation and maintenance. The price does not include the cost of permits.

<u>System</u>	<u>Vendor</u>	<u>Contact</u>	<u>Phone</u>
Norweco Singulair TNT	Back River Precast	Matt Geckle	410-833-3394
Biomicrobics	Dwayne C. Jones	Dwayne C. Jones	410-692-6900
HOOT	Mayer Bros, Inc.	Nancy Mayer	410-796-1434
Hydroaction	Sample Excavating	Mike Sample	443-807-8639
Orenco	Atlantic Solutions	Bob Johnson	877-814-8426
Septitech	Dwayne C. Jones	Dwayne C. Jones	410-692-6900
Aquaklear	BayStar Precast	Dave Care	410-977-3453

In order to receive your OSDS upgrade, **you MUST follow these steps:**

1. **Sign this letter** on the bottom of page 2 **and return it** in the envelope provided within **2 weeks of the date of this letter.**
2. File a septic repair permit application with the Howard County Health Department **within 2 weeks of the date of this letter.** The permit application fee is \$396.00 (\$165 for tank approval only).
3. Obtain the Agreement and Easement for Installation of Best Available Technology Systems with Bay Restoration Funds from the Howard County Health Department, have it signed by a Howard County Health Department Bureau Director or Designee. Then take it to the Circuit Court and have it recorded in Land Records **within 2 weeks of the date of this letter.**
4. Prepare your property and schedule installation of the system. The system must be installed **within 6 weeks of the date the Agreement and Easement is recorded.**

If assistance is needed in completing any of the steps listed above, you may contact me at 304-940-3443 or kristin.mielcarek@canaanvi.org.

10624 Appalachian Highway | Davis, WV 26260
Phone: (304) 259.4739
www.canaanvi.org

The system vendor may provide a contractor to install your BAT unit. CVI will provide payment directly to the vendor. The vendor may also require proof of insurance from your contractor.

If your system is not installed within the 8 week timeframe listed in the steps on page 1, the funds may be released and used elsewhere. If you cannot complete installation in within this timeframe, please contact me to request an extension. Please note that failure to request an extension may result in termination of your grant and your system must be installed no later than June 27, 2019 in order to retain your funding.

For more information on septic repair permitting, contact:

Jeff Williams
Program Supervisor, Well and Septic
410-313-1771

Please sign and return this original letter and keep a copy for your records. If you have any questions, please contact me at 304-940-3443 or by email at kristin.mielcarek@canaanvi.org.

Sincerely,

Kristin Mielcarek, Executive Director

I have read and agree to the conditions of this Agreement Letter.

Accepted by: Christopher Hill, Property Owner

Signature

Date

Accepted by: Carol Hill, Property Owner

Signature

Date

10624 Appalachian Highway | Davis, WV 26260
Phone: (304) 259.4739
www.canaanvi.org

Wolf, Kevin

From: Wolf, Kevin
Sent: Thursday, June 21, 2018 4:43 PM
To: 'Carol Hill'
Subject: RE: 7510 Browns Bridge Road
Attachments: SEPTIC CONTRACTORS_updated 2-1-18.pdf

Hi Carol,

The following is the engineering/design specifications for a 3 bedroom sized septic in the front yard:

3BR Design = 150gpd x 3 = 450gpd

$450\text{gpd} \div 1.2\text{gpd}/\text{ft}^3 = 375\text{ ft}^3 \div 2 = 187.5\text{ft} \times .44$ (sidewall reduction rate) = 82.5LF

Trench spec's:

- 2 ft wide trenches
- Inlet @ 2ft
- Bottom depth @ 7ft
- Effective area (sidewall reduction rate) @ 4ft
- 82.5 total linear feet of trench (probably 2x42ft trenches installed on contour)

I know this may not make too much sense but I wanted to show you the calculations based on the infiltration rates I got from the average of the 2 perc tests we did in the front yard. We ended up with a 1.2 gpd/ft³ loading rate. I have also attached our septic contractors list for your convenience. I've highlighted the ones in yellow that might compromise to your liking.

I will be out of the office all next week but Ill be in tomorrow if you have any questions.

Thanks,

Kevin M. Wolf, LEHS, REHS/RS
Groundwater Mgmt. Sec. Supervisor
Well & Septic Program
Bureau of Environmental Health
8930 Stanford Blvd.
Columbia, MD 21045
(o) 410-313-2645
(f) 410-313-2648



kwolf@howardcountymd.gov

CONFIDENTIALITY NOTICE

This message and the accompanying documents are intended only for the use of the individual or entity to which they are addressed and may contain information that is privileged, confidential, or exempt from disclosure under applicable law. If the reader of this email is not the intended recipient, you are hereby notified that you are strictly prohibited from reading, disseminating, distributing, or copying this communication. If you have received this email in error, please notify the sender immediately and destroy the original transmission.

From: Carol Hill [mailto:carolann663@gmail.com]
Sent: Wednesday, June 20, 2018 8:28 AM
To: Wolf, Kevin
Subject: Re: 7510 Browns Bridge Road

Thanks so much.

Peace,
Carol

All things that are truly great, are at first thought impossible. Don't give up - keep going. God has a fabulous plan for you!

On Wed, Jun 20, 2018 at 8:26 AM Wolf, Kevin <KWolf@howardcountymd.gov> wrote:

Yes, i apoligize for the delay. It has been hectic. Let me gather your information you are requesting later this morning.

----- Original message -----

From: Carol Hill <carolann663@gmail.com>
Date: 6/20/18 8:15 AM (GMT-05:00)
To: "Wolf, Kevin" <KWolf@howardcountymd.gov>
Subject: Re: 7510 Browns Bridge Road

Good morning Kevin,

Do you have a list of people that can dig for the new septic tank to go in? I sent the pre-application for the grant to Kristen on Monday morning.

Peace,
Carol

All things that are truly great, are at first thought impossible. Don't give up - keep going. God has a fabulous plan for you!

On Wed, Jun 13, 2018 at 1:28 PM Carol Hill <carolann663@gmail.com> wrote:

Hi Kevin,

Sorry to bother you. How deep would the well have to be? That is a huge factor in price. Currently, the well is 75' deep.

Peace,
Carol

All things that are truly great, are at first thought impossible. Don't give up - keep going. God has a fabulous plan for you!

On Wed, Jun 13, 2018 at 12:35 PM Wolf, Kevin <KWolf@howardcountymd.gov> wrote:

Carol,

It was nice speaking with you this morning. Just to reiterate, contact a couple well drillers and find out a price for drilling a new well in the back yard. The new well location would be roughly center most part of the yard, at least 100ft or so from your existing septic tank location. Of course I can meet with you and/or the well driller onsite if needed. I have attached a list of well drillers mostly seen in Howard County for your convenience.

If you choose not to drill a new well, the other option would be to find something usable in the back yard. This would have to be done in consultation with our regional representative with Maryland Department of the Environment (MDE). Please note that this may require additional testing, design and coordination as well as guidance from a specialized designer familiar in this type of soils, hydrogeology and non-conventional septic design.

In the meantime, Jeff Williams our program supervisor will connect you with the needed grant application information for the Bay Restoration Fund (BRF) program. As I stated on the phone, we have exhausted funds for this fiscal year and you would be put on the list for next fiscal year which starts July 1st. I can be reached by phone or email (see below) if you have any questions moving forward.

Thanks,

Kevin M. Wolf, LEHS, REHS/RS

Groundwater Mgmt. Sec. Supervisor

Well & Septic Program

Bureau of Environmental Health

8930 Stanford Blvd.

Columbia, MD 21045

(o) 410-313-2645

(f) 410-313-2648

kwolf@howardcountymd.gov

CONFIDENTIALITY NOTICE

This message and the accompanying documents are intended only for the use of the individual or entity to which they are addressed and may contain information that is privileged, confidential, or exempt from disclosure under applicable law. If the reader of this email is not the intended recipient, you are hereby notified that you are strictly prohibited from reading, disseminating, distributing, or copying this communication. If you have received this email in error, please notify the sender immediately and destroy the original transmission.

Wolf, Kevin

From: Wolf, Kevin
Sent: Wednesday, June 13, 2018 2:58 PM
To: Williams, Jeffrey
Subject: FW: 7510 Browns Bridge Road BRF

Hey Jeff,

Here is the owner information requesting BRF:

7510 Browns Bridge Road
Carol and Christopher Hill
301-704-4787
Carolann663@gmail.com

From: Wolf, Kevin
Sent: Wednesday, June 13, 2018 12:36 PM
To: 'carolann663@gmail.com'
Subject: 7510 Browns Bridge Road

Carol,
It was nice speaking with you this morning. Just to reiterate, contact a couple well drillers and find out a price for drilling a new well in the back yard. The new well location would be roughly center most part of the yard, at least 100ft or so from your existing septic tank location. Of course I can meet with you and/or the well driller onsite if needed. I have attached a list of well drillers mostly seen in Howard County for your convenience.

If you choose not to drill a new well, the other option would be to find something usable in the back yard. This would have to be done in consultation with our regional representative with Maryland Department of the Environment (MDE). Please note that this may require additional testing, design and coordination as well as guidance from a specialized designer familiar in this type of soils, hydrogeology and non-conventional septic design.

In the meantime, Jeff Williams our program supervisor will connect you with the needed grant application information for the Bay Restoration Fund (BRF) program. As I stated on the phone, we have exhausted funds for this fiscal year and you would be put on the list for next fiscal year which starts July 1st. I can be reached by phone or email (see below) if you have any questions moving forward.

Thanks,

Kevin M. Wolf, LEHS, REHS/RS
Groundwater Mgmt. Sec. Supervisor
Well & Septic Program
Bureau of Environmental Health
8930 Stanford Blvd.
Columbia, MD 21045
(o) 410-313-2645
(f) 410-313-2648



kwolf@howardcountymd.gov