

# APPLICATION

## FOR PERCOLATION TESTING AND SITE EVALUATION

TEST DATE(S) \_\_\_\_\_ TEST TIME \_\_\_\_\_

AP 530249/

AGENCY REVIEW: \_\_\_\_\_

DATE 11/25/08

DO NOT WRITE ABOVE THIS LINE

I HEREBY APPLY FOR THE NECESSARY TESTING/EVALUATION PRIOR TO ISSUANCE OF SEWAGE DISPOSAL SYSTEM PERMIT(S) TO:

CHECK AS NEEDED:

- CONSTRUCT NEW SEPTIC SYSTEM(S)
- REPAIR/ADD TO AN EXISTING SEPTIC SYSTEM
- REPLACE AN EXISTING SEPTIC SYSTEM  
+ RELOCATE

CHECK AS NEEDED:

- NEW STRUCTURE(S)
- ADDITION TO AN EXISTING STRUCTURE
- REPLACE AN EXISTING STRUCTURE

CHECK ONE:

- CREATE NEW LOT(S)
- BUILD ON AN EXISTING LOT IN A SUBDIVISION
- BUILD ON AN EXISTING PARCEL OF RECORD

IS THE PROPERTY WITHIN 2500' OF ANY RESERVOIR?

- YES
- NO

THE TYPE OF STRUCTURE IS:

- RESIDENTIAL WITH \_\_\_\_\_ PROPOSED BEDROOMS IN THE COMPLETED STRUCTURE (NOTE **UNKNOWN** IF APPROPRIATE)
- COMMERCIAL (PROVIDE DETAIL OF NUMBERS AND TYPES OF EMPLOYEES/ CUSTOMERS ON ACCOMPANYING PLAN)
- INSTITUTIONAL/GOVERNMENT (PROVIDE DETAIL OF NUMBERS AND TYPES OF EMPLOYEES/USERS ON ACCOMPANYING PLAN)

PROPERTY OWNER(S) DAR AL TAQWA INC.

DAYTIME PHONE (410) 531-2235 CELL \_\_\_\_\_ FAX \_\_\_\_\_

MAILING ADDRESS 10740 ROUTE 108 ELLCOTT CITY MD 21047  
STREET CITY/TOWN STATE ZIP

APPLICANT BRIAN F. CLEARY

DAYTIME PHONE (410) 465-6105 CELL \_\_\_\_\_ FAX (410) 465-6644

MAILING ADDRESS 8480 BALTIMORE NATIONAL PKE ELLCOTT CITY MD 21043  
STREET SUITE 413 CITY/TOWN STATE ZIP

APPLICANT'S ROLE: DEVELOPER BUILDER BUYER RELATIVE/FRIEND REALTOR CONSULTANT

PROPERTY LOCATION  
SUBDIVISION/PROPERTY NAME DAR AL TAQWA LOT NO. \_\_\_\_\_

PROPERTY ADDRESS 10740 ROUTE 108 ELLCOTT CITY, MD 21042  
STREET TOWN/POST OFFICE

TAX MAP PAGE(S) 29 GRID 11 PARCEL(S) 12 PROPOSED LOT SIZE \_\_\_\_\_

AS APPLICANT, I UNDERSTAND THE FOLLOWING: THE SYSTEM INSTALLED SUBSEQUENT TO THIS APPLICATION IS ACCEPTABLE ONLY UNTIL PUBLIC SEWERAGE IS AVAILABLE. THIS APPLICATION IS COMPLETE WHEN ALL APPLICABLE FEES AND A SUITABLE SITE PLAN HAVE BEEN RECEIVED. I ACCEPT THE RESPONSIBILITY FOR COMPLIANCE WITH ALL M.O.S.H.A. AND "MISS UTILITY" REQUIREMENTS. APPROVAL IS BASED UPON SATISFACTORY REVIEW OF A PERC CERTIFICATION PLAN. TEST RESULTS WILL BE MAILED TO APPLICANT.

SIGNATURE OF APPLICANT

HOWARD COUNTY HEALTH DEPARTMENT, BUREAU OF ENVIRONMENTAL HEALTH, WELL AND SEPTIC PROGRAM  
 7178 COLUMBIA GATEWAY DRIVE COLUMBIA, MARYLAND 21046 (410) 313-2640 FAX (410) 313-2648  
 TDD (410) 313-2323 TOLL FREE 1-877-4MD-DHMH

AP

# DAR ALTAQUA

- (14)
- 0.5' blk loam slightly sticky
- 2' brn clay
- 4.8' brn scl to heavy sl common mica
- 5.9' brn sl many fine mica
- 1' yel-red & lt. brn sl many mica
- 10' yel-red sl m1d chroma 3
- 12' yel-brn common Mn coatings etd & c2d chroma 12
- 12.5'
- (15)
- 0.4' blk loam
- 2.5' brn clay
- 3.5' brn g. scl
- redd brn scl
- (5) redd & lt brn sl, sm
- 6.5' lt brn sl many mica
- 9' lt. grey & lt. brn fs sl many mica
- 11'
- (13)
- 0.4' blk loam
- 3' brn cl
- brn scl c2d chroma 2
- brn fs sl
- 2 opl
- 5.5' brn sl micaceous
- 9' brn fs micaceous
- 12'



- (12A)
- 0.4' blk loam
- 2' brn clay
- brn cl
- 4.2' pale yellow st sl few boulders
- 5.5' pale yellow sl, dense 2.5 7/3
- 7' pale yellow sl 2.5 7/3
- 13'

- (16)
- 0.3' blk loam
- brn cl
- brn scl
- 3' brn scl dense 1 ppl clay skins
- 5' yel-red scl c3d & c1d chroma 2
- 7' yel-red fs sl blocky, brittle dense
- 10' pale brn sl

DATE	TEST #	DEPTH	START	BREAK 1" DROP	STOP 2" DROP	TIME OF 2ND INCH	P/F/H
1/8/09	14	5.2' / 12'	11:12	11:26	11:53	27	P
1/8/09	15	8' / 14'	0	1.5	4	2.5	P
1/8/09	13	6.5' / 12'	0	1.5	4.5	3	P
1/8/09	16	8' / -	2:12	2:36	no movement		F
1/8/09	12A	7.4' / -	3:14	3:44	no movement		F

REMARKS \*13 & 14, Trench bottom at 8, Sidewall 6.5', ~~15~~ OK 6.5' 12

SANITARIAN RB BACKHOE Bob Nell OTHERS Steve


TEST HOLES USED IN SDA \_\_\_\_\_ AVG. PERC TIME \_\_\_\_\_ SQ. FT/BR \_\_\_\_\_

TRENCH WIDTH \_\_\_\_\_ INLET DEPTH \_\_\_\_\_ MAX. BOT DEPTH \_\_\_\_\_ EFFECTIVE SW \_\_\_\_\_

Dar AL Tagua  
 # 10740 RTE 108<sup>0</sup> (Clarksville Pk)

# 17 offset 30'

2 Trenches  
 have  
 clean  
 gravel  
 Schedule 40 PVC  
 drain pipe  
 2 ft wide  
 10 ft deep  
 Inlet 3' and 4'  
 5-5.5' Effective  
 Sidewalk  
 est. 1.2 gpd/SF



0.3' dk brn loam  
 15' brn cl  
 red-brn cl  
 yel-red  
 sil  
 common mica  
 4.5' dk grey-brn  
 Saprophyte  
 many fine mica  
 some pale red  
 8.5' dk brn  
 & pale yel.  
 #20  
 sil  
 micaceous  
 13' dk brn sil  
 blocky  
 few Mn  
 concentra-  
 tions  
 14' ↓


DATE	TEST #	DEPTH	START	BREAK 1" DROP	STOP 2" DROP	TIME OF 2ND INCH	P/F/H
1/13/09	17 offset	14'	Visual		est. 1.2 gpd/SF 4.5 or 5 to 13'		P

REMARKS Observed soil profile at Repair installed  
 SANITARIAN RB BACKHOE Bob Noll OTHERS Brian Cleary  
 TEST HOLES USED IN SDA \_\_\_\_\_ AVG. PERC TIME \_\_\_\_\_ SQ. FT/BR \_\_\_\_\_  
 TRENCH WIDTH \_\_\_\_\_ INLET DEPTH \_\_\_\_\_ MAX. BOT DEPTH \_\_\_\_\_ EFFECTIVE SW \_\_\_\_\_

RAR ALTAQWA


AP

(12)  
 0.5' dk grey loam  
 2.5' brn clay  
 abk, sub gravel  
 Yel-brn  
 dense scl  
 ss, 1/4 pt  
 brn & red  
 grscl  
 ss  
 7.5' pale yel  
 loamy sl  
 c1d  
 10.5' ss  
 grey &  
 pale brn  
 micaceous  
 sl  
 13'  
 (11)  
 0.6' dk grey loam  
 3' brn cl  
 ss, sbk  
 3' brn heavy sl  
 2/4 pl  
 c2d chroma 2  
 6' 25Y 5/2  
 grey sl  
 micaceous  
 9'  
 25Y 6/3  
 c1p red  
 11'  
 c2d red-brn



10  
 0.5' dk grey loam  
 2.0' brn cl, sbk  
 3.5' brn & red-brn  
 by scl  
 6' yel-red  
 dense grsl  
 7' yel-red  
 & pale brn sl  
 8.5' pale white & dk grey  
 sl, m1p yel-red  
 13' white  
 13.5' lt. grey ls

DATE	TEST #	DEPTH	START	BREAK 1" DROP	STOP 2" DROP	TIME OF 2ND INCH	P/F/H
1/9/09	12	8.2'	11:55	12:31 <sup>+</sup>	<1"	>	F
1/9/09	10	7.5' / 13'	12:52	1:22 <sup>+</sup>	<1"	>	F
1/9/09	10	9' / 13'	1:31	1:37	1:53	16	#
1/9/09	10	6'-11'	Visual	internal drainage impeded or w.t. head of water			F
1/13/09	22	6.5' / 11'	2:21	2:50	2:20 <sup>+</sup>	>30	F



REMARKS # 10; Trench bottom 9', no side wall  
 SANITARIAN RB BACKHOE Bob Noll OTHERS \_\_\_\_\_  
 TEST HOLES USED IN SDA \_\_\_\_\_ AVG. PERC TIME \_\_\_\_\_ SQ. FT/BR \_\_\_\_\_  
 TRENCH WIDTH \_\_\_\_\_ INLET DEPTH \_\_\_\_\_ MAX. BOT DEPTH \_\_\_\_\_ EFFECTIVE SW \_\_\_\_\_  
 2.5' YR 6/8  
 11'

#22  
 brn loam  
 brn cl, sbk  
 2.5' ~~red-brn~~ cl  
 common Mn coatings  
 few coarse Mn concentrations  
 3.5' yel-brn scl  
 4.5' grey sil  
 micaceous  
 6' 3d pale red sl  
 red-yellow sl  
 c2 3d pale yellow loam  
 11' red-yellow fl sl  
 many Mn coatings on rock surfaces

# HP Color LaserJet 2840




HP LASERJET FAX

Jan-20-2009 11:56AM

## Fax Call Report


Job	Date	Time	Type	Identification	Duration	Pages	Result
4287	1/20/2009	11:47:22AM	Send	914104656644	9:09	15	OK



Bureau of Environmental Health  
 7178 Columbia Gateway Drive, Columbia, MD 21046  
 (410) 313-2640 Fax (410) 313-2648  
 TDD (410) 313-2323 Toll Free 1-866-313-6300  
 website: www.hchealth.org

Peter L. Beilenson, M.D., M.P.H., Health Officer

F A X



Date 1/20/2009  
 To Brian Cleary  
 Department Benchmark Eng. Inc.  
 FAX# 410 465 6644


From Robert Bricker

Telephone 410-313-2691 FAX (410) 313-2648

# of Pages 15 (including cover page)

Comments Dar Altagwa 1pg report, 3 pages 2009 results  
3pgs NOV 2000 Perc Cert; 2pgs JUL 2000 results  
3pgs 2005 installation 1pg Soil and Topo output  
2pgs 1992 Repair Ho Co GIS

**CONFIDENTIALITY NOTICE**  
 "WARNING: UNAUTHORIZED INTERCEPTION OF THIS TELEPHONIC COMMUNICATION COULD BE A VIOLATION OF FEDERAL AND MARYLAND LAW"  
 The documents accompanying this telecopy transmission contain confidential information belonging to the sender which is legally privileged. The information is intended only for the use of the individual or entity named above. If you are not the intended recipient, you are hereby notified that any discourse, copying, distribution or the taking of any action in reliance on the contents of this telephonic information is strictly prohibited. If you have received this telecopy in error, please immediately notify sender by telephone to arrange for return of the original documents to us.



Bureau of Environmental Health  
7178 Columbia Gateway Drive, Columbia, MD 21046-2147  
(410) 313-2640 Fax (410) 313-2648  
TDD (410) 313-2323 Toll Free 1-866-313-6300  
website: www.hchealth.org

Peter L. Beilenson, M.D., M.P.H., Health Officer

January 20, 2009

Brian Cleary  
Benchmark Engineering, Fax 410-465-6644

RE: PERCOLATION TEST RESULTS, Dar Al Taqwa, 10749 Clarksville Pike, A-530249

Dear Mr. Cleary,

Percolation testing was conducted on the subject property on January 8, 9 and 13, 2009. The purpose for conducting these tests was to identify area(s) for septic easement(s) to serve new construction as well as support existing conditions on the subject property. Percolation Test Results indicate soils' conditions in the areas tested are both satisfactory and unsatisfactory for onsite wastewater disposal. Field data collected are shown on the Percolation Test Worksheet enclosed with this letter. Values for Recommended Inlet and Trench Bottom depths, and Usable (Effective) Sidewall are all based on observed soil properties and characteristics at respective test locations as well as the particular soils materials tested. The values for the listed parameters will be interpreted and maintained in Health Department records for the subject property.

Soils' characteristics and percolation times at test locations 13, 14, 15, and 17 are satisfactory. Locations 13 and 15 have deep, moderately permeable subsoil with no indication of internal drainage or water table to 12 and 14 feet deep, respectively. Location 14 has an apparent seasonal water table at 10 feet to 12 feet depth, and at location 17 there are few, thin manganese coatings between 13 feet and 14 feet. The seasonal water table level should be proven at #14.

At location 10, there are indicators of impeded drainage or seasonal water table below 8.5 feet. The subsoil is only very slowly permeable to at least 8.5 feet depth, and has moderately slow permeability at 9 feet deep. Together these characteristics indicate that a wet-season observation of water table level is needed prior to approval of test location 10.

Unsatisfactory soils occur at test locations 12, 12-A, 11, 16, and 22. These locations are all immediately adjacent to (or within) the headland of a broad, natural drain. All but locations 11 and 22 have a dense, sandy clay loam layer with platy structure, and very slow permeability that is typical of soils occurring in and near local drains throughout the county. Locations 11 and 22 lack the dense, platy subsoils, however, each have grey subsoils indicating that saturation may occur at 6 feet and 11 feet respectively for extended periods.

Any additional testing at the east end of the subject property must be conducted during a wet-season test period declared by the Howard County Health Officer. If you have any questions regarding this evaluation or requirements for the Percolation Certification Plan, please contact me at the above address or by calling (410) 313-2691.

Respectfully,

A handwritten signature in black ink that reads 'Robert C. Bricker' with a stylized flourish at the end.

Robert C. Bricker, R.S., CPSS

Well and Septic Program  
Development Coordination Section


Enclosures

Copy: File

AP: \_\_\_\_\_

# DAR ALTAQUA

(14)  
 0.5' blk loam slightly sticky  
 2' brn clay  
 4.8' brn scl to heavy sl common mica  
 5.9' brn sl many fine mica  
 10' yel-red & lt. brn sl many mica  
 12' yel-red sl m 1d chrom  
 12.5' yel brn common mica c1d & c2d chrom



(12A)  
 0.4' blk loam  
 2' brn clay  
 4.2' pale yellow st sl few boulders  
 5.5' pale yellow sl, dense 2.5' 7/3  
 7' pale yellow sl 2.5' 7/2  
 13'

(15)  
 0.4' blk loam  
 2.5' brn clay  
 3.5' red & brn scl  
 5' red & lt brn sl, com  
 6.5' lt brn sl many mica  
 9' lt. grey & lt. brn sl many mica  
 14'

DATE	TEST #	DEPTH	START	BREAK 1" DROP	STOP 2" DROP	TIME OF 2ND INCH	P/F/H
1/8/09	14	5.3' / 12'	11:12	11:26	11:53	27	P
1/8/09	15	8' / 14'	0	1.5	4	2.5	P
1/8/09	13	6.5' / 12'	0	1.5	4.5	3	P
1/8/09	16	8' / -	2:12	2:36	no movement		F
1/8/09	12A	7.4' / -	3:14	3:44	no movement		F

(16)  
 0.3' blk loam  
 brn cl  
 brn scl  
 3' brn scl dense 1 ft clay skins  
 5' yel-red scl c3d & c2d chrom  
 7' yel-red fs / blocky, brittle dense  
 10' pale brn sl

Not used for sidewall

REMARKS #13 & 14, Trench bottom at 8' Sidewall 6.5' OK #15 OK 6.5' 12

SANITARIAN RB BACKHOE Bob Noll OTHERS Steve

TEST HOLES USED IN SDA \_\_\_\_\_ AVG. PERC TIME \_\_\_\_\_ SQ. FT/BR \_\_\_\_\_


TRENCH WIDTH \_\_\_\_\_ INLET DEPTH \_\_\_\_\_ MAX. BOT DEPTH \_\_\_\_\_ EFFECTIVE SW \_\_\_\_\_

(13)  
 0.4' blk loam  
 3' brn cl  
 5' brn scl c2d chrom  
 5.5' brn fs  
 9' micaceous  
 12'

PAR ALTAOWA

AP

12  
 0.5' dk grey loam  
 2.5' brn clay  
 abk, s&g gravel  
 5.5' ss, 1/4 pt  
 brn & red  
 grscl  
 ss  
 7.5' pale yellow  
 loamy sl  
 10.5' ss  
 grey &  
 pale brn  
 micaceous  
 sl  
 13'



10  
 0.5' dk grey loam  
 2.0' brn cl, sbk  
 3.5' brn scl, 1/4 pt  
 6' brn & red-brn  
 by scl  
 7' yellow-red  
 dense grscl  
 8.5' yellow-red  
 pale brn sl  
 13' white  
 13.5' lt. grey ls

11  
 0.6' dk grey loam  
 3' brn cl  
 ss, sbk  
 3' brn heavy sl  
 1/4 pt  
 6' 2nd chroma 2  
 25Y 5/2  
 grey sl  
 micaceous

DATE	TEST #	DEPTH	START	BREAK 1" DROP	STOP 2" DROP	TIME OF 2ND INCH	P/F/H
1/9/09	12	8.2'	11:55	12:31 <sup>+</sup>	<1"		F
1/9/09	10	7.5' / 13'	12:52	1:22 <sup>+</sup>	<1"		F
1/9/09	10	9' / 13'	1:31	1:37	1:53	16	#
1/9/09	6-11'	Visual		internal drainage impeded or w.t. head of suble			F
1/13/09	22	6.5' / 11'	2:21	2:50	2:20 <sup>+</sup>	>30	F

#22  
 2.5' brn loam  
 brn cl, sbk  
 3.5' yellow-brn scl  
 common Mn coatings  
 few coarse Mn concentrations  
 4.5' yellow-brn scl  
 6' grey sil  
 micaceous  
 3d pale red sl  
 6' red-yellow sl  
 2nd 3d pale yellow loam  
 11' red-yellow 1/4 pt sl  
 many Mn coatings on rock surfaces

REMARKS # 10; Trench bottom 9', no side wall  
 SANITARIAN RB BACKHOE Bob Noll OTHERS  
 TEST HOLES USED IN SDA \_\_\_\_\_ AVG. PERC TIME \_\_\_\_\_ SQ. FT/BR \_\_\_\_\_  
 TRENCH WIDTH \_\_\_\_\_ INLET DEPTH \_\_\_\_\_ MAX. BOT DEPTH \_\_\_\_\_ EFFECTIVE SW \_\_\_\_\_

9' grey heavy sl  
 25Y 6/2  
 C1p red  
 11' C2d red-brn


AP \_\_\_\_\_

Dar Al Taqwa

# 10740 Rte 1080 (Clarksville Pk)

# 17 offset 30'

2 Trenches  
 have  
 clean  
 gravel  
 Schedule 40 PVC  
 drain pipe  
 2 ft wide  
 10 ft deep  
 Inlet 3' and 4'  
 5-5.5' Effective  
 sidewall  
 est. 1.2 gpd/sf



0.3' dk brn loam  
 15' brn cl  
 red-brn cl  
 yel-red  
 sel  
 common mica  
 4.5' dk grey-brn  
 Saprolite  
 many fine mica  
 some pale red  
 8.5' dk brn  
 & pale yel.  
 #20 stake  
 micaceous  
 13' dk brn sl  
 blocky  
 few Mn  
 concentrations  
 14' ↓

DATE	TEST #	DEPTH	START	BREAK 1" DROP	STOP 2" DROP	TIME OF 2ND INCH	P/F/H
1/13/09	17 offset	14'	Visual		est. 1.2 gpd/sf 4.5' or so to 13'		P

REMARKS Observed soil profile at Repair installed  
 SANITARIAN RB BACKHOE Bob Noll OTHERS Brian Cleary  
 TEST HOLES USED IN SDA \_\_\_\_\_ AVG. PERC TIME \_\_\_\_\_ SQ. FT/BR \_\_\_\_\_  
 TRENCH WIDTH \_\_\_\_\_ INLET DEPTH \_\_\_\_\_ MAX. BOT DEPTH \_\_\_\_\_ EFFECTIVE S/W \_\_\_\_\_

11/20/91

# PERMIT

## SEWAGE DISPOSAL SYSTEM

### DEPARTMENT OF HEALTH AND MENTAL HYGIENE

P 47710  
A REPAIR

HOWARD COUNTY HEALTH DEPARTMENT  
BUREAU OF ENVIRONMENTAL HEALTH  
461-9933

# INDEXED

DISTRICT \_\_\_\_\_  
DATE 1/3/92  
DATE SYSTEM APPROVED 11/25/91  
INSPECTOR Carell

Jack Fyock IS PERMITTED TO INSTALL \_\_\_\_\_ ALTER X

ADDRESS \_\_\_\_\_ PHONE 988-9270

SUBDIVISION \_\_\_\_\_ LOT \_\_\_\_\_ ROAD 10740 Route 108

PROPERTY OWNER \_\_\_\_\_ Horney

ADDRESS \_\_\_\_\_

SEPTIC TANK CAPACITY 1000 GALLONS

NUMBER OF BEDROOMS 3

\_\_\_\_\_ SQUARE FEET PER BEDROOM

LINEAR FEET OF TRENCH REQUIRED \_\_\_\_\_

REPAIR - PURPOSE - Septic System has failed.

Call for inspection when ground is opened so sanitarian can recommend repair.

PLANS APPROVED BY \_\_\_\_\_ C. Williams DATE 11/25/91

COVER NO WORK UNTIL INSPECTED AND APPROVED

NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM

NOTE: CLEANOUT REQUIRED EVERY 70 FEET OF SEWER LINE AND/OR AT 90° SWEEPS IN LINES FROM HOUSE TO DRAIN FIELDS, 90° ELBOWS NOT ACCEPTABLE.

NOTE: ALL PARTS OF SEPTIC SYSTEMS (I.E. TANK, DISTRIBUTION BOX TRENCHES) TO BE 100 FEET FROM WELL (UNLESS OTHERWISE SPECIFICALLY AUTHORIZED)

NOTE: IF DEEP TRENCH(ES) ARE USED CALL FOR INSPECTION BEFORE AND AFTER PLACING GRAVEL IN TRENCH(ES)

NOTE: NO DRY WELL SHALL EXCEED 15 FOOT IN DIAMETER NO ABSORPTION TRENCH TO EXCEED 100 FEET IN LENGTH

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK MUST BE CAST IRON OR SCHEDULE 35/40 PVC OR ABS

PERMIT VOID AFTER TWO YEARS


NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL STAND PIPES MUST BE 6 INCHES IN DIAMETER CAST IRON, CONCRETE OR TERRA COTTA OR PVA OR ABS ACCEPTED. IF TOP OF SEPTIC TANK IS DEEPER THAN 3 FEET, MANHOLE TO GRADE REQUIRED.

NOTE: DISTRIBUTION BOXES MUST HAVE BAFFLES

**\*INSTALLER IS RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT**

**\*CALL 461-9933 FOR INSPECTION OF SEPTIC SYSTEM.**

P-47710



INDICATE NORTH - NAME ADJOINING ROADWAY AS BASE LINE

SEPTIC TANK LEVEL \_\_\_\_\_ CLEANOUTS \_\_\_\_\_

DISTRIBUTION BOX LEVEL \_\_\_\_\_

DRAIN FIELD/TITLE DEPTH 10 FT. TRENCH WIDTH 2 FT. INLET DEPTH 2 1/2 FT.

EFFECTIVE GRAVEL DEPTH 7 1/2 FT. TOTAL LENGTH 53 FT.

NUMBER OF TRENCHES 2 ONE SIDEWALL/BOTTOM AREA \_\_\_\_\_ SQ. FT.

DRYWALL INSIDE DIAMETER \_\_\_\_\_ FT. EFFECTIVE DEPTH BELOW INLET \_\_\_\_\_ FT.

Trench ABSORBENT AREA 397 SQ. FT.

REMARKS: Septic repair for Horney  
10740 Route -108

Kennedy Ridgely (Flock)  
11-25-91

11/25/91 NO INSP - APPROVED PER CONTRACTORS NOTES. CWI

DATE SYSTEM APPROVED 11/25/91 INSPECTOR CWilla










A 514199


Dar al Taq

COUNTY #

SOIL PROFILE 2



SOIL PROFILE



#15  
upper profile to 3'  
Same as #17 lower part similar to #11 @ 12-14' orange/white PSL-SiL (rel. csg gray matrix) very moist

DATE	TEST NO.	DEPTH	PRE-WET		TEST - 1" DROP		TIME
			START	STOP	START	STOP	
7/19/06	#2	40 1/2'	Too Rocky	@ 8 1/2 - 9 ft	(soils OK below 4')		20 mins other
	#1	14'	10:49:00	10:59:00	10:59:00	11:25	Hold percolation 26 mins
	#7	12'	water @ 12 - gray layers (2nd yel red matrix) @ 6' - 12'				Hold Percolation
	#5	14'	similar to #1 water @ Bottom (sl. csg gray)				
		5 1/2'	11:06	11:11	11:11	11:22	11 min
	4	16'	6 gravelly - Refusal (soil became pale gray & rock layers)				Fail
	4B	13 1/2'	Rock 3 ft (hard)				Fail
	#6		Not Tested				
	#3		Not Tested				

REMARKS \_\_\_\_\_  
 TYPE OF SOIL \_\_\_\_\_  
 TESTED BY APB/ly ALSO PRESENT Sam Alomer Don Robert Monty Raha or J. S. ...  
 TRENCH DESIGN DATA: AVERAGE PERCOLATION TIME \_\_\_\_\_ TRENCH WIDTH \_\_\_\_\_  
 INLET DEPTH \_\_\_\_\_ MAXIMUM BOTTOM DEPTH \_\_\_\_\_ SQ. FT./BEDROOM \_\_\_\_\_

A 514178

COUNTY #


SOIL PROFILE

0' 8  
 6-8" Red Br L  
 33 1/2" yel red sm sil  
 hL-CL  
 44 1/2" yel-yel br  
 hL sm sil  
 13 1/2" yel-bk yel  
 (9.5) P 1/8-7/8  
 L-SL  
 => SiL  
 in place  
 Mouvie  
 (Mud)

9

Some as  
 # 8  
 44 1/2" grey tan  
 13 1/2" Mottled  
 4C

6" Red Br L  
 pale - M  
 yel Br-bk yel  
 hL-SiL  
 18" red yel  
 yel Br hL-CL  
 4" Red Br CL  
 5 1/2" Red Br  
 - yel red  
 Loom  
 25% fine  
 gravel  
 30% 1/8"  
 8 1/2" 1/4"  
 12 1/2" coarse  
 PSL-SiL  
 13 1/2"



SOIL PROFILE

0'

INDICATE NORTH - NAME ADJOINING ROADWAY AS BASE LINE.

DATE	TEST NO.	DEPTH	PRE-WET		TEST - 1" DROP		TIME
			START	STOP	START	STOP	
7/19/00	8	13 1/2 5'	11:32	11:49	11:49	12:23	34 min
	9	13 1/2 5'	11:59	12:05	12:05	12:28	23 min
	4C	13 1/2 5 1/2'	provide water + Pk		56.8. Separ. 16. at 12:30		
			12:30	12:40	12:40	1:05	25 min

REMARKS \_\_\_\_\_  
 TYPE OF SOIL \_\_\_\_\_  
 TESTED BY R. P. Kelly ALSO PRESENT \_\_\_\_\_  
 TRENCH DESIGN DATA: AVERAGE PERCOLATION TIME 24 min TRENCH WIDTH 3  
 INLET DEPTH 4 1/2 MAXIMUM BOTTOM DEPTH 6 1/2 SQ. FT./BEDROOM Used 0.8 gpd / sq ft

LAYOUT 6/6/05 INSP 4 \_\_\_\_\_  
 INSP 2 6/29/05 INSP 5 \_\_\_\_\_  
 INSP 3 6/30/05 INSP 6 \_\_\_\_\_

ISSUE DATE: 5/18/05 **PERMIT** P 522484  
 APPROVAL DATE: 6/30/2005 A 514178

**ON-SITE SEWAGE DISPOSAL SYSTEM  
 HOWARD COUNTY HEALTH DEPARTMENT  
 BUREAU OF ENVIRONMENTAL HEALTH**

Fyock Septic Service, Inc. \_\_\_\_\_ IS PERMITTED TO INSTALL  ALTER   
 Field Superintendent:  
 ADDRESS: P. O. Box 89, Glenelg 21737 PHONE NUMBER: 410-988-9270

Property Name: Dar Al-Taqwa Community Center  
 ADDRESS: 10740 Clarksville Pike PROPERTY OWNER: Dar Al-Taqwa  
 TAX ID# 02-218216

Install per approved SDP02-004 dated 7/8/2002 prepared by Mildenberg, Boender & Assoc.  
 SDP # \_\_\_\_\_ sig. date \_\_\_\_\_ engineer \_\_\_\_\_

Maximum Sewage Design Flow 400 gallons per day Average Percolation time \_\_\_\_\_ min/inch  
 Design Loading Rate \_\_\_\_\_ gallons per square foot per day  
 Min. Septic Tank Capacity 2000 ~~1000~~ gallon top seamed tank with filters or other equipment  
 Min. Pump Tank Capacity TBD gallon top-seamed compartmented tank with dual alternating pumps  
 Min Trench Required 185 feet installed in 2 trenches of 93 feet each.

TRENCHES:	Trench to be 3.0 feet wide. Inlet 4.5 feet below original grade. Bottom maximum depth 6.5 feet below original grade. Effective area begins at 4.5 feet below original grade. 2.0 feet of stone below distribution pipe.
LOCATION:	Place the distribution box near the upper right corner of the septic easement and install 2-93 foot trenches on contour towards the opposite side of the septic easement.
NOTES:	Public water. Well to be abandoned & sealed after connection is complete.
PLANS APPROVED:	<u>Brian Baker/RJP</u> DATE: <u>6/13/05</u>


NOTES: PERMIT VOID AFTER 2 YEARS  
 CONTRACTOR IS RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS  
 WATERTIGHT SEPTIC TANKS REQUIRED  
 ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL UNLESS SPECIFICALLY AUTHORIZED  
 MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS UNLESS SPECIFICALLY AUTHORIZED  
 CONTRACTOR RESPONSIBLE FOR COMPLIANCE WITH APPLICABLE REGULATIONS, GUIDELINES AND THE TERMS  
 OF THIS PERMIT

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS  
 RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM  
 PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT  
 CALL 410-313-1771 FOR INSPECTION OF SEPTIC SYSTEM**

Box to be marked

Do not allow Rain Water Infiltrator pit to be within 25'

~~ROAD~~ MD SR 108



Inspection Date/Inspection Notes/Inspector's Initials & Others Present:

6/6/05 Met with Robert on site. Area staked. Contour is close. Install 2-93' trenches at top of easement. Use a transit. Pumped system may be required because building connection is now coming out somewhere under footer. Public sewer is not directly available. (BB)

6/29/05 Final called in for today. Robert says he shot contour. Trenches running on contour across easement in nearly straight line. ~ last 20' of trenches are slightly uphill. Pump system will not be necessary. No septic tank yet. Inspected trenches and D-Box and ok'd cover. Good chance of rain tonight. DBox will be left open to connect to septic tank. Check levelers and septic tank. (GAC)

6/30/05 Minimum fall from connection to tank 2-4%. Checked baffles - ok. D-box is set with levelers no port. Robert said he was going to mark it with a 2x4 or 4" piece of pipe. Tank sits level. Watched Robert put crushed blacktop around hung connection into septic tank. Robert is also to fill the remainder of this area with gravel to avoid possible breakage of inlet pipe. OK to cover. (GAC) Robert said builder wanted him to let him run the rain gutters from the building into septic. Before final approval check that rainwater infiltrators meet setbacks of 25' away from septic components. (GAC) 7/5/05 In addition no VNO to be issued before existing well is sealed/abandoned. (GAC)

-76°53'3."



39°14'11"



39°14'11"

Disclaimer: Howard County, Maryland assumes no responsibility for the accuracy of this report or the information contained herein or derived therefrom. The user assumes all risks and liabilities whatsoever resulting from or arising out of the use of this information. There are no oral agreements or warranties relating to the use of this report.

-76°53'3."



 **Howard County**  
M A R Y L A N D

By:  
Office:  
Map Width: 1,820.00 ft.  
Print Date: 12/12/2008  
Scale: 1 in. = 200 ft.

- use (need more info about use)

- add a basketball + other

- basketball ct + stage =

(frat houses)  
dinner table  
weddings?) ) multiverse

- classroom area = ~~for~~ <sup>for</sup> services  
is it a school

- (frequency of classroom use)

- kitchen use = no rear by <sup>new</sup> ~~at this time~~ <sup>at this time</sup> ~~use~~ <sup>required</sup>  
(to be expanded due to gym)

- floor plans for existing structure

HOWARD COUNTY HEALTH DEPARTMENT

*\*Catherine Kitcher*  
*renty*

Date \_\_\_\_\_

To: *\* showers in locker room*

From: \_\_\_\_\_

*Age group tailored to*

- For your information
- Please note & file
- Please note & return
- Please comment
- Please sign & return
- Please prepare reply for my signature
- Please answer, sending me copy of your letter
- Please handle
- Please circulate
- Please distribute
- Please see me
- As requested

REMARKS:

*\* if interested to me as a banquet hall (need to clarify)*

*\* explain laundry facility (how freq? comm. exp.) over how*

-76°53'3."



39°14'11"



39°14'11"


Disclaimer: Howard County, Maryland assumes no responsibility for the accuracy of this report or the information contained herein or derived therefrom. The user assumes all risks and liabilities whatsoever resulting from or arising out of the use of this information. There are no oral agreements or warranties relating to the use of this report.

-76°53'3."

**1015**  
Howard County

  
**Howard County**  
M A R Y L A N D

By:  
Office:  
Map Width: 1,820.00 ft.  
Print Date: 12/12/2008  
Scale: 1 in. = 200 ft.



6-11-12

25-11-12



approx. Top Trench



Septic Tank

Distribution Box





**BENCH MARKS NAD '83**

HO. CO. 29CA	ELEV. 422.892
STAMPED DISC ON CONCRETE MONUMENT, MANOR LANE 0.8 MILES NORTH OF RT. 108.	N 574526.116 E 1,343533.76
HO. CO. 29IC	ELEV. 468.127
STAMPED DISC ON CONCRETE MONUMENT, MANOR LANE 0.2 MILES NORTH OF RT. 108.	N 572323.543 E 1,344112.28

**GENERAL NOTES**

- 1) THE LOTS SHOWN HEREON COMPLY WITH THE MINIMUM OWNERSHIP WIDTH AND LOT AREA AS REQUIRED BY THE MARYLAND STATE DEPARTMENT OF THE ENVIRONMENT.
- 2) THIS AREA DESIGNATES A PRIVATE SEWERAGE EASEMENT AS REQUIRED BY THE MARYLAND STATE DEPARTMENT OF THE ENVIRONMENT FOR SEWERAGE DISPOSAL. IMPROVEMENTS OF ANY NATURE IN THIS AREA ARE RESTRICTED UNTIL PUBLIC SEWER IS AVAILABLE. THIS EASEMENT SHALL BECOME NULL AND VOID UPON CONNECTION TO A PUBLIC SEWER SYSTEM. THE COUNTY HEALTH OFFICER SHALL HAVE THE AUTHORITY TO GRANT ADJUSTMENTS TO THE PRIVATE SEWERAGE EASEMENT. RECORDATION OF A MODIFIED SEWERAGE EASEMENT PLAT SHALL NOT BE REQUIRED.
- 3) TOPOGRAPHY SHOWN IS BASED ON THE APPROVED SDP-02-04 AND SURVEY PERFORMED BY NTT ASSOCIATES INC. ON OR ABOUT AUGUST 1995.
- 4) THERE ARE NO EXISTING WELLS OR SEPTIC SYSTEMS WITHIN 100' OF THIS PROJECT'S BOUNDARY EXCEPT AS NOTED.
- 5) ANY CHANGES TO A PRIVATE SEWERAGE EASEMENT SHALL REQUIRE A REVISED PERCOLATION CERTIFICATION PLAN.
- 6) THE EXISTING SEPTIC AREA (BEST FIT) AND 100 YEAR FLOODPLAIN SHOWN ON LOT 1 OF PRIDES CROSSING IS BASED ON PLAT C.M.P. NO. 6401 FILED SEPTEMBER 30, 1985.
- 7) THE EXISTING PERCOLATION TESTING LOCATIONS ARE BASED ON A BEST FIT OF THE SIGNED PERCOLATION CERTIFICATION PLAN DATED OCTOBER, 2000.
- 8) PLEASE NOTE THAT A GRINDER AND PUMP WILL LIKELY BE NECESSARY TO ACCOMMODATE THE ELEVATION CHANGE BETWEEN THE BASEMENT AND THE PROPOSED SEPTIC AREA LOCATION.
- 9) THE HEALTH DEPARTMENT WAS CONTACTED ON OCTOBER 24, 2008 FOR A REQUEST OF INFORMATIONS UNDER THE PUBLIC INFORMATION ACT AND INDICATED THAT THE TESTING INFORMATION PREVIOUSLY ESTABLISHED ON SITE WAS DISCARDED AFTER THE FACILITIES WERE CONNECTED TO PUBLIC WATER.

I CERTIFY THAT THE INFORMATION SHOWN HEREON IS BASED ON FIELD WORK PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION, AND IS CORRECT, TO THE BEST OF KNOWLEDGE AND BELIEF.

**BRIAN F. CLEARY**  
PLAN PREPARER

APPROVED FOR PUBLIC WATER AND PRIVATE SEWERAGE SYSTEM  
**HOWARD COUNTY HEALTH DEPARTMENT**

**HOWARD COUNTY HEALTH OFFICER** \_\_\_\_\_ DATE \_\_\_\_\_

**PLAN**  
SCALE: 1" = 30'

**SOILS LEGEND**

MAP SYMBOL	SOIL GROUP	SOIL TYPE
GgB	B	GLENELG LOAM, 3 TO 8 PERCENT SLOPES
GgC	B	GLENELG LOAM, 8 TO 15 PERCENT SLOPES
GgB	B	GLENELG-URBAN LAND COMPLEX, 0 TO 8 PERCENT SLOPES
GgB	B	GLENVILLE-BAILE SILT LOAMS, 0 TO 8 PERCENT SLOPES
MacC	C	MANOR LOAM, 8 TO 15 PERCENT SLOPES

TAKEN FROM WEB SOILS SURVEY 2.0, DATED OCTOBER 2008

**BENCHMARK ENGINEERING, INC.**  
ENGINEERS • LAND SURVEYORS • PLANNERS

8480 BALTIMORE NATIONAL PIKE SUITE 418  
ELLCOTT CITY, MARYLAND 21043  
PHONE: 410-465-6105 FAX: 410-465-6644  
WWW.BEI-CIVILENGINEERING.COM

**PROFESSIONAL ENGINEER**  
BRIAN F. CLEARY  
No. 28598  
REGISTERED  
12/16/2008

Professional Certification. I hereby certify that these documents were prepared or approved by me, and that I am a duly licensed professional engineer under the laws of the State of Maryland. License No. 28559, Expiration Date: 7-22-2009.

**OWNER/DEVELOPER:** DAR AL TAQWA INC.  
10740 ROUTE 108  
ELLCOTT CITY, MD. 21042  
410-531-2235

**PROJECT:** DAR AL TAQWA PHASE III

**LOCATION:** TAX MAP 29, GRID: 11, PARCEL: 12  
2nd. ELECTION DISTRICT  
HOWARD COUNTY, MARYLAND

**TITLE:** PERCOLATION TESTING PLAN

**DATE:** DECEMBER, 2008 PROJECT NO. 2132

**DESIGN:** BFC **DRAFT:** BFC **CHECK:** BFC **SCALE:** AS SHOWN **SHEET:** 1 OF 1