



**Howard County  
Health Department**

Maura J. Rossman, M.D., Health Officer

**Bureau of Environmental Health**  
8930 Stanford Boulevard, Columbia, MD 21045  
Main: 410-313-2640 | Fax: 410-313-2648  
TDD 410-313-2323 | Toll Free 1-866-313-6300  
[www.hchealth.org](http://www.hchealth.org)  
Facebook: [www.facebook.com/hocohealth](http://www.facebook.com/hocohealth)

RECEIPT DATE: 7-20-20 **ONSITE SEWAGE DISPOSAL SYSTEM**

P 567906

APPROVAL DATE: 9/30/2020 **PERMIT: CONSTRUCTION**

A \_\_\_\_\_

PROPERTY ADDRESS: 3651 Paupers Folly Lane

SUBDIVISION: Belvedere Estates

LOT: 10 TAX ID: \_\_\_\_\_

CONTRACTOR: South Carroll Backhoe

EMAIL: scbackhoe@comcast.net

CONTRACTOR ADDRESS: 4410 Salem Bottom Road, Westminster, MD 21157

PHONE: 410-596-3618

PROPERTY OWNER: NV Homes

EMAIL: \_\_\_\_\_

OWNER ADDRESS: 9720 Patuxent Woods Drive

PHONE: 410-379-5956

SEPTIC TANK SIZE (GALLONS): 2000

TANK MANUFACTURER: Babylon

PUMP MODEL: \_\_\_\_\_ PUMP SIZE \_\_\_\_\_

PUMP TANK CAPACITY: \_\_\_\_\_

DISTRIBUTION SYSTEM:  GRAVITY  PRESSURE DOSED BEDROOMS: 6 APPLICATION RATE: 1.2


TRENCHES:	LINEAR FEET REQUIRED: <u>95 FT</u>	INLET DEPTH: <u>3FT</u>
	TRENCH WIDTH: <u>3 FT</u>	MAXIMUM BOTTOM DEPTH: <u>8 FT</u>
	MINIMUM SPACE BETWEEN TRENCHES: <u>12 FT</u>	EFFECTIVE AREA BEGINNING DEPTH: <u>3.5FT</u>
LOCATION:	PER APPROVED SITE PLAN. SEWAGE DISPOSAL AREA AND TANK LOCATIONS MUST BE STAKED BY LICENSED SURVEYOR PRIOR TO PRE-CONSTRUCTION INSPECTION.	
NOTES:	Install 2 trenches at 47.5 FT	

ISSUED BY: Hank Oswald ISSUE DATE: 7-20-20 EXPIRATION DATE: 7-20-20

- NOTE: CONTRACTOR MUST SCHEDULE A PRE-CONSTRUCTION INSPECTION PRIOR TO BEGINNING ANY INSTALLATION
- NOTE: CONTRACTOR MUST SCHEDULE AN INSPECTION AND GAIN APPROVAL OF ALL COMPONENTS PRIOR TO COVERING
- NOTE: STONE MUST BE APPROVED BY HEALTH DEPARTMENT AND GRAVEL TICKET MUST BE AVAILABLE FOR REVIEW.
- NOTE: WATERTIGHT TANKS REQUIRED
- NOTE: ALL PARTS OF SEPTIC SYSTEM SHALL BE AT LEAST 100 FEET DOWNGRADIENT FROM ANY WATER WELL
- NOTE: MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS
- NOTE: AN ELECTRICAL PERMIT IS REQUIRED FOR INSTALLATION OF ANY ELECTRICAL COMPONENTS OF THE SYSTEM  
 ELECTRICAL PERMIT ISSUED E \_\_\_\_\_
- NOTE: MDE RECOMMENDS SEPTIC TANKS, BAT, AND OTHER PRETREATMENT UNITS BE PUMPED AT A FREQUENCY ADEQUATE TO ENSURE THAT SOLIDS ARE NOT DISCHARGED TO THE DISPOSAL AREA

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.  
PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT.  
CALL 410-313-1771 TO SCHEDULE INSPECTIONS.**

NOT TO SCALE



ROAD NAME  
PAUPERS FOLLY LANE

**TRENCH/DRAINFIELD DATA**

WIDTH	INLET	BOTTOM
3'	3'	8'
NUMBER OF TRENCHES	2	
TOTAL LENGTH	100'	
ABSORPTION AREA	300 sq ft + side wall	
DISTRIBUTION BOX LEVEL	yes	
DISTRIBUTION BOX BAFFLE	yes	
DISTRIBUTION BOX PORT	yes	

**SEPTIC TANK DATA**

SEPTIC TANK 1 LEVEL	yes
MANUFACTURER	Babylon
CAPACITY	2000 GAL
SEAM LOC	top
TANK LID DEPTH	1.5'
BAFFLES	front + back
BAFFLE FILTER	-
MANHOLE LOC	front + back
6" PORT LOC	-
WATERTIGHT TEST	-
SLOTTED	yes
DATE ON LID	05/19/2020

**PUMP/SEPTIC TANK LEVEL**

MANUFACTURER	
CAPACITY	GAL
SEAM LOC	
TANK LID DEPTH	
BAFFLES	
BAFFLE FILTER	
MANHOLE LOC	
6" PORT LOC	
WATERTIGHT TEST	
SLOTTED	
DATE ON LID	

PRE-CONSTRUCTION:

08/07/2020 TANK, SDA, TRENCHES STAKED. CONFIRMED CONTOUR AND STRAIGHTENED TRENCHES. OK TO START. (S)

INSTALLATION:


08/10/2020 TANK SET. (S) 8/12/2020 Sewer line, d-box and trenches constructed Re-inspect for SHC. (S) 9/30/2020 Observed SHC. OK to backfill (S)

FINAL INSPECTOR

*Susan Thomas*

DATE OF APPROVAL

9/30/2020



0' BRL

30' BRL

(N-1) @ 1.00%

100'

BRL

50' PRIVATE ACCESS, DRAINAGE & UTILITY EASEMENT

LIMIT OF PROP. PAVING STA. 17+62

18" HDPE (24")

10' BRL

10' BRL

12" RCCP, CL IV

66.5'

70.5' R.L.

40'

55'

24'

50'

26'

18" HDPE (79')

50'

53'

55'

57'

59'

61'

63'

65'

67'

69'

71'

73'

75'

77'

79'

81'

83'

85'

87'

89'

91'

93'

95'

97'

99'

101'

103'

105'

107'

109'

111'

113'

115'

117'

119'

121'

123'

125'

127'

129'

131'

133'

135'

137'

139'

141'

143'

145'

147'

149'

151'

153'

155'

157'

159'

161'

163'

165'

167'

169'

171'

173'

175'

177'

179'

181'

183'

185'

187'

189'

191'

193'

195'

197'

199'

201'

203'

205'

207'

209'

211'

213'

215'

217'

219'

221'

223'

225'

227'

229'

231'

233'

235'

237'

239'

241'

243'

245'

247'

249'

251'

253'

255'

257'

259'

261'

263'

265'

267'

269'

271'

273'

275'

277'

279'

281'

283'

285'

287'

289'

291'

293'

295'

297'

299'

301'

303'

305'

307'

309'

311'

313'

315'

317'

319'

321'

323'

325'

327'

329'

331'

333'

335'

337'

339'

341'

343'

345'

347'

349'

351'

353'

355'

357'

359'

361'

363'

365'

367'

369'

371'

373'

375'

377'

379'

381'

383'

385'

387'

389'

391'

393'

395'

397'

399'

401'

403'

405'

407'

409'

411'

413'

415'

417'

419'

421'

423'

425'

427'

429'

431'

433'

435'

437'

439'

441'

443'

445'

447'

449'

451'

453'

455'

457'

459'

461'

463'

465'

467'

469'

471'

473'

475'

477'

479'

481'

483'

485'

487'

489'

491'

493'

495'

497'

499'

501'

503'

505'

507'

509'

511'

513'

515'

517'

519'

521'

523'

525'

527'

529'

531'

533'

535'

537'

539'

541'

543'

545'

547'

549'

551'

553'

555'

557'

559'

561'

563'

565'

567'

569'

571'

573'

575'

577'

579'

581'

583'

585'

587'

589'

591'

593'

595'

597'

599'

601'

603'

605'

607'

609'

611'

613'

615'

617'

619'

621'

623'

625'

627'


629'

631'

</



1. ANY CHANGE TO THE LOCATIONS OR DEPTHS TO ANY COMPONENTS MUST BE APPROVED BY THE ENGINEER AND THE HOWARD COUNTY HEALTH DEPARTMENT PRIOR TO INSTALLATION. A REVISED SITE PLAN MAY BE REQUIRED.
2. THE MAXIMUM EARTH COVER OVER THE TANK IS 3 FEET. GREATER EARTH COVER WILL REQUIRE A HEAVY LOAD BEARING TANK.
3. ELECTRICAL WORK FOR THE INSTALLATION MUST BE PERFORMED BY A LICENSED ELECTRICIAN.
4. THE WELL HO-17-0019 HAS BEEN FIELD LOCATED AND IS ACCURATELY SHOWN.
5. ALL WELLS AND SEPTIC SYSTEMS LOCATED WITHIN 100' OF THE PROPERTY BOUNDARIES AND 200' DOWN GRADIENT OF ANY WELLS AND/OR SEPTIC SYSTEMS HAVE BEEN SHOWN.



**PLAN**  
SCALE: 1" = 30'

**PROFESSIONAL CERTIFICATION**



I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 20748, EXPIRATION DATE: 02/22/2021.

*Michael J. Vukobratovic*  
Signature of Professional Engineer  
5/13/2020  
DATE




**OWNER/DEVELOPER**  
NV HOMES  
9720 PATUXENT WOODS DRIVE  
COLUMBIA, MD 21046  
410-379-9996


**FISHER, COLLINS & CARTER, INC.**  
CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS  
CENTRAL SQUARE OFFICE PARK - 10272 BALTIMORE NATIONAL PIKE  
ELIJAH CITY, MARYLAND 21042  
(410) 461-1222



BABYLON VAULT CO.	
25 WINDSOR VALLEY RD	
MIDDLEBURY, VT 05750	
404-883-0000	
2000 T.S.W.C.	
Model	
Size	
Material	
Color	



**VICINITY MAP**  
SCALE: 1" = 1200'



**SEPTIC PROFILE**  
SCALE: 1" = 30'

NOTE: NO GRAVITY SEWER SERVICE FOR BASEMENT


FFE 573.60  
BSE 563.76  
INV. OUT OF HOUSE = 569.81  
PROP. GROUND AT CLEANOUT #1 = 571.4  
INV. INTO CLEANOUT = 569.7  
INV. OUT OF CLEANOUT = 569.6  
EX. GROUND AT SEPTIC TANK = 570.4  
TOP OF SEPTIC TANK = 570.4  
PROP. GRADE ABOVE SEPTIC TANK = 570.45  
INV. INTO SEPTIC TANK = 568.45  
INV. OUT OF SEPTIC TANK = 568.2  
EX. GROUND AT DISTRIBUTION BOX = 570.4  
INV. INTO DISTRIBUTION BOX = 568.0  
INV. OUT OF DISTRIBUTION BOX = 567.9

**INITIAL SYSTEM**

SEWAGE DISPOSAL SYSTEM DATA, DESIGN FOR 6 BEDROOMS PERMIT FOR 5  
LOADING RATE = 6 BEDROOMS X 150 GPD/BEDROOM = 900 GPD  
APPLICATION RATE = 1.2  
EFFECTIVE SIDEWALL BEGINS AT 3.5 FEET  
TRENCH DEPTH = 8 FEET  
TRENCH WIDTH (W) = 3 FEET  
EFFECTIVE DEPTH (D) = 4.5 FEET  
SF OF DRAINFIELD = 900 GPD / 1.2 = 750 SF  
COEFFICIENT OF REDUCTION OF TRENCH LENGTH = (W+2)/(W+1+2D) = (3+2)/(3+1+(2x4.5)) = 0.38  
TRENCH LENGTH = 291.67 SF x 0.38 = 95.00 FEET (2 TRENCHES 47.50)  
TRENCH SPACING = 2D+W = ((2x4.5) + 3) = 12' USE 12'

**1ST REPLACEMENT SYSTEM**

SEWAGE DISPOSAL SYSTEM DATA, DESIGN FOR 6 BEDROOMS PERMIT FOR 5  
LOADING RATE = 6 BEDROOMS X 150 GPD/BEDROOM = 900 GPD  
APPLICATION RATE = 1.2  
EFFECTIVE SIDEWALL BEGINS AT 3 FEET  
TRENCH DEPTH = 8 FEET  
TRENCH WIDTH (W) = 3 FEET  
EFFECTIVE DEPTH (D) = 5 FEET  
SF OF DRAINFIELD = 900 GPD / 1.2 = 750 SF  
COEFFICIENT OF REDUCTION OF TRENCH LENGTH = (W+2)/(W+1+2D) = (3+2)/(3+1+(2x5)) = 0.35  
TRENCH LENGTH = 291.67 SF x 0.35 = 87.50 FEET (2 TRENCHES 43.75)  
TRENCH SPACING = 2D+W = ((2x5) + 3) = 13' USE 13'



**INITIAL TRENCH DETAIL**  
SCALE: 1" = 2'

**TRENCH DATA:**

**TRENCH 1:**  
EX. GROUND ABOVE = 570.4  
INV. IN = 567.8  
BOTTOM TRENCH = 562.4

**TRENCH 2:**  
EX. GROUND ABOVE = 570  
IN = 567.6  
BOTTOM TRENCH = 562.0

**2ND REPLACEMENT SYSTEM**

SEWAGE DISPOSAL SYSTEM DATA, DESIGN FOR 6 BEDROOMS PERMIT FOR 5  
LOADING RATE = 6 BEDROOMS X 150 GPD/BEDROOM = 900 GPD  
APPLICATION RATE = 1.2  
EFFECTIVE SIDEWALL BEGINS AT 3 FEET  
TRENCH DEPTH = 8 FEET  
TRENCH WIDTH (W) = 3 FEET  
EFFECTIVE DEPTH (D) = 5 FEET  
SF OF DRAINFIELD = 900 GPD / 1.2 = 750 SF  
COEFFICIENT OF REDUCTION OF TRENCH LENGTH = (W+2)/(W+1+2D) = (3+2)/(3+1+(2x5)) = 0.35  
TRENCH LENGTH = 291.67 SF x 0.35 = 87.50 FEET (2 TRENCHES 43.75)  
TRENCH SPACING = 2D+W = ((2x5) + 3) = 13' USE 13'

Approved Septic System Plan  
Howard County Health Department  
*Mark Oswald* 2/20/20  
Signature Date

**SEPTIC SYSTEM INSTALLATION SITE PLAN**  
**BELVEDERE ESTATES**  
LOT 10


3651 PAUPERS FOLLY LANE  
ZONED: RC-DEO  
TAX MAP NO.: 22 GRID NO.: 8 PARCELS NO.: 116 AND PLO 7  
THIRD ELECTION DISTRICT HOWARD COUNTY, MARYLAND  
SCALE: AS SHOWN DATE: APRIL 14, 2020  
SHEET 1 OF 1

**NOTE:**

THE EXISTING WELLS SHOWN ON THIS PLAN, HO-17-0019 HAS BEEN FIELD LOCATED BY FISHER, COLLINS & CARTER, INC. PROFESSIONAL LAND SURVEYORS AND IS ACCURATELY SHOWN.

**STORMWATER MANAGEMENT NOTES:**

STORMWATER MANAGEMENT FOR LOT 10 IS BEING PROVIDED BY A COMBINATION OF MICRO-BIORETENTION FACILITY #1 (M-6) FOR THE DRIVEWAY AREA, AND 4 DRYWELLS (M-5), FOR THE ROOF AREAS OF THE PROPOSED HOUSE.




**HOUSE DRAINAGE AREAS**

SCALE: 1" = 30'

NOTE: NO GRAVITY SEWER SERVICE FOR BASEMENT.

**OWNER/DEVELOPER**

NV HOMES  
9720 PATUXENT WOODS DRIVE  
COLUMBIA, MD 21046  
410-379-5956



NOTE: THE EXISTING WELL SHOWN ON THIS PLAN, HO-17-0019, HAS BEEN FIELD LOCATED BY FISHER, COLLINS & CARTER, INC., PROFESSIONAL LAND SURVEYORS AND IS ACCURATELY SHOWN.

**FISHER, COLLINS & CARTER, INC.**  
CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS  
CENTENNIAL SQUARE OFFICE PARK - 10272 BALTIMORE NATIONAL PIKE  
ELIJAH CITY, MARYLAND 21042  
(410) 461-2895

**PLAN**


SCALE: 1" = 30'

**PERMIT SITE PLAN  
BELVEDERE ESTATES  
LOT 10**


3651 PAUPERS FOLLY LANE  
ZONED: RC-DEO

TAX MAP NO.: 22 GRID NO.: 8 PARCELS NO.: 116 AND PLO 7  
THIRD ELECTION DISTRICT HOWARD COUNTY, MARYLAND  
SCALE: AS SHOWN DATE: APRIL 10, 2020  
SHEET 1 OF 1

1. ANY CHANGE TO THE LOCATIONS OR DEPTHS TO ANY COMPONENTS MUST BE APPROVED BY THE ENGINEER AND THE HOWARD COUNTY HEALTH DEPARTMENT PRIOR TO INSTALLATION. A REVISED SITE PLAN MAY BE REQUIRED.
2. THE MAXIMUM EARTH COVER OVER THE TANK IS 3 FEET. GREATER EARTH COVER WILL REQUIRE A HEAVY LOAD BEARING TANK.
3. ELECTRICAL WORK FOR THE INSTALLATION MUST BE PERFORMED BY A LICENSED ELECTRICIAN.
4. THE WELL HO-17-0019 HAS BEEN FIELD LOCATED AND IS ACCURATELY SHOWN.
5. ALL WELLS AND SEPTIC SYSTEMS LOCATED WITHIN 100' OF THE PROPERTY BOUNDARIES AND 200' DOWN GRADIENT OF ANY WELLS AND/OR SEPTIC SYSTEMS HAVE BEEN SHOWN.




**PLAN**  
SCALE: 1" = 30'





**FISHER, COLLINS & CARTER, INC.**  
CIVIL ENGINEERING CONSULTANTS & LAND SURVEYORS  
CENTENNIAL SQUARE OFFICE PARK - 10722 BALDORNE NATIONAL FLEE  
ELLCOTT CITY, MARYLAND 21046  
(410) 461-2895


**OWNER/DEVELOPER**  
INV HOMES  
9720 PATUXENT WOODS DRIVE  
COLUMBIA, MD 21046  
410-375-5996



**PROFESSIONAL CERTIFICATION**  
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 20748, EXPIRATION DATE: 02/22/2021.  
*Michael J. Wilbur*  
Signature of Professional Engineer  
5/13/2020  
DATE



**VICINITY MAP**  
SCALE: 1" = 1200'




**SEPTIC PROFILE**  
SCALE: 1" = 30'

NOTE: NO GRAVITY SEWER SERVICE FOR BASEMENT

FFE 573.60  
BSE 563.76  
INV. OUT OF HOUSE = 569.81  
PROP. GROUND AT CLEANOUT #1 = 571.4  
INV. INTO CLEANOUT = 569.7  
INV. OUT OF CLEANOUT = 569.6  
EX. GROUND AT SEPTIC TANK = 570.4  
PROP. GRADE ABOVE SEPTIC TANK = 570.4  
TOP OF SEPTIC TANK = 569.45  
INV. INTO SEPTIC TANK = 568.45  
INV. OUT OF SEPTIC TANK = 568.2  
EX. GROUND AT DISTRIBUTION BOX = 570.4  
INV. INTO DISTRIBUTION BOX = 568.0  
INV. OUT OF DISTRIBUTION BOX = 567.9

**INITIAL SYSTEM**  
SEWAGE DISPOSAL SYSTEM DATA, DESIGN FOR 6 BEDROOMS PERMIT FOR 5  
LOADING RATE = 6 BEDROOMS X 150 GPD/BEDROOM = 900 GPD  
APPLICATION RATE = 1.2  
EFFECTIVE SIDEWALL BEGINS AT 3.5 FEET  
TRENCH DEPTH = 8 FEET  
TRENCH WIDTH (W) = 3 FEET  
EFFECTIVE DEPTH (D) = 4.5 FEET  
SF OF DRAINFIELD = 900 GPD / 1.2 = 750 SF  
COEFFICIENT OF REDUCTION OF TRENCH LENGTH = (W+2)/(W+1+2D) = (3+2)/(3+1+(2x4.5)) = 0.38  
TRENCH LENGTH = 291.67 SF x 0.38 = 95.00 FEET (2 TRENCHES 47.50)  
TRENCH SPACING = 2D+W = ((2x4.5) + 3) = 12' USE 12'

**1ST REPLACEMENT SYSTEM**  
SEWAGE DISPOSAL SYSTEM DATA, DESIGN FOR 6 BEDROOMS PERMIT FOR 5  
LOADING RATE = 6 BEDROOMS X 150 GPD/BEDROOM = 900 GPD  
APPLICATION RATE = 1.2  
EFFECTIVE SIDEWALL BEGINS AT 3 FEET  
TRENCH DEPTH = 8 FEET  
TRENCH WIDTH (W) = 3 FEET  
EFFECTIVE DEPTH (D) = 5 FEET  
SF OF DRAINFIELD = 900 GPD / 1.2 = 750 SF  
COEFFICIENT OF REDUCTION OF TRENCH LENGTH = (W+2)/(W+1+2D) = (3+2)/(3+1+(2x5)) = 0.35  
TRENCH LENGTH = 291.67 SF x 0.35 = 87.50 FEET (2 TRENCHES 43.75)  
TRENCH SPACING = 2D+W = ((2x5) + 3) = 13' USE 13'



**INITIAL TRENCH DETAIL**  
SCALE: 1" = 2'

**TRENCH DATA:**  
TRENCH 1:  
EX. GROUND ABOVE = 570.4  
INV. IN = 567.8  
BOTTOM TRENCH = 562.4  
TRENCH 2:  
EX. GROUND ABOVE = 570  
IN = 567.6  
BOTTOM TRENCH = 562.0

**2ND REPLACEMENT SYSTEM**  
SEWAGE DISPOSAL SYSTEM DATA, DESIGN FOR 6 BEDROOMS PERMIT FOR 5  
LOADING RATE = 6 BEDROOMS X 150 GPD/BEDROOM = 900 GPD  
APPLICATION RATE = 1.2  
EFFECTIVE SIDEWALL BEGINS AT 3 FEET  
TRENCH DEPTH = 8 FEET  
TRENCH WIDTH (W) = 3 FEET  
EFFECTIVE DEPTH (D) = 5 FEET  
SF OF DRAINFIELD = 900 GPD / 1.2 = 750 SF  
COEFFICIENT OF REDUCTION OF TRENCH LENGTH = (W+2)/(W+1+2D) = (3+2)/(3+1+(2x5)) = 0.35  
TRENCH LENGTH = 291.67 SF x 0.35 = 87.50 FEET (2 TRENCHES 43.75)  
TRENCH SPACING = 2D+W = ((2x5) + 3) = 13' USE 13'

Approved Septic System Plan  
Howard County Health Department  
*Hank Oswald* 6/20/20  
Signature Date

**SEPTIC SYSTEM INSTALLATION SITE PLAN**  
**BELVEDERE ESTATES**  
LOT 10  
3651 PAUPERS FOLLY LANE  
ZONED: RC-DEO  
TAX MAP NO.: 22 GRID NO.: 8 PARCELS NO.: 116 AND P.O. 7  
THIRD ELECTION DISTRICT HOWARD COUNTY, MARYLAND  
SCALE: AS SHOWN DATE: APRIL 14, 2020  
SHEET 1 OF 1

NOTE:  
THE EXISTING WELLS SHOWN ON THIS PLAN, HO-17-0019 HAS BEEN FIELD LOCATED BY FISHER, COLLINS & CARTER, INC., PROFESSIONAL LAND SURVEYORS AND IS ACCURATELY SHOWN.