

12/10/75
12/10/75

PERMIT

SEWAGE DISPOSAL SYSTEM

A 1301

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

INDEXED

DISTRICT 4

DATE 12/7/75

Howard Pickett IS PERMITTED TO INSTALL X ALTER

ADDRESS Waterville Road, Mount Airy, Maryland PHONE 829-0543

A SEWAGE DISPOSAL SYSTEM LOCATED AT _____

SUBDIVISION Shaffersville Estates ROAD Shaffer Mill Road LOT 2

PROPERTY OWNER Ms. J. Blackart, Sr., et. al.

ADDRESS _____

SPECIFICATIONS - 3 bedrooms

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA _____ SQ. FT.

SEPTIC TANK CAPACITY 1,000 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%

OTHER Dry well - 120 sq. ft. absorbent sidewall area per bedroom to begin below

the first 4 ft. of original grade. Max. depth permitted for dry well is 12 ft. below

original grade. Place dry well 120 ft. from front lot line and 25 ft. from left side line

as seen when facing from Shaffer Mill Road.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.

PERMIT VOID AFTER THESE YEARS.

NOTE: INSTALL CLEANOUTS ON SEPTIC TANK AND DRY WELL. CLEANOUTS MUST BE 6" IN DIA.,

PLANS APPROVED BY D. W. Monaghan DATE 9/4/75
CONCRETE, CAST IRON OR TERRA COTTA ACCEPTED.

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

12/10/75