

LAYOUT 11/22/04-11 INSP 4 12/23/04 - PM  
INSP 2 \_\_\_\_\_ INSP 5 \_\_\_\_\_  
INSP 3 \_\_\_\_\_ INSP 6 \_\_\_\_\_

ISSUE DATE: 11/12/04

P 521574

APPROVAL DATE: 2/25/05

A 514944

# PERMIT

## SANDMOUND SYSTEM ON-SITE SEWAGE DISPOSAL SYSTEM HOWARD COUNTY HEALTH DEPARTMENT BUREAU OF ENVIRONMENTAL HEALTH

Cumberland Development Corp. IS PERMITTED TO INSTALL  ALTER

ADDRESS: 16391 A E Mullinix Road PHONE NUMBER: 301-854-6838

SUBDIVISION: Twin Pines Parcel A

ADDRESS: 3142 Stiles Way PROPERTY OWNER: Cliff & Betty Harrison

SEPTIC TANK CAPACITY (GALLONS): 1250 OUTLET BAFFLE FILTER REQUIRED

PUMP CHAMBER CAPACITY (GALLONS): 1250 COMPARTMENTED TANK REQUIRED

NUMBER OF BEDROOMS: 4

|           |  |
|-----------|--|
| LOCATION: | Sandmound Area #1-Prior to starting work ,review notes on design with inspecting sanitarian during pre-construction inspection. DO NOT begin if soils are wet or frozen, temperature must be above 32 degrees. Mound width = 29' , length = 122' |
| NOTES:    | See mound layout pages attached for lateral layouts.   |

PLANS APPROVED: Kacie Noonan DATE: 11/8/04

NOTES: PERMIT VOID AFTER 2 YEARS  
CONTRACTOR IS RESPONSIBLE FOR SCHEDULING A PRE-CONSTRUCTION INSPECTION FOR ALL INSTALLATIONS  
WATERTIGHT SEPTIC TANKS REQUIRED  
ALL PARTS OF SEPTIC SYSTEM SHALL BE 100 FEET FROM ANY WATER WELL UNLESS SPECIFICALLY AUTHORIZED  
MANHOLE RISERS REQUIRED ON ALL SEPTIC TANKS AND PUMP CHAMBERS UNLESS SPECIFICALLY AUTHORIZED  
CONTRACTOR RESPONSIBLE FOR COMPLIANCE WITH APPLICABLE REGULATIONS, GUIDELINES AND THE TERMS OF THIS PERMIT

**NEITHER THE HOWARD COUNTY COUNCIL NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM PERMITTEE RESPONSIBLE FOR OBTAINING FINAL APPROVAL ON THIS PERMIT ALL 410-313-2640 FOR INSPECTION OF SEPTIC SYSTEM**

*Curtis Cumberland*  
*301-252-1122*

# SAND MOUND

## SEPTIC SPECIFICATIONS WORK-SHEET

PS21574

SUBDIVISION: KINGS Grant

A 514944

STREET NAME: 3142 Styles Way

LOT NUMBER: Parcel A

AVERAGE PERCOLATION RATE:      SQUARE FEET PER BEDROOM:     

NUMBER OF BEDROOMS: 4 LINEAR FEET OF TRENCH PER BEDROOM:     

TOTAL LINEAR FEET OF TRENCH:      SEPTIC TANK CAPACITY:     

TOP SEAMED TANK REQUIRED?  YES  NO

COMPARTMENTED TANK REQUIRED?  YES  NO

TRENCH DIMENSIONS: Trench to be      feet wide. Inlet      feet below original grade. Bottom maximum depth      feet below original grade. Effective area begins at      feet below original grade.      feet of stone below distribution pipe.

===== PUMPED SYSTEM PROPOSED:  YES  NO

PUMPED SEPTIC SYSTEM DETAIL: 1250 gallon pump chamber.

YES  NO Top seamed pump chamber required?

Note 1: Septic pump detail to be provided by installer prior to issuance of septic permit.

Note 2: Pump performance test is necessary prior to Health Department approval of pumped septic system.

===== LOCATION: SAND MOUND AREA #1. Prior to starting work, review.

NOTES ON DESIGN W/ SANITARIAN DURING PRE-CONSTRUCTION

DO NOT BEGIN IF SOILS ARE WET OR FROZEN!!!

MOUND WIDTH = 29', LENGTH = 122'

ADDITIONAL NOTES: SEE MOUND LAYOUT PAGES ATTACHED

For lateral layouts, pump size, etc.


Reviewer: KN

Date: 11-8-04

Tank 1 - 1250 Top Seam

Manhole in Back  
2'-2.5' Below Grade  
Baffles In Tank

NOT TO SCALE



**DOSING CHAMBER**

Tank Level   
Capacity 1250 Gal  
Seam Location Top  
Tank Lid Depth 1.5'-2.5'  
Manhole Location Middle  
Water Tight Test No  
Baffle in Front

**FLOAT SETTINGS**

Low Off 1 \_\_\_\_\_  
Low On 2 \_\_\_\_\_  
High On 3 \_\_\_\_\_  
Alarm 4 \_\_\_\_\_  
Dose Volume \_\_\_\_\_

**SAND MOUND I**

Bed Length \_\_\_\_\_  
Bed Width \_\_\_\_\_  
Bed Area \_\_\_\_\_ sq ft  
Mound Length \_\_\_\_\_  
Mound Width \_\_\_\_\_  
Mound Area \_\_\_\_\_  
Basal Area \_\_\_\_\_ sq ft

**SAND MOUND II**

Bed Length \_\_\_\_\_  
Bed Width \_\_\_\_\_  
Bed Area \_\_\_\_\_ sq ft  
Mound Length \_\_\_\_\_  
Mound Width \_\_\_\_\_  
Mound Area \_\_\_\_\_  
Basal Area \_\_\_\_\_ sq ft

2/23/05 Turn-up extended and hole plugged. (BB)

PRE-CONSTRUCTION 11/22/04 SRA stake. Individual sand mound woods to be staked. OK to set tanks & run pressure line (SO)

INSTALLATION 11/29/04 Tanks set. Recommended installing an effluent filter. This will require moving the manhole to the rear of the first tank. Barry is checking on whether sand from S.W. Barrick can be used. Sand from Sloan should be O.K. (BB)

12/6/04 - Sand installed, gravel bed dug out, OK to cont. (SO)

12/3/04 S.W. Barrick sand meets specs. (BB) 12/13/04 - Gravel set in bed laterals installed OK to cont. (SO) 12/15/04 Installing

FINAL INSPECTOR B. Baker DATE OF APPROVAL 2/25/05

clay cap. Mound fabric looks unusual. Stuart approved? (BB)  
Alarm O.K. - hole in pipe at 2 feet on pump. Needs sealed. (PAY) 2/16/05

# HARRISON PROPERTY

## Sand Mound Construction Details and Specifications

### Prepared For:

Cumberland Development Corp.  
16391 A.E. Mullinix Road  
Woodbine, Maryland 21797  
301.854.6325

### Prepared By:

FSH Associates  
8318 Forrest Street  
Ellicott City, Maryland 21043  
File No. 3123

October 22, 2004

# FSH Associates

Engineers Planners Surveyors  
 8318 Forrest Street  
 ELLICOTT CITY, MD 21043  
 (410) 750-2251 Fax (410) 750-7350

JOB HARRISON RESIDENCE

SHEET NO. 2 OF 3

CALCULATED BY F. SILL DATE 10.08.04

CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_

SCALE NO SCALE

INV @ MOUND : 478.83

PIPE RUN + MANIFOLD : 226' ; V = 86.78 GAL @ 3" diameter pvc

MINOR LOSSES : 7 BENDS @ 6' = 42' + 1 DISCONNECT UNION @ 3' = 45'

LATERAL LENGTH : 196' ; V = 20.77 GAL (1-1/2" SCH 40 PIPE)


DOSE AMOUNT : 86.78 + 20.77 + (5 x 20.77) = 211 GALLONS

1/6 DESIGN FLOW = 750 x 1/6 = 125 GAL

∴ USE 211 GAL

PUMP CHAMBER CAPACITY : 750 + 211 = 961 GAL

PUMP CHAMBER SIZE :



PUMP OFF 470.96

PUMP ON 471.84

HIGH WATER ALARM 472.34

- STORAGE BETWEEN INVERT IN OF PUMP TANK AND HIGH WATER ALARM = 730 GALLONS
- 80 ADDITIONAL GALLONS OF STORAGE AVAILABLE WITHIN SEPTIC TANK FOR A TOTAL STORAGE OF 810 GALLONS

# FSH Associates

Engineers Planners Surveyors  
8318 Forrest Street  
ELLCOTT CITY, MD 21043  
(410) 750-2251 Fax (410) 750-7350

JOB HARRISON RESIDENCE  
SHEET NO. 3 OF 3  
CALCULATED BY P. SILL DATE 10.11.04  
CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_  
SCALE NO SCALE

- FLOW FOR 5/16" PERFORATIONS IS 1.63 GPM  
4 LATERALS X 14 PERFORATIONS EACH = 56 ✓  
 $56 \times 1.63 \text{ GPM} = 91.28 \text{ GPM}$
- STATIC HEAD =  $478.83 - 470.96 = 7.87'$  ✓
- FRICTION HEAD =  $226' + 45' = 2.71'$
- FRICTION LOSS =  $1.78 \times 2.71 = 4.82$  ✓
- TOTAL DYNAMIC HEAD =  $7.87' + 4.82' + 2.0' \text{ (DISTALEND)} = 14.69'$  ✓

Pump to deliver 91.28 gpm

TWIN PINES  
PRES. PARCEL  
11% SLOPE  
2 LONG SAND  
MOUNDS

**TABLE 3.1**

**EQUATIONS FOR CALCULATING SAND MOUND DIMENSIONS**

$$\text{Absorption bed ft.}^2 (A \times B) = \frac{\text{Design flow}}{1.2 \text{ gpd/ft.}^2} = \frac{750.6 \text{ gpd}}{1.2} = 625 \text{ ft.}^2$$

$$\text{Bed length (B)} = 100 \text{ ft. (21 ft. to 101 ft. dependent on site)}$$

$$\text{Bed width (A)} = \frac{\text{Bed } 625 \text{ ft.}^2}{B \text{ } 100 \text{ ft.}} = 6.25 \text{ ft. (15 ft. or less)}$$

$$\text{Upslope sand fill depth (D)} = 48 \text{ in.} - Z \text{ in.} = 12 \text{ in. (12 in. min.)}$$

$$\text{Downslope sand fill depth (E)} = [12 A \times \% \text{ slope}] + D \text{ in.} = 20.3 \text{ in.}$$

$$\text{Cap + topsoil at bed center (H)} = 18 \text{ in.}$$

$$\text{Cap + topsoil at bed edge (G)} = 12 \text{ in.}$$

$$\text{Total Bed Depth (F)} = 10 \text{ in.}$$

$$\text{Sideslope setback (K)} = \frac{[(D + E) + 28 \text{ in.}] \times 3}{2} = 132.5 \text{ in.}$$

$$\text{Upslope setback (J)} = (22 \text{ in.} + D) \times 3 \times \text{upslope corr. factor} = 74.5 \text{ in.}$$

$$\text{Downslope setback (I)} = (22 \text{ in.} + E) \times 3 \times \text{downslope corr. factor} = 199.2 \text{ in.}$$

$$\text{Total Width of Mound (W)} = 12A + J + I = 348.7 \text{ in. } 29'$$


$$\text{Total Length of Mound (L)} = 12B + K_1 + K_2 = 1465.0 \text{ in. } 122'$$

BASAL AREA REQUIRED = 1500 #

BASAL AREA PROVIDED = (A+I) B = 2285 #


**FSH Associates**

Engineers Planners Surveyors  
8318 Forrest Street Ellicott City, MD 21043  
Tel: 410-750-2251 Fax: 410-750-7350  
E-mail: FSHAssociates@cs.com




## HYDRAULIC PROFILE

Not to Scale




## SAND MOUND DETAIL

Not to Scale




MOUND LAYOUT

Not to Scale




LATERAL DETAIL


Not to Scale



**SUPPLY LINE - MANIFOLD DETAIL**  
 Not to Scale



LATERAL END TURN-UP  
USE ON LATERAL FARTHEST FROM PUMP  
AND ON LATERAL DIAGONALLY ACROSS BED  
 Not to Scale



LATERAL END CAP

USE ON LATERAL NOT  
EQUIPPED WITH TURN-UP

Not to Scale

**EDARA Submersible Stainless Steel Pumps**


**DWU – Dominator**

**Dimensions**

Project: \_\_\_\_\_ Model: \_\_\_\_\_ Chk'd: \_\_\_\_\_ Date: \_\_\_\_\_

**Model DWU**  
Manual Operation Pumps

Unit: inch (mm)



| Phase  | Size<br>ø    | Model       | Output |       | Pump          | Weight<br>Lbs (kg) |
|--------|--------------|-------------|--------|-------|---------------|--------------------|
|        |              |             | kw     | HP    | H             |                    |
| Single | 2"<br>(50mm) | 50DWU6.4S   | 0.4    | 1/2   | 21 1/8 (550)  | 35 (16)            |
|        |              | 50DWU6.75S  | 0.75   | 1     | 22 1/16 (580) | 40 (18)            |
|        |              | 50DWU6.4S2  | 0.4    | 1/2   | 19 1/8 (485)  | 35 (16)            |
|        |              | 50DWU6.75S2 | 0.75   | 1     | 20 1/4 (515)  | 40 (18)            |
|        |              | 50DWU6.11S2 | 1.1    | 1 1/2 | 20 1/4 (515)  | 44 (20)            |
|        |              | 50DWU6.15S2 | 1.5    | 2     | 24 (610)      | 51 (23)            |
| Three  | 2"<br>(50mm) | 50DWU6.4    | 0.4    | 1/2   | 19 1/8 (485)  | 33 (15)            |
|        |              | 50DWU6.75   | 0.75   | 1     | 19 1/8 (485)  | 35 (16)            |
|        |              | 50DWU6.11   | 1.1    | 1 1/2 | 20 1/4 (515)  | 40 (18)            |
|        |              | 50DWU6.15   | 1.5    | 2     | 20 1/4 (515)  | 44 (20)            |



EBARA Submersible Stainless Steel Pumps


DWU, DWXU - Dominator

Performance Curves

Project: GPM: TDH: EFF: HP: Chk'd: Date:


50DW6.4 (1/2HP) Synchronous Speed: 3600 RPM

2 inch Discharge



50DW6.75 (1HP) Synchronous Speed: 3600 RPM

2 inch Discharge



**EBARA Submersible Stainless Steel Pumps**

**DWU, DWXU – Dominator**

**Specifications and Selection Chart**

**Model DWXAU**


**DWXFAU**







**Automatic Operation Pumps**

|   | Standard  | Optional   |
|---|---|------------|
| Discharge Size  | 2 inch  |            |
| Range of HP<br>Range of Performance   | 1/2 HP to 1 1/2 HP<br>Capacity 8 to 140 GPM<br>Head 8 to 32 feet  |            |
| Limitation<br>Maximum Water Temperature   | 104°F (40°C)  |            |
| Synchronous Speed   | 3600 RPM  |            |
| Materials<br>Casing<br>Impeller<br>Shaft<br>Motor Frame<br>Fastener   | 304 Stainless Steel<br>304 Stainless Steel<br>303 Stainless Steel<br>304 Stainless Steel<br>304 Stainless Steel   |            |
| Mechanical Seal<br>Material – Upper Side<br>Material – Lower Side<br>Impeller Type<br>Bearing<br>Motor<br>Single Phase<br>Motor Protection<br>Accessories | Double Mechanical Seal<br>Carbon/Ceramic<br>Silicon Carbide/Silicon Carbide<br>Vortex<br>Prelubricated Ball Bearing<br>Air-filled, Insulation Class F<br>115 V (1/2, 1HP), 208/230V<br>Built-in Overload Protection (Single Phase models)<br>Submersible Cable 20 ft. | QDC System |

**Selection Chart**

**Single Phase**





**PERMANENT SEEDING NOTES**

APPLY TO GRADED OR CLEANED AREAS NOT SUBJECT TO FURTHER DISTURBANCE HEREIN. A PERMANENT LONG-TERM VEGETATIVE COVER IS REQUIRED.

**SEEDING PREPARATION:** Loosen upper three inches of soil by raking, digging or other acceptable means before seeding, if not previously amended.

**SOIL AMENDMENTS:** In lieu of soil test recommendations, use one of the following schedules:

- 1) Preferred - Apply 2 tons per acre diammonium phosphate (32 lbs/100 sq ft) and 400 lbs per acre 10-10-10 fertilizer (14 lbs/100 sq ft) before seeding. Harrow or disc into upper three inches of soil. At the time of seeding, apply 400 lbs per acre 30-0-0 ureamiform fertilizer (14 lbs/100 sq ft).
- 2) Acceptable - Apply 2 tons per acre diammonium phosphate (32 lbs/100 sq ft) and apply 1000 lbs per acre 10-10-10 fertilizer (28 lbs/100 sq ft) before seeding. Harrow or disc into upper three inches of soil.

**SEEDING:** For the period March 1 thru April 30, and August 1 thru October 15, seed with 60 lbs per acre (1.4 lbs/1000 sq ft) of Kentucky 31 Tall Fescue per acre and 2 lbs per acre (0.5 lbs/1000 sq ft) of creeping lovegrass. During the period of October 15 thru February 28, protect site by Option (1) 2 tons per acre well anchored straw mulch and seed as soon as possible in the spring. Option (2) Use seed, Option (3) Seed with 60 lbs/acre Kentucky 31 Tall Fescue and mulch with 2 tons/acre well anchored straw.

**PLANTING:** Apply 1/2 to 2 tons per acre (70 to 40 lbs/1000 sq ft) of untreated small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 20 gallons per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 340 gallons per acre (8 gal/1000 sq ft) for anchoring.

**MAINTENANCE:** Inspect all seeded areas and make needed repairs, replacements and reseeding.

**21.0 STANDARDS AND SPECIFICATIONS FOR TOPSOIL**

**Definition:** Placement of topsoil over a prepared subsoil prior to establishment of permanent vegetation.


**Purpose:** To provide a suitable soil medium for vegetable growth. Soils of coarsest texture shall be between 6.0 and 7.6; if the tested soil demonstrates a pH of less than 6.0, soil amendments shall be prescribed to raise the pH to 6.5 or higher.

**Grades on the area to be topsoiled, which have been previously established, shall be maintained, about 2\"/>**

**SAND MOUND DETAIL**  
Not to Scale

**SOILS LEGEND**

| SYMBOL | NAME / DESCRIPTION   | SOIL GROUP |
|--------|--|------------|
| CHC2   | Chester silt loam, 8 to 15 percent slopes, moderately eroded   | B          |
| CHD2   | Chester silt loam, 15 to 25 percent slopes, moderately eroded  | B          |
| Cs     | Conasa silt loam   | B          |
| MgC2   | Manor gravelly loam, 8 to 15 percent slopes, moderately eroded | B          |
| MIB2   | Manor loam, 3 to 8 percent slopes, moderately eroded           | B          |
| MID2   | Manor loam, 15 to 25 percent slopes, moderately eroded         | B          |
| MID3   | Manor loam, 15 to 25 percent slopes, moderately eroded         | B          |
| MIE    | Manor loam, 25 to 45 percent slopes                            | B          |
| MIF    | Manor very stony loam, 25 to 60 percent slopes                 | B          |



**SEDIMENT CONTROL NOTES**

1. A minimum of 48 hours notice must be given to the Howard County Department of Inspection, License and Permits (Sediment Control) prior to the start of any construction (C10-105).
2. All vegetation and structural practices are to be installed according to the provisions of this plan and are to be in conformance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL, and revisions thereto.
3. Following initial soil disturbance or redistribution, permanent or temporary stabilization shall be completed within (a) 7 calendar days for all perimeter sediment control structures, dikes, perimeter slopes, and all slopes greater than 3:1, (b) 14 days for all other disturbed or graded areas on the project site.
4. All sediment traps/basins shall be fenced and warning signs posted around their perimeter in accordance with Vol. 1, Chapter 7, HOWARD COUNTY DESIGN MANUAL, Storm Drainage.
5. All disturbed areas must be stabilized within the time period specified above in accordance with the 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL for permanent seeding, sod, temporary seeding, and mulching (Sec. G). Temporary stabilization with mulch alone shall be done when recommended seeding dates do not allow for proper germination and establishment of grasses.
6. All sediment control structures are to remain in place and are to be maintained in operative condition until permanent vegetation has been established from the Howard County Sediment Control Inspector.
7. Site Analysis:
 

|                                    |             |
|------------------------------------|-------------|
| Total Area                         | 19.97 Acres |
| Area Disturbed                     | 0.24 Acres  |
| Area to be roofed or paved         | 0.24 Acres  |
| Area to be vegetatively stabilized | 0.60 Acres  |
| Total Cut                          | 540 CY      |
| Total Fill                         | 490 CY      |
| Offsite waste/borrow area location | ##          |
8. Any sediment control practice which is disturbed by grading activity for placement of utilities must be repaired on the same day of disturbance.
9. Additional sediment controls must be provided, if deemed necessary by the Howard County Sediment Control Inspector.
10. On all sites with disturbed areas in excess of 2 acres, approval of the inspection agency shall be requested upon completion of installation of perimeter erosion and sediment controls, but before proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until this initial approval by the inspection agency is made.
11. Trenches for the construction of utilities is limited to three pipe lengths or that which shall be back-filled and stabilized within one working day, whichever is shorter.
12. Earthwork quantities are solely for the purpose of calculating fees. Contractor to verify all quantities prior to the start of construction.
13. To be determined by contractor, with pre-approval of the Sediment Control Inspector with an approved and active grading permit.

**TEMPORARY SEEDING NOTES**

**SEEDING PREPARATION:** Loosen upper 1 1/2 inches of soil by raking, digging or other acceptable means before seeding, if not previously amended.

**SOIL AMENDMENTS:** Apply 400 lbs per acre 10-10-10 fertilizer (14 lbs/100 sq ft).









**SEEDING:** For the period March 1 thru April 30 and from August 15 thru November 15, seed with 2 1/2 bushels per acre of annual ryegrass (3.2 lbs/1000 sq ft) for the period May 1 thru August 14, seed with 3 lbs per acre of creeping lovegrass (0.7 lbs/1000 sq ft). For the period November 15 thru February 28, protect site by applying 2 tons per acre of well anchored straw mulch and seed as soon as possible in the spring. For anchoring.

**PLANTING:** Apply 1/2 to 2 tons per acre (70 to 40 lbs/1000 sq ft) of untreated small grain straw immediately after seeding. Anchor mulch immediately after application using mulch anchoring tool or 20 gallons per acre (5 gal/1000 sq ft) of emulsified asphalt on flat areas. On slopes 8 feet or higher, use 340 gallons per acre (8 gal/1000 sq ft) for anchoring.

**REFER TO THE 1994 MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL FOR RATE AND METHOD NOT COVERED.**

**CONSTRUCTION AND MATERIAL SPECIFICATIONS**

1. Topsoil salvaged from the existing site may be used provided that it meets the standards as set forth in these specifications. Typically, the depth of topsoil to be salvaged for a given soil type can be found in the representative soil profile section in the Soil Survey published by USDA-SCS in cooperation with Maryland Agricultural Experiment Station.
2. Topsoil Specifications - Soil to be used as topsoil must meet the following:
  - a. Topsoil shall be a loam, sandy loam, clay loam, silt loam, sandy clay loam, loamy sand. Other soils may be used if recommended by an approved soil scientist and approved by the appropriate approval authority. Regardless, topsoil shall not be a mixture of contrasting textures and shall contain less than 5% by volume of chert, stones, clumps of coarse grass, twigs, sticks, rocks, trash, or other materials larger than 1/2\"/>
3. Where the subsoil is either highly acidic or composed of heavy clay, the graded limestone shall be spread at the rate of 4-8 lbs/acre (200-800 pounds per 1,000 square feet) prior to the placement of topsoil. Lime shall be distributed uniformly over designated areas and worked into the soil in conjunction with tillage operations as described in the following procedures:
  - a. For sites having disturbed areas under 5 acres: Place topsoil (if required) and apply soil amendments as specified in 21.0 Vegetative Stabilization - Section 1 - Vegetative Stabilization Methods and Materials.
  - b. For sites having disturbed areas over 5 acres: On all meeting topsoil specifications, obtain test results including fertilizer and lime amendments required to bring the soil into compliance with the following:
    - i. pH level shall be between 6.0 and 7.6; if the tested soil demonstrates a pH of less than 6.0, soil amendments shall be prescribed to raise the pH to 6.5 or higher.
    - ii. Organic content of topsoil shall be not less than 1.5 percent by weight.
    - iii. Topsoil having a cationic soil content greater than 500 parts per million shall not be used.
    - iv. No soil or seed shall be placed on soil which has been treated with soil sterilants or chemicals used for weed control until sufficient time has elapsed (14 days min.) to permit dissipation of phytotoxic materials.
4. The soil material to be used for the seeding zone is not to be used to amend plants or furnish continuing supplies of moisture and plant nutrients. The original soil to be vegetated contains material toxic to other growth.
5. The soil is so acidic that treatment with limestone is not feasible.
6. For the purpose of these Standards and Specifications, areas having slopes steeper than 2:1 require grade stabilization structures, Earth Dikes, Slope Silt Fence and Sediment Traps and Basins.
7. Grades on the areas to be topsoiled, which have been previously established, shall be maintained, about 2\"/>



REVIEWED FOR HOWARD SCD AND MEETS TECHNICAL REQUIREMENTS

USE - NATURAL RESOURCES CONSERVATION SERVICE DATE 6/8/04

THE DEVELOPMENT PLAN IS TO BE FOR SOIL EROSION AND SEDIMENT CONTROL BY THE HOWARD SOIL CONSERVATION DISTRICT

John K. Robertson 6/8/04 DATE

**ENGINEER'S CERTIFICATE**

"I CERTIFY THAT THIS PLAN FOR SEDIMENT AND EROSION CONTROL REPRESENTS A PRACTICAL AND WORKABLE PLAN BASED ON MY PERSONAL KNOWLEDGE OF THE SITE CONDITIONS AND THAT IT WAS PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE HOWARD SOIL CONSERVATION DISTRICT."

Zacharia Y. Fisch 6/8/04 DATE

SIGNATURE OF ENGINEER ZACHARIA Y. FISCH

**DEVELOPER'S CERTIFICATE**

"I/WE CERTIFY THAT ALL DEVELOPMENT AND CONSTRUCTION WILL BE DONE ACCORDING TO THIS PLAN FOR SEDIMENT AND EROSION CONTROL, AND THAT ALL RESPONSIBLE PERSONNEL INVOLVED IN THE CONSTRUCTION PROJECT WILL HAVE A CERTIFICATE OF ATTENDANCE AT A DEPARTMENT OF THE ENVIRONMENT APPROVED TRAINING PROGRAM FOR THE CONTROL OF SEDIMENT AND EROSION BEFORE BEGINNING THE PROJECT. I ALSO AUTHORIZE PERIODIC ON-SITE INSPECTION BY THE HOWARD SOIL CONSERVATION DISTRICT."

Clifford E. Harrison 6/8/04 DATE

SIGNATURE OF DEVELOPER CLIFFORD E. HARRISON

**SEQUENCE OF CONSTRUCTION**

1. Obtain Grading permit.
2. Notify Howard County Department of Inspections, License and Permits at (410) 318-1880 at least 24 hours before starting any work.
3. Install stabilized construction entrances (Sf and Ssf), (3 day).
4. Rough grade site and begin house and driveway construction. (2 weeks)
5. Complete house and driveway construction and fine grade site and install erosion control matting. (1 week)
6. During grading and after each rainfall, contractor will inspect and provide necessary maintenance to the sediment control measures on this plan.
7. Following initial soil disturbance or any redistributions, permanent or temporary stabilization shall be completed within:
  - A. 7 calendar days for all perimeter sediment control structures, dikes, basins and all slopes greater than 3:1.
  - B. 14 calendar days for all other disturbed areas.
8. Upon stabilization of all disturbed areas and with the permission of the sediment control inspector, remove all sediment control measures and stabilize any remaining disturbed area. (1 week)

**OWNER**

Clifford E. & Betty K. Harrison  
P.O. Box 287  
West Friendship, Maryland 21794

**BUILDER**

Cumberland Development Corp.  
16391 A.E. Mullinix Road  
Woodbine, Maryland 21797  
(301)-554-6325

**GP-04-103**

**SEDIMENT & EROSION CONTROL PLAN**

**HARRISON RESIDENCE**

**BUILDABLE PRESERVATION PARCEL 'A'**

TAX MAP 22, GRID B 3RD ELECTION DISTRICT PARCEL 17 HOWARD COUNTY, MARYLAND

DESIGN BY: PS  
DRAWN BY: BB  
CHECKED BY: ZYF  
SCALE: 1"=50'  
DATE: June 8, 2004  
W.O. No.: 3241  
SHEET No.: 1 OF 1

**FSH Associates**  
Engineers Planners Surveyors  
8318 Forrest Street Ellicott City, MD 21043  
Tel: 410-750-2251 Fax: 410-750-7350  
E-mail: fsh@load.net