

PERMIT NUMBER: B 23003260

DATE ACCEPTED:

# COMMERCIAL BUILDING PERMIT APPLICATION

HOWARD COUNTY DEPARTMENT OF INSPECTIONS, LICENSES, AND PERMITS

3430 COURT HOUSE DRIVE, ELLICOTT CITY, MD 21043 - PHONE: (410) 313-2455 OPTION #1  
www.howardcountymd.gov



## BUILDING SITE ADDRESS REQUIRED

Street Address: 3950 FAN CLUB ROAD		Unit: -
City: GLENOLD	State: MD	Zip Code: 21737
Subdivision/Village/Complex Name:		SDP/WP/BA #: 508 22-013
Lot: 221	Tax Map: 22-013	Grading Permit #: 6300000002

## DESCRIPTION OF WORK REQUIRED

Existing Use: FIELD	Proposed Use: WIRE ELECTRICAL	Estimated Cost: \$ 2,300
Trade Work to Be Completed (Separate Permits Required): <input type="checkbox"/> Mechanical (HVACR) <input checked="" type="checkbox"/> Electrical <input type="checkbox"/> Plumbing <input type="checkbox"/> None		

## PROPERTY OWNER INFORMATION REQUIRED

Owner(s) Name(s) (As it appears on tax records): FRANK GLENOLD FARM (Glennold Sodor Farm)		
Owner's Street Address: FIELD STREET		
City: GLENOLD	State: MARYLAND	Zip Code: 21737
Phone:	Email:	

## TENANT INFORMATION REQUIRED

Business Name:	Contact Name:
Street Address:	
City:	State: MARYLAND
Phone:	Email:

## APPLICANT NAME REQUIRED - INDIVIDUAL WHO SIGNS THIS APPLICATION

Business Name: SUBAMERICA ENERGY	Contact Name: FRANK BUCCERI
Street Address: 190 WILSON DRIVE NE	
City: ATLANTA	State: GEORGIA
Phone: 404 351-7471	Email:

## CONTRACTOR INFORMATION REQUIRED

Business Name: SUBAMERICA ENERGY	License #: 03120774
Licensee's Name:	
Street Address: 190 WILSON DRIVE NE	
City: ATLANTA	State: GEORGIA
Phone: 404 351-7471	Email:

## ARCHITECT/ENGINEER INFORMATION REQUIRED - INDIVIDUAL WHO SIGNED PLANS

Business Name: CONSTRUCTION ENG GROUP	Name:
Street Address: 7651 GAN BARRIE BLVD	
City: MELROSE PARK FL 32935	State: FL
Phone: 352 331-7471	Email:

## BUILDING CHARACTERISTICS (PLEASE SELECT/COMPLETE ALL THAT APPLY)

Utilities: <input checked="" type="checkbox"/> Electric <input type="checkbox"/> Gas	Water Supply: <input checked="" type="checkbox"/> Public <input type="checkbox"/> Private (Well)	Sewage Disposal: <input type="checkbox"/> Public <input type="checkbox"/> Private (Septic)
Heating System: <input type="checkbox"/> Electric <input type="checkbox"/> Natural Gas <input type="checkbox"/> Propane <input type="checkbox"/> Other: NONE	Roadside Tree Project: <input type="checkbox"/> No <input type="checkbox"/> Yes:#	
Sprinkler System: <input type="checkbox"/> NFPA 13 <input type="checkbox"/> NFPA 13R <input checked="" type="checkbox"/> None	Fire Alarm System: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Voice Evac	

## ADDITIONAL COMMERCIAL INFORMATION (PLEASE SELECT/COMPLETE ALL THAT APPLY)

Area of Construction: sq ft	Gross Area: sq ft	Height: ft	# of Stories: 1
Construction Classification(s):		Use Group:	
Was the tenant space previously occupied? <input type="checkbox"/> Yes <input type="checkbox"/> No		Shell Building Permit # (for interior completions):	

## ADDITIONAL MULTI-FAMILY INFORMATION IF APPLICABLE

# of efficiency units (MF):	# of 1 BR (MF):	# of 2 BR (MF):	# of 3 BR (MF):
Energy Method: <input type="checkbox"/> Performance <input type="checkbox"/> UA Alternative <input type="checkbox"/> ERI <input type="checkbox"/> A 90.1		Gross Area: sq ft	Occupiable Area: sq ft

## AGREEMENT/ DISCALIMER REQUIRED

THE UNDERSIGNED HEREBY CERTIFIES AND AGREES AS FOLLOWS: (1) THAT HE/SHE IS AUTHORIZED TO MAKE THIS APPLICATION; (2) THAT THE INFORMATION IS CORRECT; (3) THAT HE/SHE WILL COMPLY WITH ALL REGULATIONS OF HOWARD COUNTY WHICH ARE APPLICABLE THERETO; (4) THAT HE/SHE WILL PERFORM NO WORK ON THE ABOVE REFERENCED PROPERTY NOT SPECIFICALLY DESCRIBED IN THIS APPLICATION; (5) THAT HE/SHE GRANTS COUNTY OFFICIALS THE RIGHT TO ENTER ONTO THIS PROPERTY FOR THE PURPOSE OF INSPECTING THE WORK PERMITTED AND POSTING NOTICES

APPLICANT'S ORIGINAL SIGNATURE: FRANK J. BUCCERI DATE SIGNED: 8/21/23

## FOR OFFICE USE ONLY

CHECKS PAYABLE TO: DIRECTOR OF FINANCE OF HOWARD COUNTY

AGENCIES REQUIRED/APPROVALS:				
<input type="checkbox"/> PR	<input type="checkbox"/> DPZ	<input type="checkbox"/> DED	<input checked="" type="checkbox"/> Health 8/21/23	<input type="checkbox"/> SHA <input type="checkbox"/> CID
SUBMITTAL FEES:	PAYMENT:	ACCEPTED BY: [Signature]		

# NEW PHOTOVOLTAIC SYSTEM

FOR

# TEN OAKS SOLAR

AT

## 3950 TEN OAKS ROAD, GLENELG, MD 21737

DATE:

### AUGUST 4, 2023


### PROJECT INFORMATION

CLIMATE DATA:	
WEATHER DATA LOCATION:	BALTIMORE BLT-WASHINGTON INT'L
HOTTEST 2% ASHRAE DRY BULB AIR TEMP:	31.5 °C
EXTREME COLDEST ASHRAE MIN TEMP:	-13.9 °C
MODULE DATA:	
VENDOR:	QCELLS
MODEL:	Q.PEAK DUO XL-G10.3/BFG
QUANTITY:	5,760
RATED POWER @ STC (P <sub>max</sub> ):	485 W
MAX SYSTEM VOLTAGE:	1500 V
OPEN CIRCUIT VOLTAGE @ STC (V <sub>oc</sub> ):	53.63 V
MAX POWER VOLTAGE @ STC (V <sub>mp</sub> ):	45.63 V
SHORT CIRCUIT CURRENT @ STC (I <sub>sc</sub> ):	11.16 A
MAX POWER CURRENT @ STC (I <sub>mp</sub> ):	10.63 A
MODULE EFFICIENCY:	22.70 %
STRING DATA:	
DESIGN MODULES PER STRING:	24
MODULE V <sub>oc</sub> at T <sub>MIN</sub> :	59.3 V
SOURCE CIRCUIT V <sub>oc</sub> at T <sub>MIN</sub> :	1422 V
MAX SYSTEM VOLTAGE:	1500 V
RACKING DATA:	
VENDOR:	TERRASMART
RACKING TYPE:	FIXED TILT (432 2X13 BLOCKS)
MODULE ORIENTATION:	PORTRAIT (2 HIGH)
RACK POST SPACING PITCH:	29'-8 1/2"
AZIMUTH:	180 °
TILT ANGLE:	25.00
GROUND COVERAGE RATIO (GCR):	0.44
*INVERTER DATA:	
VENDOR:	SUNGROW
MODEL:	SG125HV
QUANTITY:	16
MAX INPUT VOLTAGE:	1500 V
RATED AC ACTIVE OUTPUT POWER:	125 kW
MAX AC APPARENT OUTPUT POWER:	125 kVA
OUTPUT VOLTAGE:	600 V
OUTPUT PHASE:	3Ø
MAX OUTPUT CURRENT:	120 A
INVERTER EFFICIENCY:	98.9 %
SWITCHGEAR DATA:	
VENDOR:	TBD
MODEL:	TBD
DESCRIPTION:	(1) 2500A MCB
RATING:	600V, 3Ø, 4W, NEMA 3R
OVERALL SYSTEM SIZE:	
OVERALL DC OUTPUT POWER	2,794 kW
OVERALL AC OUTPUT POWER	1,999 kVA
OVERALL DC/AC RATIO	1.40

\* ONE INVERTER IS DERATED TO 124KVA


### DRAWING LIST

NUMBER	SHEET NAME
PVE-1.0	COVER SHEET
PVE-1.1	SPECIFICATIONS
PVE-2.0	OVERALL SITE PLAN
PVE-2.1	ENLARGED SITE PLAN
PVE-3.1	PARTIAL PV STRINGING PLAN
PVE-3.2	PARTIAL PV STRINGING PLAN
PVE-3.3	PARTIAL PV STRINGING PLAN
PVE-4.1	MV SINGLE-LINE DIAGRAM
PVE-4.2	PV SINGLE-LINE DIAGRAM
PVE-5.1	SWITCHBOARD AND PANEL SCHEDULES
PVE-5.2	DC SCHEDULES AND CALCULATIONS
PVE-5.3	AC SCHEDULES AND CALCULATIONS
PVE-6.1	ENLARGED PLANS
PVE-6.2	DETAILS
PVE-6.3	SECTIONS & ELEVATIONS
PVE-7.1	SIGNAGE
PVE-8.1	DATA ACQUISITION PLAN
PVE-9.1	PV EQUIPMENT DATA SHEETS




**REGIONAL MAP**

SCALE: N.T.S.



**CITY MAP**

SCALE: N.T.S.



**PROJECT SITE**

SCALE: N.T.S.

REVISION

NO.	DATE	DESCRIPTION
1	08-08-23	ISSUED FOR PERMIT ONLY

2051 EAU GALLE BLVD, SUITE A  
MELBOURNE, FL 32935  
TEL: 321.283.1221  
WWW.CCGENGINEERING.COM

**CONSTRUCTION ENGINEERING GROUP**  
Consulting Engineers

TEN OAKS SOLAR  
NEW PHOTOVOLTAIC SYSTEM  
3950 TEN OAKS ROAD GLENELG, MD 21737  
DRAWING TITLE  
COVER SHEET

ENGINEER OF RECORD



I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 42678, EXPIRATION DATE: 2024-09-12.

DATE: 08-08-23

SCALE: AS NOTED

PROJ. NO.: 230120

DESIGNED BY: JNH

DRAWN BY: JNH

CHECKED BY: DEA

DRAWING NO.: PVE-1.0

RECEIVED

AUG 11 2023

LICENSES & PERMITS DIVISION

Table with 2 columns: SYMBOLS and ELECTRICAL NOTES. SYMBOLS includes symbols for raceway concealed below floor, ground, plan note, fused disconnect switch, non-fused disconnect switch, meter enclosure, inverter/combiner enclosure, electrical panel, pad mounted utility transformer, inverter, fuse, PV sub-array, circuit breaker, PV module, and meter. ELECTRICAL NOTES includes GROUNDING, CONDUCTOR PROTECTION, LABELING AND IDENTIFICATION, DC SYSTEM WIRING, and MISCELLANEOUS sections.

Table with 2 columns: ELECTRICAL NOTES and ABBREVIATIONS. ABBREVIATIONS lists terms like AMPERES, ALTERNATING CURRENT, ABOVE FINISHED GRADE, AMERICAN WIRE GAUGE, CONDUIT, COPPER, DATA ACQUISITION SYSTEM, DISCONNECT, LAMINATING VINYL, MACHINE PRINTED ID LABELS, ELECTRICAL METALLIC TUBING, FLEXIBLE METAL CONDUIT, GROUND, GROUNDING RIGID CONDUIT, JUNCTION, KILOWATT AMPERE INTERRUPTING CAPACITY, KILOWATT AMPERES, KILOWATT SYSTEMS, THOUSANDS OF CIRCULAR MILS, NEUTRAL, NATIONAL ELECTRICAL CODE, NON-FUSED, POLY, PANELBOARD, POLYVINYL CHLORIDE, REVENUE GRADE METER, SOLID NEUTRAL, SPECIFICATION, STAINLESS STEEL, SQUARE, UNDERGROUND, VOLTS, WIRE, WEATHERPROOF, WYE (CONNECTED).

Table with 2 columns: ELECTRICAL NOTES and MEDIUM VOLTAGE NOTES. MEDIUM VOLTAGE NOTES includes sections for GROUNDING, CONDUCTOR PROTECTION, LABELING AND IDENTIFICATION, DC SYSTEM WIRING, and MISCELLANEOUS. It details requirements for grounding connections, conductor protection, labeling, and DC system wiring.

Table with 2 columns: ELECTRICAL NOTES and MEDIUM VOLTAGE NOTES. MEDIUM VOLTAGE NOTES includes sections for GROUNDING, CONDUCTOR PROTECTION, LABELING AND IDENTIFICATION, DC SYSTEM WIRING, and MISCELLANEOUS. It details requirements for grounding connections, conductor protection, labeling, and DC system wiring.

Table with 2 columns: ELECTRICAL NOTES and MEDIUM VOLTAGE NOTES. MEDIUM VOLTAGE NOTES includes sections for GROUNDING, CONDUCTOR PROTECTION, LABELING AND IDENTIFICATION, DC SYSTEM WIRING, and MISCELLANEOUS. It details requirements for grounding connections, conductor protection, labeling, and DC system wiring.

Table with 2 columns: ELECTRICAL NOTES and MEDIUM VOLTAGE NOTES. MEDIUM VOLTAGE NOTES includes sections for GROUNDING, CONDUCTOR PROTECTION, LABELING AND IDENTIFICATION, DC SYSTEM WIRING, and MISCELLANEOUS. It details requirements for grounding connections, conductor protection, labeling, and DC system wiring.

REVISION table with columns for REV#, DATE, and DESCRIPTION. Includes project information: TEN OAKS SOLAR NEW PHOTOVOLTAIC SYSTEM, 3950 TEN OAKS ROAD GLENELG, MD 21737. Includes professional engineer information: DAVID E. HALE, PROFESSIONAL ENGINEER, LICENSE NO. 42678. Includes a RECEIVED stamp dated AUG 11 2023. Includes drawing title: SPECIFICATIONS.

PV SYSTEM SUMMARY											
SYSTEM	INVERTER TYPE	MODULE TYPE	NUMBER OF STRINGS PER INVERTER	MODULES PER STRING	NUMBER OF MODULES	MODULE PEAK POWER	TOTAL DC POWER	MAX INVERTER AC OUTPUT POWER	NUMBER OF INVERTERS	TOTAL AC POWER	DC/AC RATIO
1	SG125HV	Q-PEAK DUO XL-G10.3/BFG	15	24	5,760	485 W	2794 kW	125 kVA	15	1999 kVA	1.40
			15	24					1		
<b>TOTALS</b>			-	-	5,760	-	2.79 MW	-	16	1.999 MVA	1.40



**OVERALL SITE PLAN**

**PLAN NOTES:**

- ALL GATES THAT IMPEDE FIRE DEPARTMENT ACCESS TO A SITE MUST BE EQUIPPED WITH EITHER A KNOX BOX OR A SIREN-OPERATED SYSTEM. REFER TO CIVIL DRAWINGS FOR ADDITIONAL INFORMATION.
- MODULE RACKING SUPPORT STRUCTURE. REFER TO RACKING SHOP DRAWINGS FOR ADDITIONAL RACKING DETAILS. INSTALL MODULES ON RACKING PER RACKING AND MODULE MANUFACTURERS WRITTEN INSTRUCTIONS.
- TYPICAL PV STRING COMBINER. INSTALL VERTICALLY BESIDE ARRAY SUPPORT STRUCTURE ON SUPPORT FRAME. REFER TO MOUNTING DETAILS ON DRAWING PVE-6.3 FOR ADDITIONAL INFORMATION.
- PROPOSED TRENCH LINE FOR U.G. COMBINER DC OUTPUT CIRCUITS BETWEEN COMBINER AND INVERTER. REFER TO FEEDER SCHEDULE ON PVE-5.3.
- TYPICAL PV STRING INVERTER. INSTALL VERTICALLY ON CUSTOM RACKING FRAME. REFER TO MOUNTING DETAILS ON DRAWING PVE-6.3 FOR ADDITIONAL INFORMATION.
- PROPOSED TRENCH LINE FOR U.G. INVERTER AC OUTPUT CIRCUITS BETWEEN INVERTER AND SWITCHBOARD. REFER TO FEEDER SCHEDULE ON PVE-5.3.
- PROPOSED LOCATION OF PAD-MOUNTED AC SWITCHBOARD. REFER TO SINGLE-LINE DIAGRAM ON PVE-4.2 AND ENLARGED PLANS ON SHEET PVE-2.1 AND PVE-6.1 FOR ADDITIONAL INFORMATION.
- PROPOSED LOCATION OF PAD MOUNTED TRANSFORMER. REFER TO SINGLE-LINE DIAGRAM ON PVE-4.1 FOR ADDITIONAL INFORMATION.
- PROPOSED LOCATION OF PAD MOUNTED MV SWITCHGEAR. REFER TO SINGLE-LINE DIAGRAM ON PVE-4.1 FOR ADDITIONAL INFORMATION.
- PROPOSED LOCATION OF BGE PAD-MOUNTED EQUIPMENT.
- PROPOSED ROUTING OF U.G. MV FEEDER TO RISER POLE. REFER TO SINGLE-LINE DIAGRAM ON PVE-4.1 FOR ADDITIONAL INFORMATION.

REVISION	ISSUED FOR PERMIT ONLY
DATE	08-08-23
REV#	1

2651 EAU GAULE BLD. SUITE A  
MEADOWS, MD 21053  
TEL. 301.253.1221  
WWW.CEGENGINEERING.COM

**CONSTRUCTION ENGINEERING GROUP**  
Consulting Engineers

**TEN OAKS SOLAR  
NEW PHOTOVOLTAIC SYSTEM**

3950 TEN OAKS ROAD GLENELG, MD 21137

DRAWING TITLE  
**OVERALL SITE PLAN**

ENGINEER OF RECORD

STATE OF MARYLAND  
DAVID E. ALLEN  
PROFESSIONAL ENGINEER  
NO. 42878

**RECEIVED**  
AUG 11 2023  
LICENSES & PERMITS  
DIVISION

KEY PLAN

SCALE: NTS

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 42878, EXPIRATION DATE 2024-08-12.

DATE: 08-08-23

SCALE: AS NOTED

PROJ. NO.: 230120

DESIGNED BY: JNH

DRAWN BY: JNH

CHECKED BY: DEA

DRAWING NO.: PVE-2.0

UG 291-3  
2 OF 3

### 13 kV EQUIPMENT PADS

FLAT PAD USAGE

FLAT PAD FOR 18 TRANSFORMERS  
1617755 13 kV 18 DEAD-FRONT TRANSFORMERS (25-167 kVA)  
1618209 13 kV 18 DEAD-FRONT TRANSFORMERS (250 kVA)

FLAT PAD FOR 30 TRANSFORMERS  
1623012 13 kV 30 DEAD-FRONT TRANSFORMERS (75-500 kVA) - NOTE: THIS FLAT PAD HAS 8 IN. UNCOULDS TO INCREASE THE SIZE OF THE CABLE ACCESS OPENING. THIS PAD ALSO HAS OIL DRAIN GROOVES AND A DRAIN HOLE FOR OIL RETENTION.

FLAT PAD FOR PAD-MOUNTED CAPACITORS  
1627274 13 kV 30 CAPACITOR ENCLOSURE  
1627274 13 kV 30 DEFERRAL CAPACITOR ENCLOSURE

SPECIAL PAD  
1622968 EQUIPMENT PAD USED TO SUPPORT 800-AMP DEAD-FRONT SWITCHGEAR  
1622968 USED IN CONJUNCTION WITH 1627271 BOX PAD FOR 13 kV AIR-INSULATED DEAD-FRONT SWITCHGEAR

CAT ID	1627274	1622968	1623012	1617755	1618209	1618209
SUBSTANCE	CONCRETE	CONCRETE	PLASTIC FIBERCRETE	CONCRETE	CONCRETE	CONCRETE
WEIGHT	2200#	1000#	200#	40#	80#	3935#
A	82"	60"	75"	42"	48"	100"
B	64"	76"	66"	42"	48"	84"
C	50"	64"	50"	28"	28"	50"-66"
D	4"	60"	18"	12"	10"	18"
E	6"	8"	14"	6"	10"	17"-22"
F	6"	8"	6"	6"	6"	8"
G	6"	5"	6"	4"	4"	8"

SHADED AREA INDICATES ITEMS THAT ARE NO LONGER IN STOCK.

UNDERGROUND CONSTRUCTION STANDARDS

LATEST REVISION: 06/28/19

ADDED CAT ID'S: APPROVAL: *DB*

UG 291-3  
1 OF 3

### 13 kV EQUIPMENT PADS

BOX PAD USAGE

NOTE: ALL FIBERGLASS BOX PADS ARE INSTALLED IN EARTH ONLY.

BOX PAD FOR SWITCHGEAR  
1617771 13 kV 30 DEAD-FRONT AIR-INSULATED SWITCHGEAR - BOTH MANUAL AND AUTOMATIC TYPE

BOX PAD FOR RECLOSERS  
1626259 13 kV 30 WITTLER/UPPER PHASECLOSER (163655)

BOX PAD FOR SECTIONALIZING ENCLOSURE  
1624243 13 kV 10 SECTIONALIZING ENCLOSURE 1624233 FOR THE 300 AMP 3 POSITION 1618161 OR 1618229 13 kV 30 SECTIONALIZING ENCLOSURE 1617785 FOR THE 300 AMP 3 POSITION 1618161, 4 POSITION 1627302 MODULE, OR THE 600 AMP 2 POSITION 1617778 MODULE

BOX PAD FOR MODULES  
1618229, 1624343

BOX PAD FOR MODULE/WS  
1686229, 1686230

CAT ID	1617771	1618229	1624343	1626259	1624243	163655
SUBSTANCE	FIBERGLASS	FIBERGLASS	FIBERGLASS	FIBERGLASS	REINFORCED FIBER	REINFORCED FIBER
WEIGHT	190#	105#	280#	63#	250#	335#
A	30"	36"	78"	23"	74"	73-1/2"
B	85"	41-1/2"	76"	68"	76"	77-1/4"
C	30"	32"	61"	18"	60"	48"
D	79"	32"	67"	61"	62"	61-3/4"
E	38"	48"	88"	29-1/2"	83-1/2"	83-1/2"
F	83"	42-1/2"	86"	74-1/2"	87-1/2"	87-1/2"
G	45"	30"	68"	30"	81-1/2"	81-1/2"
H	100"	55-1/2"	98"	80"	93-1/2"	90-1/2"
J	30"	32"	36"	18"	36"	36-1/4"

UNDERGROUND CONSTRUCTION STANDARDS

LATEST REVISION: 06/28/19

ADDED CAT ID'S: APPROVAL: *DB*

UG 291-3  
3 OF 3

### 13 kV EQUIPMENT PADS

BOX PAD INSTALLATION

200 AMP SIDE

500 AMP SIDE

(1) 200 AMP SEPARABLE CONNECTOR  
(2) FUSE WELL  
(3) AIR-INSULATED SWITCHGEAR  
(4) FAULT INDICATOR  
(5) STATIC GROUND WIRE  
(6) REMOTE FAULT INDICATOR SENSOR  
(7) 6" MIN. COVER OVER CABLES  
(8) 6" MIN. COVER OVER CABLES


GENERAL  
BOX PADS SHALL BE USED AS A SUPPORT FOR ALL PAD-MOUNTED SWITCHGEAR, SECTIONALIZING ENCLOSURES, AND DA RECLOSERS.  
NOTE: WHERE POSSIBLE, PLAN TO HAVE FAULT INDICATOR WINDOWS FACE NEAREST STREET OR ROAD.

INSTALLATION INSTRUCTIONS  
(1) A CRITICAL STEP WHEN INSTALLING THE EQUIPMENT BOX PAD IS TO HAVE IT PERFECTLY LEVEL. IF THE BOX PAD IS NOT LEVEL, THE EQUIPMENT DOORS WILL BE OUT-OF-ALIGNMENT AND WILL NOT OPEN AND CLOSE PROPERLY.  
(2) EXCAVATE FOR THE BOX PAD, OCCASIONALLY CHECKING FOR THE SIDE OF THE BOX PAD BEING INSTALLED. THE EXCAVATION DEPTH MUST ALLOW THE BOX PAD TO EXTEND 4 IN. ABOVE FINAL GRADE.  
(3) THE AREA SURROUNDING THE BOX PAD SHALL BE LEVEL AND CLEAR OF OBSTRUCTIONS. THIS LEVEL AREA SHALL BE 4 IN. BELOW THE TOP OF THE BOX PAD AND SHALL EXTEND A MINIMUM OF 8 FT. FROM THE SIDES WITH DOORS TO PROVIDE FOR STICK OPERATIONS AND 4 FT. ON ALL SIDES THAT HAVE CONTROL OR OPERATING COMPARTMENTS. ON ALL OTHER SIDES, A 2 FT. MINIMUM CLEARANCE IS REQUIRED.  
(4) DIG THE CABLE TRENCHES TO THE EXCAVATION.  
(5) INSTALL THE CABLES. WHEN TERMINATING THE CABLES, LOOP THE CABLES AT THE BOTTOM OF THE BOX PAD EXCAVATED AREA TO PROVIDE CABLE SLACK. BACKFILL THE CABLE TRENCHES AND TAMP AS REQUIRED.  
(6) INSTALL THE BOX PAD. THE PAD MUST NOT REST ON THE CABLES BUT RATHER ON 6 IN. OF COMPACTED EARTH. IF THE PAD IS TO BE INSTALLED ON BACKFILL, THOROUGHLY TAMP THE EARTH IN INDIVIDUALLY COMPACTED LAYERS NOT IN EXCESS OF 8 IN. BEFORE INSTALLING THE PAD. AFTER INSURING THAT THE PAD IS LEVEL, BACKFILL EVENLY AROUND THE OUTSIDE OF THE PAD TO A DEPTH OF 8 IN., ADD 6 IN. OF SELECT BACKFILL OR SAND TO THE INSIDE OF THE BOX PAD BOTTOM. THIS WILL EQUALIZE THE PRESSURE ON THE BOX PAD.  
(7) WHEN INSTALLING GROUND RODS IN BOX PAD OPENINGS, USE EXTREME CAUTION TO AVOID DAMAGING BURIED CABLE. GROUND RODS SHALL BE DRIVEN AT LEAST 7 FT.-8 IN. IN EARTH, SOIL PERMITTING.  
(8) POSITION THE EQUIPMENT EXCISED ON THE BOX PAD AND SHALL ONE 3/4 IN. HOLE THROUGH THE FIBERGLASS BOX PAD FLANGE AT EACH CORNER OF THE PAD. INSTALL HOLD-DOWN CLAMPS WITH 5/8 IN. X 2-3/4 IN. SQUARE HEAD BOLTS AND NUTS (CAT ID 1618151) AND WASHERS (CAT ID 1622020). NOTE: BOLTS, NUTS, AND WASHERS ARE SUPPLIED WITH SWITCHGEAR. ONCE THE EQUIPMENT IS SECURED TO THE BOX PAD, COMPLETE BACKFILLING ON THE OUTSIDE OF THE BOX PAD. HAND TAMP 6 IN. LAYERS ONLY AROUND THE SIDES OF THE BOX PAD UNTIL REACHING FINAL GRADE.  
(9) WHEN TERMINATING CABLES ON THE EQUIPMENT, ALLOW SUFFICIENT SLACK IN THE CONCENTRIC NEUTRAL WIRES TO CONNECT THEM TO THE GROUNDING BUS AND TO PERMIT THE ELBOWS TO BE MOVED FREELY FROM THE MAIN BUSBARS TO THE GROUNDING BUS.  
(10) INSTALL FAULT INDICATORS, INSULATING CAPS OR ELBOW ARRESTERS AS REQUIRED. INSTALL THE FAULT INDICATOR LEADS (ON THE 600 AMP SIDE) NEARLY SO AS NOT TO INTERFERE WITH ELBOW OPERATION. RUN THE LEADS DOWN THE FACE OF THE BEAR BEHIND THE GROUNDING BUS, TAPING EACH SET TOGETHER EVERY 6 IN. WITH PLASTIC TAPE (CAT ID 1628798). USE CABLE TIES (CAT ID 1623036) TO ATTACH THE LEADS TO THE WIRE RETAINING CLIPS PROVIDED ON THE SWITCHGEAR.  
(11) IN AREAS WHERE HEAVY CONSTRUCTION EQUIPMENT COULD BE USED IN THE VICINITY OF THE BOX PAD, INSTALL 2 FT. X 2 FT. X 1/2 IN. STEAKS 3 FT. FROM THE EQUIPMENT AND RUN BRASS-CLAD TAPE (CAT ID 1618151) BETWEEN THEM. THIS PROTECTS THE BOX PAD FROM EXCESSIVE SIDEWALL PRESSURES. AFTER THE WORK IS DONE, REMOVE THE STEAKS AND TAPE.  
(12) BEFORE ENERGIZING OIL-INSULATED SWITCHGEAR, CHECK THAT THE OIL LEVEL IS AT A NORMAL LEVEL. IF THE OIL LEVEL IS FOUND TO BE LOW, CONTACT THE EQUIPMENT MANUFACTURER. IF THE OIL LEVEL IS AT ALL DO NOT ENERGIZE THE GEAR. CONTACT THE EQUIPMENT DIAGNOSTIC AND REPAIR UNIT, RUTHERFORD BUSINESS CENTER.  
(13) MAKE SURE ALL PRETENSION BOLTS ARE IN PLACE, PROPERLY ALIGNED AND SECURED. INSURE THE GEAR IS PROPERLY PADLOCKED BEFORE LEAVING THE JOB.

UNDERGROUND CONSTRUCTION STANDARDS

LATEST REVISION: 06/28/19

ADDED CAT ID'S: APPROVAL: *DB*



- ### PLAN NOTES:
- MODULE RACKING SUPPORT STRUCTURE. REFER TO RACKING SHOP DRAWINGS FOR ADDITIONAL RACKING DETAILS. INSTALL MODULES ON RACKING PER RACKING AND MODULE MANUFACTURERS WRITTEN INSTRUCTIONS.
  - TYPICAL PV STRING COMBINER. INSTALL VERTICALLY BESIDE ARRAY SUPPORT STRUCTURE ON SUPPORT FRAME. REFER TO MOUNTING DETAILS ON DRAWING PVE-6.3 FOR ADDITIONAL INFORMATION. REFER TO SCHEDULE ON PVE-5.2 AND PVE-9.1 FOR DATA SHEETS.
  - PROPOSED TRENCH LINE FOR U.G. COMBINER DC OUTPUT CIRCUITS BETWEEN COMBINERS AND RESPECTIVE INVERTER. REFER TO FEEDER SCHEDULE ON PVE-5.2.
  - TYPICAL PV STRING INVERTER. INSTALL VERTICALLY ON SUPPORT FRAME. REFER TO MOUNTING DETAILS ON DRAWING PVE-6.3 FOR ADDITIONAL INFORMATION. REFER TO SCHEDULE ON PVE-5.3 AND PVE-9.1 FOR DATA SHEETS.
  - PROPOSED TRENCH LINE FOR U.G. INVERTER AC OUTPUT CIRCUITS BETWEEN INVERTER AND SWITCHBOARD. REFER TO FEEDER SCHEDULE ON PVE-5.3.
  - PROPOSED LOCATION OF PAD-MOUNTED AC CONSOLIDATION SWITCHBOARD. REFER TO SINGLE-LINE DIAGRAM ON PVE-4.2 AND PVE-4.3 FOR SWITCHBOARD SCHEDULE.
  - PROPOSED TRENCH LINE FOR U.G. FEEDER FROM AC CONSOLIDATION SWITCHBOARD. REFER TO AC DISTRIBUTION OUTPUT FEEDER SCHEDULE ON PVE-5.2 AND SINGLE-LINE DIAGRAM ON PVE-4.2 FOR ADDITIONAL INFORMATION.
  - PROPOSED U.G. PRIMARY BETWEEN TRANSFORMER AND MV SWITCHGEAR. REFER TO MV SINGLE-LINE DIAGRAM ON PVE-4.1 FOR ADDITIONAL INFORMATION.
  - PROPOSED LOCATION OF MV PAD-MOUNTED SWITCHGEAR. REFER TO MV SINGLE-LINE DIAGRAM ON PVE-4.1 FOR ADDITIONAL INFORMATION.
  - PROPOSED U.G. PRIMARY BETWEEN MV SWITCHGEAR AND UTILITY PAD-MOUNTED RECLOSER. REFER TO MV SINGLE-LINE ON PVE-4.1 FOR ADDITIONAL INFORMATION.
  - PROPOSED PAD-MOUNTED UTILITY EQUIPMENT. REFER TO MV SINGLE-LINE ON PVE-4.1 FOR ADDITIONAL INFORMATION.
  - PROPOSED AUXILIARY EQUIPMENT RACK FOR DAS, POWER CENTER, ETC. REFER TO ENLARGED PLANS ON PVE-6.1 AND ELEVATIONS ON PVE-6.3 FOR ADDITIONAL INFORMATION.

REV#	DATE	ISSUED FOR	PERMIT ONLY
1	08-08-23		

2651 ENI (CALIFORNIA) SUITE A  
MELBOURNE, FL 32935  
WWW.CSGENGINEERS.COM  
TEL: 301.233.1221

**CONSTRUCTION ENGINEERING GROUP**  
Consulting Engineers

TEN OAKS SOLAR  
NEW PHOTOVOLTAIC SYSTEM  
3950 TEN OAKS ROAD GLENELG, MD 21737  
DRAWING TITLE  
ENLARGED SITE PLAN


ENGINEER OF RECORD  
STATE OF MARYLAND  
DAVID E. ALLEN  
PROFESSIONAL ENGINEER  
MARYLAND  
PROFESSIONAL ENGINEER  
NO. 42678

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 42678, EXPIRATION DATE: 2024-08-12.

DATE: 08-08-23  
SCALE: AS NOTED  
PROJ. NO.: 230120  
DESIGNED BY: JNH  
DRAWN BY: JNH  
CHECKED BY: DEA  
DRAWING NO.: PVE-2.1


ENLARGED PLAN  
SCALE 3/16" = 1'-0"

RECEIVED  
AUG 11 2023  
LICENSES & PERMITS DIVISION




**PLAN NOTES:**


1. MODULE RACKING SUPPORT STRUCTURE. REFER TO RACKING SHOP DRAWINGS FOR ADDITIONAL RACKING DETAILS. INSTALL MODULES ON RACKING PER RACKING AND MODULE MANUFACTURERS WRITTEN INSTRUCTIONS.
2. PROPOSED LOCATION OF PV STRING COMBINER AS SCHEDULED ON PVE-5.2. REFER TO DRAWING PVE-6.3 FOR MOUNTING DETAILS.
3. SOURCE CIRCUIT STRING IDENTIFICATION LABEL. FIRST NUMBER INDICATES WHICH INVERTER THE STRING IS CONNECTED TO, THE LAST NUMBER INDICATES THE STRING NUMBER. PROVIDE PERMANENT UV RESISTANT TYPED WIRE LABEL AT BOTH ENDS.
4. SOURCE CIRCUIT STRING OF 24 MODULES PER STRING CONNECTED IN SERIES. REFER TO STRING WIRING DETAIL ON PVE-4.2 FOR ADDITIONAL INFORMATION. NEATLY SECURE STRING INTERCONNECTS AND HOMERUNS TO RACKING STRUCTURE WITH STAINLESS STEEL CABLE CLIPS. ROUTE HOMERUNS TO STRING INVERTER UNDER MODULES AND SECURED TO RACKING STRUCTURE WHERE POSSIBLE. IN SOME CASES THE FACTORY INTERCONNECTS MAY NOT BE LONG ENOUGH TO REACH THE ADJACENT MODULE INTERCONNECT AND FIELD JUMPERS WILL BE REQUIRED. COMPLETE A SINGLE STRING DEMONSTRATING WIRING AND SECURING METHODS FOR OWNER APPROVAL PRIOR TO COMPLETING THE REMAINING STRINGS.
5. PROVIDE 1-1/2" CONDUITS FROM RACKING ROWS TO COMBINER FOR DC STRING HOME RUNS (6 STRINGS MAX PER CONDUIT). ROUTE #6 CU EGC IN EACH RACEWAY AND BOND COMBINER SUPPORT STRUCTURES AND MODULE RACKING STRUCTURES TO FORM A CONTINUOUSLY GROUND SYSTEM. FIELD COORDINATE ACTUAL LOCATIONS AND QUANTITIES AND ADJUST AS NEEDED.



**PARTIAL STRINGING PLAN**



**RECEIVED**  
AUG 11 2023  
LICENSES & PERMITS  
DIVISION



**KEY PLAN**  
SCALE: NTS


REVISION	ISSUED FOR PERMIT ONLY
DATE	08-08-23
REV#	1
260 FAUCALLEN RD, SUITE 400 AUBURN, AL 36830 TEL: 331.233.1271 WWW.CEGENGINEERING.COM	
<b>CONSTRUCTION ENGINEERING GROUP</b> Consulting Engineers	

**TEN OAKS SOLAR  
NEW PHOTOVOLTAIC SYSTEM**  
DRAWING TITLE  
PARTIAL STRINGING PLAN  
3950 TEN OAKS ROAD GLENELG, MD 21737




ENGINEER OF RECORD  
I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 42678, EXPIRATION DATE: 2024-09-12.

DATE:	08-08-23
SCALE:	AS NOTED
PROJ. NO.:	230120
DESIGNED BY:	JNH
DRAWN BY:	JNH
CHECKED BY:	DEA
DRAWING NO.:	PVE-3.1



**PARTIAL STRINGING PLAN**



**RECEIVED**  
AUG 11 2023  
LICENSES & PERMITS  
DIVISION

**PLAN NOTES:**

1. MODULE RACKING SUPPORT STRUCTURE. REFER TO RACKING SHOP DRAWINGS FOR ADDITIONAL RACKING DETAILS. INSTALL MODULES ON RACKING PER RACKING AND MODULE MANUFACTURERS WRITTEN INSTRUCTIONS.
2. SOURCE CIRCUIT STRING IDENTIFICATION LABEL. FIRST NUMBER INDICATES WHICH INVERTER THE STRING IS CONNECTED TO, THE LAST NUMBER INDICATES THE STRING NUMBER. PROVIDE PERMANENT UV RESISTANT TYPED WIRE LABEL AT BOTH ENDS.
3. SOURCE CIRCUIT STRING OF 24 MODULES PER STRING CONNECTED IN SERIES. REFER TO STRING WIRING DETAIL ON PVE-4.2 FOR ADDITIONAL INFORMATION. NEATLY SECURE STRING INTERCONNECTS AND HOMERUNS TO RACKING STRUCTURE WITH STAINLESS STEEL CABLE CLIPS. ROUTE HOMERUNS TO STRING INVERTER UNDER MODULES AND SECURED TO RACKING STRUCTURE WHERE POSSIBLE. IN SOME CASES THE FACTORY INTERCONNECTS MAY NOT BE LONG ENOUGH TO REACH THE ADJACENT MODULE INTERCONNECT AND FIELD JUMPERS WILL BE REQUIRED. COMPLETE A SINGLE STRING DEMONSTRATING WIRING AND SECURING METHODS FOR OWNER APPROVAL PRIOR TO COMPLETING THE REMAINING STRINGS.

261 FAUCALBINE RD, SUITE 4  
MELBOURNE, FL 32955  
TEL: 321.233.1211  
WWW.CEGENGINEERING.COM

**CONSTRUCTION ENGINEERING GROUP**  
Consulting Engineers


**TEN OAKS SOLAR  
NEW PHOTOVOLTAIC SYSTEM**  
3950 TEN OAKS ROAD GLENELG, MD 21737  
DRAWING TITLE  
**PARTIAL STRINGING PLAN**


ENGINEER OF RECORD  
STATE OF MARYLAND  
DAVID E. ALLEN  
PROFESSIONAL ENGINEER  
MARYLAND  
PROFESSIONAL ENGINEER  
NO. 42678

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 42678, EXPIRATION DATE: 2024-09-12.


DATE: 08-08-23  
SCALE: AS NOTED  
PROJ. NO.: 230120  
DESIGNED BY: JNH  
DRAWN BY: JNH  
CHECKED BY: DEA

DRAWING NO.: **PVE-3.2**





**PARTIAL STRINGING PLAN**



**PLAN NOTES:**

1. MODULE RACKING SUPPORT STRUCTURE. REFER TO RACKING SHOP DRAWINGS FOR ADDITIONAL RACKING DETAILS. INSTALL MODULES ON RACKING PER RACKING AND MODULE MANUFACTURERS WRITTEN INSTRUCTIONS.
2. PROPOSED LOCATION OF PV STRING COMBINER AS SCHEDULED ON PVE-5.2. REFER TO DRAWING PVE-6.3 FOR MOUNTING DETAILS.
3. SOURCE CIRCUIT STRING IDENTIFICATION LABEL. FIRST NUMBER INDICATES WHICH INVERTER THE STRING IS CONNECTED TO, THE LAST NUMBER INDICATES THE STRING NUMBER. PROVIDE PERMANENT UV RESISTANT TYPED WIRE LABEL AT BOTH ENDS.
4. SOURCE CIRCUIT STRING OF 24 MODULES PER STRING CONNECTED IN SERIES. REFER TO STRING WIRING DETAIL ON PVE-4.2 FOR ADDITIONAL INFORMATION. NEATLY SECURE STRING INTERCONNECTS AND HOMERUNS TO RACKING STRUCTURE WITH STAINLESS STEEL CABLE CLIPS. ROUTE HOMERUNS TO STRING INVERTER UNDER MODULES AND SECURED TO RACKING STRUCTURE WHERE POSSIBLE. IN SOME CASES THE FACTORY INTERCONNECTS MAY NOT BE LONG ENOUGH TO REACH THE ADJACENT MODULE INTERCONNECT AND FIELD JUMPERS WILL BE REQUIRED. COMPLETE A SINGLE STRING DEMONSTRATING WIRING AND SECURING METHODS FOR OWNER APPROVAL PRIOR TO COMPLETING THE REMAINING STRINGS.
5. PROVIDE 1-1/2" CONDUITS FROM RACKING ROWS TO COMBINER FOR DC STRING HOME RUNS (6 STRINGS MAX PER CONDUIT). ROUTE #6 CU EGC IN EACH RACEWAY AND BOND COMBINER SUPPORT STRUCTURES AND MODULE RACKING STRUCTURES TO FORM A CONTINUOUSLY GROUNDED SYSTEM. FIELD COORDINATE ACTUAL LOCATIONS AND QUANTITIES AND ADJUST AS NEEDED.

REV#	DATE	ISSUED FOR PERMIT ONLY	REVISION
1	08-08-23		

2651 EAST CAULFIELD SUITE A  
ARBOURNE, FL 32005  
TEL: 321.233.1221  
WWW.CEGENGINEERING.COM

**CONSTRUCTION ENGINEERING GROUP**  
Consulting Engineers


**TEN OAKS SOLAR  
NEW PHOTOVOLTAIC SYSTEM  
PARTIAL STRINGING PLAN**

3950 TEN OAKS ROAD GLENELG, MD 21737  
DRAWING TITLE

ENGINEER OF RECORD

STATE OF MARYLAND  
DAVID E. ALLEN  
PROFESSIONAL ENGINEER  
NO. 42578

**RECEIVED**  
AUG 11 2023  
LICENSES & PERMITS  
DIVISION



I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND. LICENSE NO. 42578. EXPIRATION DATE: 2024-09-12.

DATE:	08-08-23
SCALE:	AS NOTED
PROJ. NO.:	230120
DESIGNED BY:	JNH
DRAWN BY:	JNH
CHECKED BY:	DEA
DRAWING NO.:	<b>PVE-3.3</b>

**MV TRANSFORMER SPEC**

SIZE: 2200kVA, THREE PHASE PAD MOUNT TRANSFORMER, UL LISTED, RATED FOR STEP UP SOLAR DUTY OPERATION.

CLASS: 15 KV

FREQUENCY: 60HZ NOMINAL AND SHALL BE TOLERANT OF CONTINUOUS FREQUENCIES BETWEEN 57.0HZ AND 60.5HZ

TEMP RISE: 65 DEGREE C TEMPERATURE RISE, BASED UPON 30 DEG C AVERAGE AND 40 DEGREE C MAX

HIGH VOLTAGE: 13,200V/7,620V

LOW VOLTAGE: 600V/346V

WINDINGS: TRANSFORMERS SHALL HAVE TWO WINDINGS, ONE 2200KVA SECONDARY WINDING AND ONE 2200KVA PRIMARY WINDING.

CONFIGURATION: THE LOW-VOLTAGE WINDING CONFIGURATION SHALL BE 600/346V NOMINAL, GROUNDING WYE, THE HIGH VOLTAGE WINDING CONFIGURATION SHALL BE 13,200V/7,620V GROUNDING WYE, FIVE LEGGED CORE DESIGN.

BIL: HIGH VOLTAGE: 95KV, LOW VOLTAGE 30KV

WINDING: ALUMINUM

IMPEDANCE: NOMINAL 5.5%

TAPS: (2) - 2.5% ABOVE AND BELOW IN HV

CONFIGURATION: DEADFRONT, LOOP FEED, SIX HV BUSHINGS, STAGGERED LV BUSHINGS

PROTECTION: BAYONET EXP. FUSE, PARTIAL RANGE CURRENT LIMITING FUSES, DUAL SENSING EXPULSION FUSES

SWITCHING: LOAD BREAK, 2 POSITION, 600A, 15 KV

ARRESTERS: 8.4KV MCOV ELBOW ARRESTOR, 15KV INTERFACE X 3

COOLING: TYPE KNAN, 125 KV BIL

INSULATING FLUID: ENVIRO-TEMP FR3

SOUND LEVEL: NEMA TR1

ENCLOSURE: 18 INCH DEEP CABINET, TEMP. RISE: 65C, GREEN COLOR WITH TOUCH-UP PAINT

EFFICIENCY: >99% AT 50% LOAD

PRIMARY BUSHINGS: 200 AMP HV BUSHING WELLS X 6, 15 KV CLASS

SECONDARY BUSHINGS: 12 HOLES NEMA SPADE TERMINALS X 4, THREADED STUD

NEUTRAL BUSHING: X0 NEUTRAL (ISOLATED FROM HO)  
HO NEUTRAL, BONDED EXTERNALLY TO TANK MV COMPARTMENT

INSERTS: LOAD BREAK INSERTS X 6



ELECTROSTATIC SHIELD: TRANSFORMERS RATED 2200KVA WITH TWO WINDINGS SHALL INCLUDE ELECTROSTATIC SHIELDING BETWEEN THE LOW AND HIGH VOLTAGE WINDINGS. THE SHIELDING MUST BE GROUNDED EXTERNALLY TO THE LV COMPARTMENT TO THE TRANSFORMER TANK.

TANK GROUNDING: CLAMP-TYPE TANK GROUNDING CONNECTIONS SHALL BE PROVIDED FOR PAD MOUNT DISTRIBUTION TRANSFORMERS IN ACCORDANCE WITH ANSI C57.12.26


MISCELLANEOUS ITEMS: BOLTED COVER, HINGED DOORS, PENTA-HEAD CABINET DOOR BOLTS, LOCKABLE  
LIQUID LEVEL GAUGE  
STANDARD PRESSURE RELIEF VALVE  
THERMOMETER, DIAL TYPE  
VACUUM PRESSURE GAUGE  
1 INCH DRAIN VALVE WITH 3/8 INCH SAMPLER IN EXTERNAL, LOCKABLE ENCLOSURE  
TEMPORAL DECAL WITH SERIAL NUMBER BARCODE AND DESCRIPTION  
WARNING DECALS, DANGER DECALS  
STANDARD NAMEPLATE  
FLAPPER VALVE  
GROUND CONNECTOR PLUG  
NITROGEN BLANKET  
JACKING FACILITIES  
DOOR GASKET  
SHRADER VALVE  
GROUNDING PADS, IEEE STANDARD TWO-HOLE, 3 EACH  
HV AND LV FUSE STEMELS  
FUSE MODEL NUMBERS PRINTED ON NAMEPLATE  
LOCKABLE EXTERNAL GAUGE ENCLOSURE

FACTORY TESTING: IEEE, RESISTANCE, TURNS RATIO, POLARITY, PHASING, EXCITATION, IMPEDANCE, POTENTIAL, LEAK TEST

PV SYSTEM SUMMARY											
SYSTEM	INVERTER TYPE	MODULE TYPE	NUMBER OF STRINGS PER INVERTER	MODULES PER STRING	NUMBER OF MODULES	MODULE PEAK POWER	TOTAL DC POWER	MAX INVERTER AC OUTPUT POWER	NUMBER OF INVERTERS	TOTAL AC POWER	DC/AC RATIO
1	SG125HV	Q.PEAK DUO XL-G10.3/BFG	15	24	5,760	485 W	2794 kW	125 kVA	15	1999 kVA	1.40
TOTALS					5,760		2.79 MW		16	1.999 MVA	1.40



**2 TRANSFORMER DETAIL**  
SCALE: N.T.S.



**SWGR**

MV SWITCHGEAR  
15K, 3Ø, 4W,  
600A, 95KV BIL, 40KA ASYM  
25KA SYM, NEMA 3R  
BGE ID #1110

MV SWITCHGEAR SHALL BE PROCURED AND INSTALLED BY CUSTOMER


- NOTES FOR MV SWITCHGEAR:
- CUSTOMER SHALL SUPPLY LOCKS FOR ALL INNER AND OUTER SECTION DOORS, EXCLUDING BGE METERING BAY, ALL KEYS ALIKE WITH A DOOR KEY PROVIDED TO BGE. THE DOOR KEY WILL BE STORED IN A LOCKBOX SUPPLIED BY BGE.
  - GROUND CONNECTIONS TO THE MAIN GROUND BUSS SHALL BE MADE AT EACH OF THE SWITCHGEAR GROUNDING SYSTEMS WITH NEMA STANDARD TWO BOLT COMPRESSION TYPE CONNECTORS.
  - TELECOMMUNICATIONS LINE TO BE PROVIDED BY CUSTOMER, WITH CONDUIT INSTALLED TO BGE METERING CABINET.
  - METERING CABINET PROVIDED BY BGE TYPICALLY MOUNTED ON THE BACK SIDE OF SWITCHGEAR, DIRECTLY BEHIND REAR OF METERING BAY.
  - INTERNAL 120VAC POWER SOURCE NEEDED TO SUPPLY SWITCHGEAR HEATERS IN BAYS 1, 2, 3, AND 4.

BGE CUSTOMER NOTES:




- CUSTOMER TO WORK WITH BGE TO INSTALL DUCT AND ALL EQUIPMENT PADS PRIOR TO START OF CONSTRUCTION.
- CUSTOMER SHOULD REFER TO BGE'S "NATURAL GAS & ELECTRIC GUIDE" ONLINE @BGE.COM FOR ALL EQUIPMENT PAD AND DUCT INSTALLATION QUESTIONS.
- CUSTOMER TO REFER TO BGE'S METER MANUAL ONLINE FOR ANY METER ENCLOSURE QUESTIONS.
- CUSTOMER REQUIRED TO CONSULT BGE'S METER INSPECTOR JOSEPH BOSSE (410-470-6974) BEFORE FINALIZING ANY METERING INSTALLATION.
- CUSTOMER REQUIRED TO FURNISH AND INSTALL A MINIMUM OF 2"-6" SCH. 40 PVC DUCTS WITH PULL STRINGS BETWEEN THE RISER POLE AND THE SWITCH CABINET AND 1"-6" BETWEEN THE SWITCH CABINET AND THE RECLOSER AND BETWEEN THE RECLOSER AND THE CUSTOMER SWITCHGEAR.
- MINIMUM COVERAGE FOR DUCTS SHALL BE 36".
- ALL DUCT RUNS ARE LIMITED TO A 180° RADIUS WITH A MAXIMUM OF (2) PREFAB 90° BENDS.
- ANY BGE EQUIPMENT PLACED WITHIN 8 FEET OF DRIVABLE SURFACE WILL REQUIRE THE INSTALLATION OF BOLLARDS.

**T-1**


2200kVA AT 65 DEG C MAX  
600/346V UP TO 13,200/7,620V  
3Ø, 4W, 5.75%  
Yg GRID SIDE,  
Yg INVERTER SIDE  
X/R=7.25



(3) 1C UNDERGROUND #1/0 AL, 15KV MV105 CABLES, 133% EPR, WITH 1/3 CONCENTRIC NEUTRAL, WITH (1) #6 CU GROUND IN 6" SCHEDULE 80 PVC.



**1 MV SINGLE LINE DIAGRAM**  
SCALE: NTS



**RECEIVED**  
AUG 11 2023  
LICENSES & PERMITS DIVISION

CONSTRUCTION ENGINEERING GROUP  
260 EAU CLAIRE BLVD, SUITE 4 MEDFORD, NJ 08055  
TEL: 321.233.1271 WWW.CEENGINEERING.COM

TEN OAKS SOLAR  
NEW PHOTOVOLTAIC SYSTEM  
3950 TEN OAKS ROAD GLENELG, MD 21737  
DRAWING TITLE  
MV SINGLE-LINE DIAGRAM

ENGINEER OF RECORD  
STATE OF MARYLAND  
DAVID E. JELLEN  
PROFESSIONAL ENGINEER  
MARYLAND  
PROFESSIONAL ENGINEER NO. 42678

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. 42678, EXPIRATION DATE: 2024-09-12.

DATE: 08-08-23  
SCALE: AS NOTED  
PROJ. NO.: 230120  
DESIGNED BY: JNH  
DRAWN BY: JNH  
CHECKED BY: DEA  
DRAWING NO.: PVE-4.1