

10-13

PERMIT

P 23804
A 22400

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

144 to Millers Mill
Approved
10-13-76

DISTRICT 4th

DATE 8/30/76

Brittingham installed

INDEXED

H. K. Turner

IS PERMITTED TO INSTALL ALTER

ADDRESS Rt. 1, Box 265-B Mt. Airy, Md. 21771

PHONE 253-9489

A SEWAGE DISPOSAL SYSTEM LOCATED AT

SUBDIVISION ROAD Bushy Park Rd. LOT 5

PROPERTY OWNER H. K. Turner

ADDRESS

SPECIFICATIONS 8 Bedrooms

DRAIN FIELD DEPTH FEET, BOTTOM AREA SQ. FT.

SEEPAGE PITS ABSORBENT SIDE-WALL AREA SQ. FT.

SEPTIC TANK CAPACITY 1000 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 80%.

OTHER DRY WELL-to have 140 sq. ft. effective absorbent sidewall area per bedroom below first 5 ft. of original soil. Inlet can come in at 4 or 5 ft. and maximum depth 12 ft. Location per certified plat- 10 ft. off left property line and 265 ft. from rear point of lot. (See plat if necessary) when facing lot from road. Cleanouts needed every 50 ft. from tank to Dry Well area on house sewer.

NOTE: ALL PIPE FROM HOUSE TO DISPOSAL AREA MUST BE CAST IRON.
~~PERMIT VOID AFTER THREE YEARS.~~

NOTE: INSTALL STAND PIPE ON SEPTIC TANK. STAND PIPES MUST BE 6 INCHES IN DIAMETER. CAST IRON, CONCRETE OR TERRA COTTA ACCEPTED.

PLANS APPROVED BY Charles B. Steaker DATE 4/23/76

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

22400

