

10/5/73 PM

app - 10/3/73
Sewer

PERMIT

SEWAGE DISPOSAL SYSTEM

MARYLAND STATE DEPARTMENT OF HEALTH

HOWARD COUNTY

ELLICOTT CITY

DISTRICT 4

DATE 9/19/73

19003

17997

INDEXED

Herman Sirk IS PERMITTED TO INSTALL ALTER

ADDRESS Jennings Chapel Road, Woodbine, Md. PHONE 489-4724

A SEWAGE DISPOSAL SYSTEM LOCATED AT _____

SUBDIVISION _____ ROAD 163.24 Carr's Mill (see application for better directions) LOT Parcel 3

PROPERTY OWNER Peter Janka 442-2673

ADDRESS _____

SPECIFICATIONS - 4 bedrooms

DRAIN FIELD _____ DEPTH _____ FEET, BOTTOM AREA _____ SQ. FT.

SEEPAGE PITS _____ ABSORBENT SIDE-WALL AREA _____ SQ. FT.

SEPTIC TANK CAPACITY 1,000 GALLONS

FOR GARBAGE GRINDER, INCREASE DISPOSAL AREA 22% & TANK CAPACITY 50%.

OTHER System to have 260 ± sq. ft. effective absorbent sidewall area per bedroom

below inlet. Inlet to be 4 ft. below original grade and maximum depth 12 ft. (if now trench one (1) side of trench counted for absorbent sidewall area.) Two (2) dry wells or equivalent. Location (general area) 129 ft. from front property line and 35 ft. in from left side when facing lot from road. IF TRENCH USED TWO INSPECTIONS WILL BE NECESSARY.

NOTE: ALL PIPE FROM HOUSE TO SEPTIC TANK AND DRY WELL MUST BE CAST IRON.

PERMIT VOID AFTER THREE YEARS.

NOTE: INSTALL STAND PIPE ON SEPTIC TANK AND DRY WELL.

PLANS APPROVED BY C. Streaker & P. Wine DATE 9/3/73

FILL SEPTIC TANK AND DISTRIBUTION BOX WITH WATER BEFORE CALLING FOR AN INSPECTION. COVER NO WORK UNTIL INSPECTED AND APPROVED.

NEITHER THE HOWARD COUNTY COMMISSIONERS NOR THE HEALTH DEPARTMENT IS RESPONSIBLE FOR THE SUCCESSFUL OPERATION OF ANY SYSTEM.

BLDG. PERMIT SIGNED AND RETURNED 5/13/82

Serial # 11578
Pre-Build - Shop - Storage

BLDG. PERMIT SIGNED AND RETURNED 10/17/83

Serial No. 55907

Inground Pool

A 17997

DATE SYSTEM APPROVED _____

